




ODISHA POWER TRANSMISSION CORPORATION LTD

TECHNICAL SPECIFICATION

VOLUME-II (PART-I)

CONTENTS OF THE TECHNICAL BIDDING DOCUMENTS (VOL-II)

CHAPTER No	DESCRIPTION	PAGES
E1	GENERAL CLAUSES	1-13
E2	GENERAL TECHNICAL CLAUSES FOR DESIGN	1-34
E3	SYSTEM DATA	1-2
E4	GENERAL METEROLOGICAL DATA	1-2
E5	DESIGN CLAUSES FOR SUB STATION	1-8
E6	CIVIL WORKS	'1-84
E7	SWITCHYARD STRUCTURE	1-9
E8	DRAWING,TEST CERTIFICATE,O&M MANUALS	1-16
E9	ELECTRICAL EQUIPMENT INSTALLATION & COMMISSIONING	1-12
E10	GENERAL EQUIPMENT & SUBSTATION ACCESSORIES	1-25
E11	CIRCUIT BREAKER	1-55
E12	CURRENT TRANSFORMER	1-37
E13	ISOLATORS	1-16
E14	STATION TRANSFORMER	1-18
E15	SURGE ARRESTER	1-21
E16	IVT,CVT	1-29
E17	BATTERY & BATTERY CHARGER	1-30
E18	PLCC	1-35
E19	DISTRIBUTION BOARD	1-25
E20	CONDUCTOR,EARTH WIRE,INSULATORS,HARDWARES, CLAMPS & CONNECTORS	1-78
E21	CONTROL & PROTECTION PANEL	'1-98
E21A	Technical Spec for Sub station Automation (control & Protection) & Out door AC Kiosk	'1-98
E22	AIR CONDITIONER	1-3
E23	CONTROL &POWER & COAXIAL CABLES	1-30
E24	SUB STATION LIGHTING	1-10
E25	TESTING INSTRUMENTS &MAINTENANCE KITS	1-10
E26	TRANSMISSION LINES	1-91
E27	OPGW CABLE & ITS SYSTEM	'1-39
E28	250 KVA DG SET	'1-14
E29	SHUNT REACTOR-NGR-SA	'1-51
E30	FIRE FIGHTING SYSTEM	01/01/72



ODISHA POWER TRANSMISSION CORPORATION LIMITED

**TECHNICAL SPECIFICATION
VOLUME-II (PART-I)**

GENERAL
GENERAL CLAUSES
TABLE OF CONTENTS

1.4 Limit of contract.....	4
2.GENERAL PARTICULARS OF SYSTEM.....	5
System description	5
Substation description:.....	5
Layout arrangement	5
Meteorological data.....	5
Soil data.....	6
Completeness and accuracy of information.....	6
3.DRAWINGS ATTACHED WITH TENDER DOCUMENT	6
4.GUARANTEES TECHNICAL PARTICULARS	6
5.COMPLIANCE WITH SPECIFICATION.....	6
6.TEST AND MAINTENANCE EQUIPMENT	7
7.SPARES.....	7
7.1 General.....	7
7.2 Mandatory spares.....	7
7.3 Optional spares (shall not be considered for evaluation purpose).	7
8.0 TRAINING	8
8.1 Hardware maintenance.....	8
8.2 Operator familiarisation	8

8.3 Software management.....	8
II.A) Installation and commissioning techniques	9
II.B) Proposals for training and manning	9
9.0 ERECTION AT SITE AND ACCOMMODATION.....	10
10.0 SITE CONSTRUCTION SUPPLIES.....	10
11.0 SUPERVISION AND CHECKING OF WORK ON SITE.....	10
12.0 RESPONSIBILITY FOR THE RUNNING OF PLANT BY CONTRACTOR.....	11
13.0 COMPLIANCE WITH REGULATIONS	11
14.0 MAINTENANCE AND CLEARING OF SITE	12
15.0 INSURANCE	12
15.1 General	12
15.2 Workmen's Compensation Insurance	12
15.3 Comprehensive auto mobile insurance	12
15.4 Comprehensive General Liability Insurance.....	13
16.0 PROTECTION OF MONUMENTS AND REFERENCE POINTS	13
17.0 WORK AND SAFETY REGULATIONS	13
18.0 FOREIGN PERSONNEL.....	15

1. GENERAL CONDITIONS

1.1 Responsibility of the Contractor

The Contractor shall also be responsible for the complete design and engineering, overall co-ordination with internal and external agencies, project management, training of Employer's manpower, loading, unloading, storage at site, inventory management at site during construction, dismantling, re-erection of installations as per Engg Incharge advice, handling, moving to final destination, obtaining statutory authority's clearance for successful erection, and testing and commissioning of the substation.

1.2 Specific exclusions:

The following items of work are specifically excluded from the Contractor's scope of work unless otherwise specifically brought out..

I. Substation site selection

II. Land acquisition

1.3 Interfacial point for line termination at substation

The line Contractor shall terminate the transmission line along with insulator hardware and other essential fittings at the substation gantry. The substation Contractor shall provide necessary anchoring plates in co-ordination with the transmission line contractor. The substation Contractor shall be responsible for providing the necessary electrical interconnection from the line conductor to the substation.

1.4 Limit of contract

The scope of work shall also include all work incidental for successful operation and commissioning and handing over of works whether specifically mentioned or not. In general works are to be carried out by the Contractor in accordance with stipulations in Conditions of Contract.

1.5 Quantity variation

The Employer reserves the right to order and delete such works which may be necessary for him within the quantity variation option laid down in the conditions of the contract. This shall include but not be limited to: the manufacture, supply, testing, and delivery to site, erection and commissioning as may be required in accordance with the Conditions of Contract at the prices stated in the Schedules.

The Employer shall be at liberty to order from the Contractor such quantities of the apparatus at any time before the expiration of the maintenance period of the scope of work, provided that such quantities do not exceed the limitation of the Contract Value as defined in the Conditions of Contract. Each separate order for Work at the Option of the Employer shall constitute a section for the purpose of payment and taking over.

The Employer shall also be at liberty to delete from the Contractor such quantities of the apparatus at any time before commencement of supply of works under the detailed scope of work.

1.6 Supply of non specified equipment/service during execution of contract.

The Employer may require the Contractor to supply and install a number of items such as testing and measuring instruments, vehicles, repairing of existing equipment, removal and refurbishment of plant/equipment from one place to another etc., which in the opinion of the Engg Incharge are to the interest of the project execution. These items and services shall not be limited to proprietary goods provided for the project.

Such supplies and services shall be reimbursed against supply and service invoices for the materials or services actually supplied from the manufacturer or supplier of these items. The bidder shall quote on cost for these items for the earmarked funds in appropriate schedules which shall be considered in bid prices. However these costs shall be payable to the Contractor on pro rata basis for the actual amount spent for procurement and availing of the services.

For such items of supply the Contractor shall follow the fair principle of contracting procedure to the satisfaction of Engg Incharge.

2. GENERAL PARTICULARS OF SYSTEM

System description

The following are the general particulars governing the design and working of the complete system of which the Contract Works will eventually form a part:

Electrical energy is generated at a number of thermal and hydro power plants generally located in the North, Central and Southern areas of Orissa State. The system is three phase, 50Hz and power is transmitted at 400kV, 220kV and 132kV to the distribution system, via grid substations, which operate at 33kV, 11kV and 400V. The 400kV and 220kV networks tie into the OPTCL's 400kV and 220kV grid systems operated by OPTCL. The proposed works will increase the interconnection of, and will thus reinforce the 400kV and 220kV networks within Orissa State. The detailed technical parameters of the system are given in the schedules.

Substation description:

OPTCL has adopted the philosophy of installing open terminal air insulated substations. The busbars for 400 KV rigid type and for 220 KV flexible strain type depending upon the choice of the designer considering the overall suitability and economy of the substation to be installed.

Layout arrangement

The Contractor shall study the details of layout arrangements already indicated in the schedules details for the existing substations. The bay width and height of the conductors for these substations shall be achieved by the Contractor in case of extension substations. However the Contractor shall finalise the layout arrangements in case of new substations in line with this Specification with the approval of the Engg Incharge, which shall be meeting at least the basic minimum electrical clearances as specified in the schedules.

Location and site description

Details of the sub-substation locations, their approach, geography and topography has been provided to the extent possible. The Bidder shall make necessary visit to the substation sites and fully appraise himself before bidding. Deviations on account of inadequate data for substation works shall not be acceptable and the Bid shall not be considered for evaluation in such cases.

Meteorological data

Appropriate meteorological data is given in the schedules.

Soil data

Detailed soil investigations in respect of various substations have not been made. However the general characteristics of the soil are given in the schedules. The Contractor shall investigate the properties of the substations and measure the soil resistivity as part of the scope of work.

Completeness and accuracy of information

The Contractor shall note that the information provided above and in the relevant schedules may not be complete or fully accurate at the time of bidding. For his own interest the Contractor is advised to make site visits and fully satisfy himself regarding site conditions in all respects, and shall be fully responsible for the complete design and engineering of the substations.

3. DRAWINGS ATTACHED WITH TENDER DOCUMENT

The various drawings and schedules provided are a part of the specification and for information purposes only. These are not necessarily binding on the part of the Contractor. Bids shall be prepared by the Bidder based on information provided in the drawings and schedules and that gathered by the Bidder himself.

4. GUARANTEES TECHNICAL PARTICULARS

The Contract Works shall comply with the guaranteed technical particulars specified or quoted in the bid. All plant and apparatus supplied under this Contract shall be to the approval of the Engg Incharge .

All plant and equipment supplied under this contract must have been type tested, have been in manufacture and satisfactory service at identical ratings for at least two years. The bidder shall furnish in his bid the necessary supporting data in specified formats for consideration during bid evaluation. If during evaluation non compliance is identified the successful Contractor shall be bound to supply the equipment from manufacturers complying with the stipulated requirements / OPTCL approval renders.

The Contractor shall be responsible for any discrepancies, errors or omissions in the particulars and guarantees.

The Bidder for his own interest, shall establish the technical responsiveness of his bid, shall provide all data in appropriate technical data sheets, general/ technical information, literature, and pamphlets etc. along with the bid.

5. COMPLIANCE WITH SPECIFICATION

All apparatus should comply with this Specification. Any departures from the requirements of this Specification shall be stated in the relevant Bid Proposal Schedules and will be considered during Bid evaluation. Unless brought out clearly in the technical schedules, it will be presumed that the equipment is deemed to comply with the technical specification.

In the event of there being any inconsistency between the provisions of the conditions of contract and the provisions of this Specification in respect of commercial requirements, the provisions of the conditions of contract shall take precedence for commercial matters and the provisions of this Specification shall take precedence in respect of technical matters.

In case of inconsistency between technical specification & bid proposal sheet, quantities of various items as specified in the bid proposal sheet shall be considered for quoting however the work shall be executed as specified in the technical specification. Only brief description is given in the BPS & the work shall be executed in line with the requirement given in the TS.

The manufacturer and places of manufacture, testing and inspection of the various portions of the Contract Works shall be stated in the relevant Bid Proposal Schedules.

6. TEST AND MAINTENANCE EQUIPMENT

The Contractor shall supply the type and quantity of test and maintenance equipment specified in the Schedules as part of the contract works.

7. SPARES

7.1 General

The Contractor shall provide the mandatory spares detailed in the Schedules. Provide a list of recommended spare parts (optional spares) together with their individual prices, but that will not be considered for evaluation. The Employer may order all or any of the Optional spare parts listed at the time of contract award . Mandatory spares shall be supplied as part of the Works under this

specification. Additional spares(Mandatory) may be ordered at any time during the contract at the rates stated in the Price Schedule.

7.2 Mandatory spares

The Employer has indicated the requirement of mandatory spares as a percentage of the population of main equipment together with proposed storage locations. The quantities shall be determined by the Contractor and indicated in the relevant Bid Price Schedules. These quantities shall be considered for evaluation of the bids.

7.3 Optional spares (shall not be considered for evaluation purpose).

The Contractor may recommend a list of optional spare parts together with the quantity and usage rates for their equipment in the relevant Bid Proposal Schedule. The Engg Incharge shall assess their requirement and place orders.

The spares shall include consumable items sufficient for a plant operational period of five years after commissioning, as well as essential replacement parts to cover the event of a break-down which would affect the availability or safety of the plant. Spares shall be available during the life of the equipment and the Contractor shall give 12 months notice of his, or any sub-contractor's, intention to cease manufacture of any component used in the equipment.

The Contractor shall ensure that sufficient spare parts and consumable items are available for his own use during commissioning of the plant. Spares ordered by the Employer shall not be used by the Contractor without the written consent of the Engg Incharge and any spares so used by the Contractor during the commissioning of the plant shall be replaced by the Contractor at the Contractor's expense.

Any spare apparatus, parts and tools shall be subject to the same specification, tests and conditions as similar material supplied under the Scope of Works of the Contract. They shall be strictly interchangeable and suitable for use in place of the corresponding parts supplied with the plant and must be suitably marked and numbered for identification and prepared for storage by greasing or painting to prevent deterioration.

All spare apparatus or materials containing electrical insulation shall be packed and delivered in cases suitable for storing such parts or material over a period of years without deterioration. Such cases shall have affixed to both the underside and topside of the lid a list detailing its contents. The case will remain the property of the Employer.

8.0 TRAINING

The Contractor will be required to provide suitable training for selected staff both on site and at the Contractor's place of work. Details of the training considered appropriate shall be stated clearly, at the bidding stage, based on the number of trainees specified. The cost of training including all course fees shall be included.

The areas in which it is considered training should be provided, and duration of the training courses, are given in this section. Alternative arrangements, where considered appropriate, should be suggested.

Four categories of training are considered appropriate namely :

- I. Hardware maintenance.
- II. Operator familiarisation.
- III. Software management.
- IV. Installation and commissioning techniques.

8.1 Hardware maintenance

Courses for hardware maintenance shall identify techniques for preventative physical maintenance and for identification, isolation and replacement of faulty components. This course shall take place before equipment is delivered to site.

An essential part of the hardware maintenance course shall include highlighting the philosophy of computer based preventive maintenance and identification of the various diagnostic/interrogation facilities available. The Contractor shall supply adequate documented instructions to enable a detailed interrogation and analysis process to be carried out using the diagnostic software facilities. All items of hardware to be supplied shall be covered by the course.

8.2 Operator familiarisation

This course is intended to familiarise the operators with the system and its use in operating and controlling the PLCC network. The course shall ensure that the control room staff are completely familiar with all operational aspects of the equipment. The means of obtaining special data, report logs and all other facilities which would enable the operators to be fully conversant with the system, shall also be incorporated.

It is envisaged that it will be necessary for the Contractor to run operator familiarisation courses each of approximately one week in duration at site for the training of the Employer's staff.

8.3 Software management

This course shall comprise two main areas and shall take place at the Contractor's works before equipment is delivered to site .

I). A FORMAL COURSE ON THE SOFTWARE FOR EPAX ETC. DETAILING THE VARIOUS MODULES USED AND THEIR INTERACTION.

II). A PRACTICAL COURSE ON EDITING THE DATABASE (TO INCORPORATE EXTENSIONS TO THE POWER NETWORKS, INCLUSION OF ADDITIONAL ANALOGUE/DIGITAL SIGNALS FROM EXISTING EQUIPMENT, ETC.) AND GENERATING NEW LOGS, ALPHANUMERIC DISPLAYS, ETC.

It is envisaged that the software management courses shall extend for a period of approximately six weeks.

II.A) Installation and commissioning techniques

The Employer's staff will be present during the installation and commissioning period and it is essential that they be fully involved in any on-site corrections or modifications to hardware and software equipment.

It is envisaged that it will be necessary for the Contractor to run installation and commissioning techniques courses each of approximately one week in duration at site for the training of the Employer's staff.

II.B) Proposals for training and manning

For each course recommended the following information shall be provided:

- I. Course name and identification.
- II. Short description of the curriculum.
- III. Level of competency required for each course.
- IV. Date and duration.
- V. Maximum number of staff that can attend.

VI. Location.

VII. Other important information.

The times at which the various training courses will take place shall be stated, and fully documented notes shall be available to the Employer not later than two months before the commencement of the course.

All training course notes and documentation shall be in the English language.

An estimate of the total number of the Employer's staff required to run, operate and service the works covered by this Specification shall be given if this is different to the numbers specified.

The prices of the training courses shall be detailed in full such that additions or deletions to personnel or courses can be calculated by the Employer without necessarily having to contact the Contractor. This is particularly important for the 'Software management' courses where prices for formal course days and practical course days shall be individually detailed.

9.0 ERECTION AT SITE AND ACCOMMODATION

The Contractor shall provide, at his own cost and expense, all labour, plant and material necessary for unloading and erection at the Site and shall be entirely responsible for its efficient and correct operation.

The Contractor shall be responsible for arranging and providing all living accommodation services and amenities required by his employees. He shall also provide suitable office accommodation at each substation site for the sole use by the Engg Incharge (Divisional Engr.) **for new substations only**.

10.0 SITE CONSTRUCTION SUPPLIES

The Contractor shall provide at his own cost and expense, any site supplies of electrical energy which he may require for supplying power for heavy erection plant, welding plant or other tools and lighting and testing purposes.

All wiring for such tackle and for lighting from the point of supply shall be provided by the Contractor and all such installations shall comply with all appropriate statutory regulations to which the Employer is subject.

Wiring shall be of the best quality double insulated flexible cable, suitably fixed, protected and maintained. All necessary precautions shall be taken to ensure the safety of every person employed or working on the Site and this shall include routine inspection of all temporary installations and portable equipment.

The Engg Incharge or his authorised representative may require the disconnection or alteration of any parts which he may consider dangerous.

As soon as any part or the whole of the Contractor's installation is no longer required for the carrying out of the works, the Contractor shall disconnect and remove the same to the satisfaction of the Engg Incharge or his authorised representative.

The contractor shall be responsible for arranging construction water at his own cost.

How ever in case water is available at any substation site, Contractor may request Engg Incharge for availing water at one point, which shall be charged to the contractor at prevailing rates for supply of water by Govt. Dept. / Municipal Authorities.

In no case the work shall suffer on account of the Employer not making available the supply of water and electricity for construction purposes.

11 .0 SUPERVISION AND CHECKING OF WORK ON SITE

All work on site included in the Contract scope of works shall be supervised by a sufficient number of qualified representatives of the Contractor.

Before putting any plant or apparatus into operation the Contractor shall satisfy himself as to the correctness of all connections between the plant and apparatus supplied under this and other contracts. The Contractor shall advise the Engg Incharge in writing, giving the period of notice as specified in the General Conditions of Contract, when the plant or apparatus is ready for inspection or energisation.

12 .0 RESPONSIBILITY FOR THE RUNNING OF PLANT BY CONTRACTOR

Until each Section of the Contract Works has been taken over or deemed to have been taken over under the Conditions of Contract, the Contractor shall be entirely responsible for the Contract Works, whether under construction, during tests, or in use for the Employer's service.

The Contractor shall instruct the Employer's operating staff in the recommended method of operation of the plant supplied. Such instruction shall commence prior to the commissioning of the plant and shall be followed by practical instruction for a period of up to one month after the plant is taken over by the Employer. During this one month period the Contractor shall provide an engineer, on each site that is taken over, to assist with operation of the plant and to provide on-site training of the Employer's operating staff. The training schedule and programme for each substation shall be submitted to the Engg Incharge for approval, three months prior to the substation's planned completion date.

If the Employer shall so require, the Contractor shall provide the services of a skilled engineer acquainted with the running of the plant for any period required by the Employer between commencing of use of any portion of the plant (whether taken over or not) and the expiry of the period of maintenance, the wages for such services being paid by the Employer to the Contractor, except in respect of the carrying out of any work already covered by the Contractor's obligations under this Contract.

When the Contractor ceases to be obliged to maintain a supervising engineer on the Site under the foregoing provisions of this clause, the Contractor shall, until the expiration of the period of maintenance, make such arrangements as to ensure the attendance on site within 24 hours of being called upon by the Engg Incharge of a competent supervising engineer for the purpose of carrying out any work of maintenance or repair for which the Contractor shall be liable. During such part or parts of the said period as the Engg Incharge shall deem it necessary the said representative shall be continuously available on the Site.

Any work which may be necessary for the Contractor to carry out in pursuance of his obligations under the Conditions of Contract shall be carried out with the minimum of interference to the normal operation of the substation. Work on the Site shall be carried out at such time and during such hours as the Engg Incharge may require.

13 .0 COMPLIANCE WITH REGULATIONS

All apparatus and material supplied, and all work carried out shall comply in all respects with such of the requirements of all Regulations and Acts in force in the country of the Employer as are applicable to the Contract Works and with any other applicable regulations to which the Employer is subject.

The Contractor shall fully inform himself of the requirements of the local Laws, Regulations and rules in force in the State of Orissa, especially with respect to local employment laws, licensing requirements, electrical safety rules and regulations, building regulations and planning procedures.

The Contractor shall be responsible for applying for all necessary licenses; including Electrical Contractors License, Workman's Permits and Certificates of Competency for Supervisors, and local government approvals required for the contract works and for the payment of all necessary fees associated with such licenses and approvals.

Correspondence with the Electrical Inspector shall be conducted through the Engg Incharge (Divisional Engr.), but the Contractor shall provide all necessary information, regarding the contract works, as may be required by the Electrical Inspector.

Additionally the Contractor shall also follow the minimum regulations on safety, employees welfare, industry etc. as stipulated under the relevant Clause of this section.

14 .0 MAINTENANCE AND CLEARING OF SITE

The placing of materials and plant near the erection site prior to their being erected and installed shall be done in a neat, tidy and safe manner. The Contractor shall at his own expense keep the site area allocated to him and also the erection area of the Contract Works reasonably clean and shall remove all waste material as it accumulates and as directed by the Engg Incharge from time to time.

15 .0 INSURANCE

15.1 General

In addition to the conditions covered under the Clause titled insurance in the Special Conditions of Contract, the following provisions will also apply to the portion of works to be done beyond the Suppliers own or his sub-Contractors manufacturing Works.

15.2 Workmen's Compensation Insurance

This insurance shall protect the Contractor against all claims applicable under the Workmen's Compensation Act, 1948 (Government of India). This policy shall also cover the Contractor against the claims for injury, disability, disease or death of his or his sub-contractor's employees, which for any reason are not covered under the Workman's Compensation Act, 1948. The liabilities shall not be less than;

- | | | |
|-----|------------------------|-----------------------------|
| I. | Workmen's Compensation | As per statutory provisions |
| II. | Employee's liability | As per statutory provisions |

* According to the Govt. rules.

15.3 Comprehensive auto mobile insurance

This insurance shall be in a such a form to protect the Contractor against all claims for injuries, disability, disease and death to members of public including the Employer's men and damage to the property of others arising from the use of motor vehicles during on or off the Site operations, irrespective of the ownership of such vehicles. The minimum liability covered shall be as herein indicated:

- | | | | |
|------|--------------|---|-------------------------------|
| I. | Fatal Injury | : | Rs. 100,000/- each person |
| II. | Property | : | Rs. 200,000/- each occurrence |
| III. | Damage | : | Rs. 100,000/- each occurrence |

* As per latest prevailing Govt. rules.

15.4 Comprehensive General Liability Insurance

This insurance shall protect the Contractor against all claims arising from injuries, disabilities, disease or death of members or public or damage to property of others, due to any act or omission on the part of the Contractor, its agents, its employees, its representatives and sub-contractors or from riots, strikes and civil commotion.

The hazards to be covered will pertain to all works and areas where the Contractor, its sub-contractors, agents and employees have to perform work pursuant to the Contracts.

The above are only an illustrative list of insurance covers normally required and it will be the responsibility of the Contractor to maintain all necessary insurance coverage to the extent both in time and amount to take care of all its liabilities either direct or indirect, in pursuance of the Contract.

16.0 PROTECTION OF MONUMENTS AND REFERENCE POINTS

The Contractor shall ensure that any finds such as relics, antiques, coins, fossils, etc. which he may come across during the course of performance of his works either during excavation or elsewhere, are properly protected and handed over to the Employer. Similarly, the Contractor shall ensure that the bench marks, reference points, etc. which are marked either with the help of Employer or by the Employer shall not be disturbed in any way during the performance of his works. If any work is to be performed which disturbs such reference points, the same shall be done only after these are transferred to other suitable locations under the direction of the Employer. The Contractor shall provide all necessary materials and assistance for such relocation of reference points etc.

17 .0 WORK AND SAFETY REGULATIONS

The Contractor shall ensure safety of all the workmen, plant and equipment belonging to him or to others, working at the Site. The Contractor shall also provide for all safety notices and safety equipment required by the relevant legislation and deemed necessary by the Engg Incharge .

The Contractor will notify, well in advance to the Engg Incharge, his intention to bring to the Site any container filled with liquid or gaseous fuel, explosive or petroleum substance or such chemicals which may involve hazards. The Engg Incharge shall have the right to prescribe the conditions under which such a container is to be stored, handled and used during the performance of the works and the Contractor shall strictly adhere to and comply with such instructions. The Engg Incharge shall also have the right, at his sole discretion, to inspect any such container or such construction plant and equipment for which materials in the container is required to be used and if in his opinion, its use are not safe, he may forbid their use.

No claim due to such prohibition or towards additional safety provisions called for by him shall be entertained by the Employer.

Further, any such decision of the Engg Incharge shall not, in any way, absolve the Contractor of his responsibilities and in case use of such a container or entry thereof into the Site areas is forbidden by the Engg Incharge the Contractor shall use alternative methods with the approval of the Engg Incharge without any cost implication to the Employer or extension of work schedule.

Where it is necessary to provide and/or store petroleum products or petroleum mixtures and explosives, the Contractor shall be responsible for carrying out such provision and/or storage in accordance with the rules and regulations laid down in Petroleum Act 1934, Explosives Act 1948 and amendments thereof, and Petroleum and Carbide of Calcium Manual published by the Chief Inspector of Explosives of India. All such storage shall have prior approval of the Engg Incharge. In case, any approval is necessary from the Chief Inspector (Explosives) or any statutory authorities, the Contractor shall be responsible for obtaining the same.

All equipment used in construction and erection by Contractor shall meet Indian or International Standards and where such standards do not exist, the Contractor shall ensure these to be absolutely safe. All equipment shall be strictly operated and maintained by the Contractor in accordance with manufacturers operation manual and safety instructions and as per any existing Guidelines/Rules in this regard.

Periodical examinations and all tests for all lifting and hoisting equipment and tackle shall be carried out in accordance with the relevant provisions of Factories Act 1948, Indian Electricity (Supply) Act and associated Laws/Rules in force, from time to time. A register of such examinations and tests shall be properly maintained by the Contractor and will be promptly produced as and when desired by Engg Incharge.

The Contractor shall provide suitable safety equipment of prescribed standard to all employees and workmen according to the need, as may be directed by the Engg Incharge who will also have the right to examine such safety equipment to determine its suitability, reliability, acceptability and adaptability.

Where explosives are to be used, the same shall be used under the direct control and supervision of an expert, experienced and qualified competent person, strictly in accordance with the Code of Practices/Rules framed under Indian Explosives Act pertaining to handling, storage and use of explosive.

Contractors employing more than 250 workmen whether temporary, casual, probationer, regular or permanent or on contract, shall employ at least one full time officer exclusively as Safety Officer to supervise safety aspects of the equipment and workmen. Such an officer will co-ordinate with the Project Safety officer of the Employer.

The name and address of the Safety Officer of the Contractor will be promptly informed in writing to the Engg Incharge with a copy to the Safety Officer-in-charge before he starts work or immediately after any change of the incumbent is made during currency of the Contract.

In case any accident occurs during the construction, erection or other associated activities undertaken by the Contractor, thereby causing any minor or major or fatal injury to his employees due to any reason whatsoever, it shall be the responsibility of the Contractor to promptly inform the same to the Engg Incharge and also to all the authorities envisaged under the applicable laws.

The Engg Incharge shall have the right at his sole discretion to stop the work, if in his opinion the work is being carried out in such a way as may cause accidents or endanger the safety of the persons and/or equipment. In such cases, the Contractor shall be informed in writing about the nature of hazards and possible injury/accident and he shall remove shortcomings immediately. The Contractor, after stopping the specific work, can if felt necessary appeal against the order of stoppage of work to the Engg Incharge within three days of such stoppage of work and the decision of the Engg Incharge in this respect shall be conclusive.

The Contractor shall not be entitled for any damages or compensation for stoppage of work due to safety reasons and the period of such stoppage of work will not be taken as an extension of time for completion of work, nor will it be the grounds for waiver of any part of suppliers liability for timely completion of the works.

The Contractor shall follow and comply with all Safety Rules, relevant provisions of applicable laws pertaining to the safety of workmen, employees, plant and equipment as may be prescribed from time to time without any demur, protest or contest or reservation. In case of any conflict between statutory requirement and Safety Rules referred above, the most stringent clause shall be applicable.

If the Contractor fails in providing safe working environment as per Safety Rules or continues the works even after being instructed to stop work by the Engg Incharge, the Contractor shall promptly pay to the Employer on demand, compensation at the rate of Rs. 5,000/- per day or part thereof till the instructions are complied with and so certified by the Employer. However, in case of accident taking place causing injury to any individual, the provision contained in subsequent paragraph as here below shall also apply in addition to the compensation mentioned in this paragraph.

If the Contractor does not take all safety precautions and comply with Safety Rules as prescribed by the Engg Incharge or as prescribed under the applicable law, to safeguard equipment, plant and personnel the Contractor shall be responsible for payment of compensation to the Employer as per the schedule given below.

If the Contractor does not prevent hazardous conditions which may cause injury to his own employees, employees of other Contractors, or the Employer or any other person at Site or adjacent thereto, the Contractor shall be responsible for payment of compensation to the Employer as per the following Schedule:

Fatal injury or accident causing death.	Rs. 100,000/- per person	Applicable for injury or death to any person whomsoever.
---	--------------------------	--

Major injuries or accident causing 25% or more permanent disability. Rs. 20,000/- per person Applicable for injury or death to any person whomsoever.

* As per prevailing Govt. rules.

Permanent disability shall have the same meaning as indicated in Workmen's Compensation Act. The compensation mentioned above shall be in addition to the compensation payable to the workmen/employees under the relevant provisions of the Workmen's Compensation Act and rules framed thereunder or any other applicable law as applicable from time to time. In case the Employer is made to pay such compensation, the Contractor will reimburse the Employer such amount(s) in addition to the compensation indicated above.

18 .0 FOREIGN PERSONNEL

If necessary for the execution of the works, the Contractor shall bring foreign supervisors for the execution of the Contract at his own cost. The Contractor shall submit to the Employer data on all personnel he proposes to bring into India for the performance of the works under the Contract, at least Sixty (60) days prior to their arrival in India. Such data shall include the name of each person, his present address, his assignment and responsibility in connection with the works, and a short resume of his qualifications and experience etc. in relation to the work to be performed by him.

Any person unsuitable and unacceptable to the Employer, shall not be brought to India. Any person brought to India, and found unsuitable or unacceptable to the Employer shall be immediately removed from Site and repatriated. If found necessary, he may be replaced by other personnel acceptable to the Employer.

No person brought to India by the Contractor for the works shall be repatriated without the consent of the Employer in writing, based on a written request from the Supplier for such repatriation giving reasons for such an action to the Employer. The Employer may give permission for such repatriation provided the Employer is satisfied that the progress of work will not suffer due to such repatriation.

The cost of passports, visas and all other travel expenses to and from India, shall be to the Contractor's account. The Employer will not provide any residential accommodation and/or furniture for any of the Contractor's personnel including foreign personnel. Contractor shall make his own arrangements for such facilities.

The Contractor and his expatriate personnel shall respect all Indian Acts, Laws, Rules and Regulations and shall not in any way, interfere with Indian political and religious affairs and shall conform to any other rules and regulations which the Government of India, and the Employer may establish on them. The Contractor's expatriate personnel shall work and live in close co-operation and co-ordination with their co-workers and the community and shall not engage themselves in any other employment either part-time or full-time nor shall they take part in any local politics.

The Employer shall assist the Contractor, to the extent possible, in obtaining necessary certificates and other information needed by the Government agencies.




ODISHA POWER TRANSMISSION CORPORATION LTD

**TECHNICAL
SPECIFICATION
VOLUME-II (PART-I)**

CONTENTS OF THE TECHNICAL BIDDING DOCUMENTS (VOL-II)

CHAPTER No	DESCRIPTION	PAGES
E1	GENERAL CLAUSES	1-13
E2	GENERAL TECHNICAL CLAUSES FOR DESIGN	1-34
E3	SYSTEM DATA	1-2
E4	GENERAL METEROLOGICAL DATA	1-2
E5	DESIGN CLAUSES FOR SUB STATION	1-8
E6	CIVIL WORKS	'1-84
E7	SWITCHYARD STRUCTURE	1-9
E8	DRAWING,TEST CERTIFICATE,O&M MANUALS	1-16
E9	ELECTRICAL EQUIPMENT INSTALLATION & COMMISSIONING	1-12
E10	GENERAL EQUIPMENT & SUBSTATION ACCESSORIES	1-25
E11	CIRCUIT BREAKER	1-55
E12	CURRENT TRANSFORMER	1-37
E13	ISOLATORS	1-16
E14	STATION TRANSFORMER	1-18
E15	SURGE ARRESTER	1-21
E16	IVT,CVT	1-29
E17	BATTERY & BATTERY CHARGER	1-30
E18	PLCC	1-35
E19	DISTRIBUTION BOARD	1-25
E20	CONDUCTOR,EARTH WIRE,INSULATORS,HARDWARES, CLAMPS & CONNECTORS	1-78
E21	CONTROL & PROTECTION PANEL	'1-98
E21A	Technical Spec for Sub station Automation (control & Protection) & Out door AC Kiosk	'1-98
E22	AIR CONDITIONER	1-3
E23	CONTROL &POWER & COAXIAL CABLES	1-30
E24	SUB STATION LIGHTING	1-10
E25	TESTING INSTRUMENTS &MAINTENANCE KITS	1-10
E26	TRANSMISSION LINES	1-91
E27	OPGW CABLE & ITS SYSTEM	'1-39
E28	250 KVA DG SET	'1-14
E29	SHUNT REACTOR-NGR-SA	'1-51
E30	FIRE FIGHTING SYSTEM	01/01/72



ODISHA POWER TRANSMISSION CORPORATION LIMITED

**TECHNICAL SPECIFICATION
VOLUME-II (PART-I)**

GENERAL
GENERAL CLAUSES
TABLE OF CONTENTS

1.4 Limit of contract.....	4
2.GENERAL PARTICULARS OF SYSTEM.....	5
System description	5
Substation description:.....	5
Layout arrangement	5
Meteorological data.....	5
Soil data.....	6
Completeness and accuracy of information.....	6
3.DRAWINGS ATTACHED WITH TENDER DOCUMENT	6
4.GUARANTEES TECHNICAL PARTICULARS	6
5.COMPLIANCE WITH SPECIFICATION.....	6
6.TEST AND MAINTENANCE EQUIPMENT	7
7.SPARES.....	7
7.1 General.....	7
7.2 Mandatory spares.....	7
7.3 Optional spares (shall not be considered for evaluation purpose).	7
8.0 TRAINING	8
8.1 Hardware maintenance.....	8
8.2 Operator familiarisation	8

8.3 Software management.....	8
II.A) Installation and commissioning techniques	9
II.B) Proposals for training and manning	9
9.0 ERECTION AT SITE AND ACCOMMODATION.....	10
10.0 SITE CONSTRUCTION SUPPLIES.....	10
11.0 SUPERVISION AND CHECKING OF WORK ON SITE.....	10
12.0 RESPONSIBILITY FOR THE RUNNING OF PLANT BY CONTRACTOR.....	11
13.0 COMPLIANCE WITH REGULATIONS	11
14.0 MAINTENANCE AND CLEARING OF SITE	12
15.0 INSURANCE	12
15.1 General	12
15.2 Workmen's Compensation Insurance	12
15.3 Comprehensive auto mobile insurance	12
15.4 Comprehensive General Liability Insurance.....	13
16.0 PROTECTION OF MONUMENTS AND REFERENCE POINTS	13
17.0 WORK AND SAFETY REGULATIONS	13
18.0 FOREIGN PERSONNEL.....	15

1. GENERAL CONDITIONS

1.1 Responsibility of the Contractor

The Contractor shall also be responsible for the complete design and engineering, overall co-ordination with internal and external agencies, project management, training of Employer's manpower, loading, unloading, storage at site, inventory management at site during construction, dismantling, re-erection of installations as per Engg Incharge advice, handling, moving to final destination, obtaining statutory authority's clearance for successful erection, and testing and commissioning of the substation.

1.2 Specific exclusions:

The following items of work are specifically excluded from the Contractor's scope of work unless otherwise specifically brought out..

I. Substation site selection

II. Land acquisition

1.3 Interfacial point for line termination at substation

The line Contractor shall terminate the transmission line along with insulator hardware and other essential fittings at the substation gantry. The substation Contractor shall provide necessary anchoring plates in co-ordination with the transmission line contractor. The substation Contractor shall be responsible for providing the necessary electrical interconnection from the line conductor to the substation.

1.4 Limit of contract

The scope of work shall also include all work incidental for successful operation and commissioning and handing over of works whether specifically mentioned or not. In general works are to be carried out by the Contractor in accordance with stipulations in Conditions of Contract.

1.5 Quantity variation

The Employer reserves the right to order and delete such works which may be necessary for him within the quantity variation option laid down in the conditions of the contract. This shall include but not be limited to: the manufacture, supply, testing, and delivery to site, erection and commissioning as may be required in accordance with the Conditions of Contract at the prices stated in the Schedules.

The Employer shall be at liberty to order from the Contractor such quantities of the apparatus at any time before the expiration of the maintenance period of the scope of work, provided that such quantities do not exceed the limitation of the Contract Value as defined in the Conditions of Contract. Each separate order for Work at the Option of the Employer shall constitute a section for the purpose of payment and taking over.

The Employer shall also be at liberty to delete from the Contractor such quantities of the apparatus at any time before commencement of supply of works under the detailed scope of work.

1.6 Supply of non specified equipment/service during execution of contract.

The Employer may require the Contractor to supply and install a number of items such as testing and measuring instruments, vehicles, repairing of existing equipment, removal and refurbishment of plant/equipment from one place to another etc., which in the opinion of the Engg Incharge are to the interest of the project execution. These items and services shall not be limited to proprietary goods provided for the project.

Such supplies and services shall be reimbursed against supply and service invoices for the materials or services actually supplied from the manufacturer or supplier of these items. The bidder shall quote on cost for these items for the earmarked funds in appropriate schedules which shall be considered in bid prices. However these costs shall be payable to the Contractor on pro rata basis for the actual amount spent for procurement and availing of the services.

For such items of supply the Contractor shall follow the fair principle of contracting procedure to the satisfaction of Engg Incharge.

2. GENERAL PARTICULARS OF SYSTEM

System description

The following are the general particulars governing the design and working of the complete system of which the Contract Works will eventually form a part:

Electrical energy is generated at a number of thermal and hydro power plants generally located in the North, Central and Southern areas of Orissa State. The system is three phase, 50Hz and power is transmitted at 400kV, 220kV and 132kV to the distribution system, via grid substations, which operate at 33kV, 11kV and 400V. The 400kV and 220kV networks tie into the OPTCL's 400kV and 220kV grid systems operated by OPTCL. The proposed works will increase the interconnection of, and will thus reinforce the 400kV and 220kV networks within Orissa State. The detailed technical parameters of the system are given in the schedules.

Substation description:

OPTCL has adopted the philosophy of installing open terminal air insulated substations. The busbars for 400 KV rigid type and for 220 KV flexible strain type depending upon the choice of the designer considering the overall suitability and economy of the substation to be installed.

Layout arrangement

The Contractor shall study the details of layout arrangements already indicated in the schedules details for the existing substations. The bay width and height of the conductors for these substations shall be achieved by the Contractor in case of extension substations. However the Contractor shall finalise the layout arrangements in case of new substations in line with this Specification with the approval of the Engg Incharge, which shall be meeting at least the basic minimum electrical clearances as specified in the schedules.

Location and site description

Details of the sub-substation locations, their approach, geography and topography has been provided to the extent possible. The Bidder shall make necessary visit to the substation sites and fully appraise himself before bidding. Deviations on account of inadequate data for substation works shall not be acceptable and the Bid shall not be considered for evaluation in such cases.

Meteorological data

Appropriate meteorological data is given in the schedules.

Soil data

Detailed soil investigations in respect of various substations have not been made. However the general characteristics of the soil are given in the schedules. The Contractor shall investigate the properties of the substations and measure the soil resistivity as part of the scope of work.

Completeness and accuracy of information

The Contractor shall note that the information provided above and in the relevant schedules may not be complete or fully accurate at the time of bidding. For his own interest the Contractor is advised to make site visits and fully satisfy himself regarding site conditions in all respects, and shall be fully responsible for the complete design and engineering of the substations.

3. DRAWINGS ATTACHED WITH TENDER DOCUMENT

The various drawings and schedules provided are a part of the specification and for information purposes only. These are not necessarily binding on the part of the Contractor. Bids shall be prepared by the Bidder based on information provided in the drawings and schedules and that gathered by the Bidder himself.

4. GUARANTEES TECHNICAL PARTICULARS

The Contract Works shall comply with the guaranteed technical particulars specified or quoted in the bid. All plant and apparatus supplied under this Contract shall be to the approval of the Engg Incharge .

All plant and equipment supplied under this contract must have been type tested, have been in manufacture and satisfactory service at identical ratings for at least two years. The bidder shall furnish in his bid the necessary supporting data in specified formats for consideration during bid evaluation. If during evaluation non compliance is identified the successful Contractor shall be bound to supply the equipment from manufacturers complying with the stipulated requirements / OPTCL approval renders.

The Contractor shall be responsible for any discrepancies, errors or omissions in the particulars and guarantees.

The Bidder for his own interest, shall establish the technical responsiveness of his bid, shall provide all data in appropriate technical data sheets, general/ technical information, literature, and pamphlets etc. along with the bid.

5. COMPLIANCE WITH SPECIFICATION

All apparatus should comply with this Specification. Any departures from the requirements of this Specification shall be stated in the relevant Bid Proposal Schedules and will be considered during Bid evaluation. Unless brought out clearly in the technical schedules, it will be presumed that the equipment is deemed to comply with the technical specification.

In the event of there being any inconsistency between the provisions of the conditions of contract and the provisions of this Specification in respect of commercial requirements, the provisions of the conditions of contract shall take precedence for commercial matters and the provisions of this Specification shall take precedence in respect of technical matters.

In case of inconsistency between technical specification & bid proposal sheet, quantities of various items as specified in the bid proposal sheet shall be considered for quoting however the work shall be executed as specified in the technical specification. Only brief description is given in the BPS & the work shall be executed in line with the requirement given in the TS.

The manufacturer and places of manufacture, testing and inspection of the various portions of the Contract Works shall be stated in the relevant Bid Proposal Schedules.

6. TEST AND MAINTENANCE EQUIPMENT

The Contractor shall supply the type and quantity of test and maintenance equipment specified in the Schedules as part of the contract works.

7. SPARES

7.1 General

The Contractor shall provide the mandatory spares detailed in the Schedules. Provide a list of recommended spare parts (optional spares) together with their individual prices, but that will not be considered for evaluation. The Employer may order all or any of the Optional spare parts listed at the time of contract award . Mandatory spares shall be supplied as part of the Works under this

specification. Additional spares(Mandatory) may be ordered at any time during the contract at the rates stated in the Price Schedule.

7.2 Mandatory spares

The Employer has indicated the requirement of mandatory spares as a percentage of the population of main equipment together with proposed storage locations. The quantities shall be determined by the Contractor and indicated in the relevant Bid Price Schedules. These quantities shall be considered for evaluation of the bids.

7.3 Optional spares (shall not be considered for evaluation purpose).

The Contractor may recommend a list of optional spare parts together with the quantity and usage rates for their equipment in the relevant Bid Proposal Schedule. The Engg Incharge shall assess their requirement and place orders.

The spares shall include consumable items sufficient for a plant operational period of five years after commissioning, as well as essential replacement parts to cover the event of a break-down which would affect the availability or safety of the plant. Spares shall be available during the life of the equipment and the Contractor shall give 12 months notice of his, or any sub-contractor's, intention to cease manufacture of any component used in the equipment.

The Contractor shall ensure that sufficient spare parts and consumable items are available for his own use during commissioning of the plant. Spares ordered by the Employer shall not be used by the Contractor without the written consent of the Engg Incharge and any spares so used by the Contractor during the commissioning of the plant shall be replaced by the Contractor at the Contractor's expense.

Any spare apparatus, parts and tools shall be subject to the same specification, tests and conditions as similar material supplied under the Scope of Works of the Contract. They shall be strictly interchangeable and suitable for use in place of the corresponding parts supplied with the plant and must be suitably marked and numbered for identification and prepared for storage by greasing or painting to prevent deterioration.

All spare apparatus or materials containing electrical insulation shall be packed and delivered in cases suitable for storing such parts or material over a period of years without deterioration. Such cases shall have affixed to both the underside and topside of the lid a list detailing its contents. The case will remain the property of the Employer.

8.0 TRAINING

The Contractor will be required to provide suitable training for selected staff both on site and at the Contractor's place of work. Details of the training considered appropriate shall be stated clearly, at the bidding stage, based on the number of trainees specified. The cost of training including all course fees shall be included.

The areas in which it is considered training should be provided, and duration of the training courses, are given in this section. Alternative arrangements, where considered appropriate, should be suggested.

Four categories of training are considered appropriate namely :

- I. Hardware maintenance.
- II. Operator familiarisation.
- III. Software management.
- IV. Installation and commissioning techniques.

8.1 Hardware maintenance

Courses for hardware maintenance shall identify techniques for preventative physical maintenance and for identification, isolation and replacement of faulty components. This course shall take place before equipment is delivered to site.

An essential part of the hardware maintenance course shall include highlighting the philosophy of computer based preventive maintenance and identification of the various diagnostic/interrogation facilities available. The Contractor shall supply adequate documented instructions to enable a detailed interrogation and analysis process to be carried out using the diagnostic software facilities. All items of hardware to be supplied shall be covered by the course.

8.2 Operator familiarisation

This course is intended to familiarise the operators with the system and its use in operating and controlling the PLCC network. The course shall ensure that the control room staff are completely familiar with all operational aspects of the equipment. The means of obtaining special data, report logs and all other facilities which would enable the operators to be fully conversant with the system, shall also be incorporated.

It is envisaged that it will be necessary for the Contractor to run operator familiarisation courses each of approximately one week in duration at site for the training of the Employer's staff.

8.3 Software management

This course shall comprise two main areas and shall take place at the Contractor's works before equipment is delivered to site .

I). A FORMAL COURSE ON THE SOFTWARE FOR EPAX ETC. DETAILING THE VARIOUS MODULES USED AND THEIR INTERACTION.

II). A PRACTICAL COURSE ON EDITING THE DATABASE (TO INCORPORATE EXTENSIONS TO THE POWER NETWORKS, INCLUSION OF ADDITIONAL ANALOGUE/DIGITAL SIGNALS FROM EXISTING EQUIPMENT, ETC.) AND GENERATING NEW LOGS, ALPHANUMERIC DISPLAYS, ETC.

It is envisaged that the software management courses shall extend for a period of approximately six weeks.

II.A) Installation and commissioning techniques

The Employer's staff will be present during the installation and commissioning period and it is essential that they be fully involved in any on-site corrections or modifications to hardware and software equipment.

It is envisaged that it will be necessary for the Contractor to run installation and commissioning techniques courses each of approximately one week in duration at site for the training of the Employer's staff.

II.B) Proposals for training and manning

For each course recommended the following information shall be provided:

- I. Course name and identification.
- II. Short description of the curriculum.
- III. Level of competency required for each course.
- IV. Date and duration.
- V. Maximum number of staff that can attend.

VI. Location.

VII. Other important information.

The times at which the various training courses will take place shall be stated, and fully documented notes shall be available to the Employer not later than two months before the commencement of the course.

All training course notes and documentation shall be in the English language.

An estimate of the total number of the Employer's staff required to run, operate and service the works covered by this Specification shall be given if this is different to the numbers specified.

The prices of the training courses shall be detailed in full such that additions or deletions to personnel or courses can be calculated by the Employer without necessarily having to contact the Contractor. This is particularly important for the 'Software management' courses where prices for formal course days and practical course days shall be individually detailed.

9.0 ERECTION AT SITE AND ACCOMMODATION

The Contractor shall provide, at his own cost and expense, all labour, plant and material necessary for unloading and erection at the Site and shall be entirely responsible for its efficient and correct operation.

The Contractor shall be responsible for arranging and providing all living accommodation services and amenities required by his employees. He shall also provide suitable office accommodation at each substation site for the sole use by the Engg Incharge (Divisional Engr.) **for new substations only**.

10.0 SITE CONSTRUCTION SUPPLIES

The Contractor shall provide at his own cost and expense, any site supplies of electrical energy which he may require for supplying power for heavy erection plant, welding plant or other tools and lighting and testing purposes.

All wiring for such tackle and for lighting from the point of supply shall be provided by the Contractor and all such installations shall comply with all appropriate statutory regulations to which the Employer is subject.

Wiring shall be of the best quality double insulated flexible cable, suitably fixed, protected and maintained. All necessary precautions shall be taken to ensure the safety of every person employed or working on the Site and this shall include routine inspection of all temporary installations and portable equipment.

The Engg Incharge or his authorised representative may require the disconnection or alteration of any parts which he may consider dangerous.

As soon as any part or the whole of the Contractor's installation is no longer required for the carrying out of the works, the Contractor shall disconnect and remove the same to the satisfaction of the Engg Incharge or his authorised representative.

The contractor shall be responsible for arranging construction water at his own cost.

How ever in case water is available at any substation site, Contractor may request Engg Incharge for availing water at one point, which shall be charged to the contractor at prevailing rates for supply of water by Govt. Dept. / Municipal Authorities.

In no case the work shall suffer on account of the Employer not making available the supply of water and electricity for construction purposes.

11 .0 SUPERVISION AND CHECKING OF WORK ON SITE

All work on site included in the Contract scope of works shall be supervised by a sufficient number of qualified representatives of the Contractor.

Before putting any plant or apparatus into operation the Contractor shall satisfy himself as to the correctness of all connections between the plant and apparatus supplied under this and other contracts. The Contractor shall advise the Engg Incharge in writing, giving the period of notice as specified in the General Conditions of Contract, when the plant or apparatus is ready for inspection or energisation.

12 .0 RESPONSIBILITY FOR THE RUNNING OF PLANT BY CONTRACTOR

Until each Section of the Contract Works has been taken over or deemed to have been taken over under the Conditions of Contract, the Contractor shall be entirely responsible for the Contract Works, whether under construction, during tests, or in use for the Employer's service.

The Contractor shall instruct the Employer's operating staff in the recommended method of operation of the plant supplied. Such instruction shall commence prior to the commissioning of the plant and shall be followed by practical instruction for a period of up to one month after the plant is taken over by the Employer. During this one month period the Contractor shall provide an engineer, on each site that is taken over, to assist with operation of the plant and to provide on-site training of the Employer's operating staff. The training schedule and programme for each substation shall be submitted to the Engg Incharge for approval, three months prior to the substation's planned completion date.

If the Employer shall so require, the Contractor shall provide the services of a skilled engineer acquainted with the running of the plant for any period required by the Employer between commencing of use of any portion of the plant (whether taken over or not) and the expiry of the period of maintenance, the wages for such services being paid by the Employer to the Contractor, except in respect of the carrying out of any work already covered by the Contractor's obligations under this Contract.

When the Contractor ceases to be obliged to maintain a supervising engineer on the Site under the foregoing provisions of this clause, the Contractor shall, until the expiration of the period of maintenance, make such arrangements as to ensure the attendance on site within 24 hours of being called upon by the Engg Incharge of a competent supervising engineer for the purpose of carrying out any work of maintenance or repair for which the Contractor shall be liable. During such part or parts of the said period as the Engg Incharge shall deem it necessary the said representative shall be continuously available on the Site.

Any work which may be necessary for the Contractor to carry out in pursuance of his obligations under the Conditions of Contract shall be carried out with the minimum of interference to the normal operation of the substation. Work on the Site shall be carried out at such time and during such hours as the Engg Incharge may require.

13 .0 COMPLIANCE WITH REGULATIONS

All apparatus and material supplied, and all work carried out shall comply in all respects with such of the requirements of all Regulations and Acts in force in the country of the Employer as are applicable to the Contract Works and with any other applicable regulations to which the Employer is subject.

The Contractor shall fully inform himself of the requirements of the local Laws, Regulations and rules in force in the State of Orissa, especially with respect to local employment laws, licensing requirements, electrical safety rules and regulations, building regulations and planning procedures.

The Contractor shall be responsible for applying for all necessary licenses; including Electrical Contractors License, Workman's Permits and Certificates of Competency for Supervisors, and local government approvals required for the contract works and for the payment of all necessary fees associated with such licenses and approvals.

Correspondence with the Electrical Inspector shall be conducted through the Engg Incharge (Divisional Engr.), but the Contractor shall provide all necessary information, regarding the contract works, as may be required by the Electrical Inspector.

Additionally the Contractor shall also follow the minimum regulations on safety, employees welfare, industry etc. as stipulated under the relevant Clause of this section.

14 .0 MAINTENANCE AND CLEARING OF SITE

The placing of materials and plant near the erection site prior to their being erected and installed shall be done in a neat, tidy and safe manner. The Contractor shall at his own expense keep the site area allocated to him and also the erection area of the Contract Works reasonably clean and shall remove all waste material as it accumulates and as directed by the Engg Incharge from time to time.

15 .0 INSURANCE

15.1 General

In addition to the conditions covered under the Clause titled insurance in the Special Conditions of Contract, the following provisions will also apply to the portion of works to be done beyond the Suppliers own or his sub-Contractors manufacturing Works.

15.2 Workmen's Compensation Insurance

This insurance shall protect the Contractor against all claims applicable under the Workmen's Compensation Act, 1948 (Government of India). This policy shall also cover the Contractor against the claims for injury, disability, disease or death of his or his sub-contractor's employees, which for any reason are not covered under the Workman's Compensation Act, 1948. The liabilities shall not be less than;

- | | | |
|-----|------------------------|-----------------------------|
| I. | Workmen's Compensation | As per statutory provisions |
| II. | Employee's liability | As per statutory provisions |

* According to the Govt. rules.

15.3 Comprehensive auto mobile insurance

This insurance shall be in a such a form to protect the Contractor against all claims for injuries, disability, disease and death to members of public including the Employer's men and damage to the property of others arising from the use of motor vehicles during on or off the Site operations, irrespective of the ownership of such vehicles. The minimum liability covered shall be as herein indicated:

- | | | | |
|------|--------------|---|-------------------------------|
| I. | Fatal Injury | : | Rs. 100,000/- each person |
| II. | Property | : | Rs. 200,000/- each occurrence |
| III. | Damage | : | Rs. 100,000/- each occurrence |

* As per latest prevailing Govt. rules.

15.4 Comprehensive General Liability Insurance

This insurance shall protect the Contractor against all claims arising from injuries, disabilities, disease or death of members or public or damage to property of others, due to any act or omission on the part of the Contractor, its agents, its employees, its representatives and sub-contractors or from riots, strikes and civil commotion.

The hazards to be covered will pertain to all works and areas where the Contractor, its sub-contractors, agents and employees have to perform work pursuant to the Contracts.

The above are only an illustrative list of insurance covers normally required and it will be the responsibility of the Contractor to maintain all necessary insurance coverage to the extent both in time and amount to take care of all its liabilities either direct or indirect, in pursuance of the Contract.

16.0 PROTECTION OF MONUMENTS AND REFERENCE POINTS

The Contractor shall ensure that any finds such as relics, antiques, coins, fossils, etc. which he may come across during the course of performance of his works either during excavation or elsewhere, are properly protected and handed over to the Employer. Similarly, the Contractor shall ensure that the bench marks, reference points, etc. which are marked either with the help of Employer or by the Employer shall not be disturbed in any way during the performance of his works. If any work is to be performed which disturbs such reference points, the same shall be done only after these are transferred to other suitable locations under the direction of the Employer. The Contractor shall provide all necessary materials and assistance for such relocation of reference points etc.

17 .0 WORK AND SAFETY REGULATIONS

The Contractor shall ensure safety of all the workmen, plant and equipment belonging to him or to others, working at the Site. The Contractor shall also provide for all safety notices and safety equipment required by the relevant legislation and deemed necessary by the Engg Incharge .

The Contractor will notify, well in advance to the Engg Incharge, his intention to bring to the Site any container filled with liquid or gaseous fuel, explosive or petroleum substance or such chemicals which may involve hazards. The Engg Incharge shall have the right to prescribe the conditions under which such a container is to be stored, handled and used during the performance of the works and the Contractor shall strictly adhere to and comply with such instructions. The Engg Incharge shall also have the right, at his sole discretion, to inspect any such container or such construction plant and equipment for which materials in the container is required to be used and if in his opinion, its use are not safe, he may forbid their use.

No claim due to such prohibition or towards additional safety provisions called for by him shall be entertained by the Employer.

Further, any such decision of the Engg Incharge shall not, in any way, absolve the Contractor of his responsibilities and in case use of such a container or entry thereof into the Site areas is forbidden by the Engg Incharge the Contractor shall use alternative methods with the approval of the Engg Incharge without any cost implication to the Employer or extension of work schedule.

Where it is necessary to provide and/or store petroleum products or petroleum mixtures and explosives, the Contractor shall be responsible for carrying out such provision and/or storage in accordance with the rules and regulations laid down in Petroleum Act 1934, Explosives Act 1948 and amendments thereof, and Petroleum and Carbide of Calcium Manual published by the Chief Inspector of Explosives of India. All such storage shall have prior approval of the Engg Incharge. In case, any approval is necessary from the Chief Inspector (Explosives) or any statutory authorities, the Contractor shall be responsible for obtaining the same.

All equipment used in construction and erection by Contractor shall meet Indian or International Standards and where such standards do not exist, the Contractor shall ensure these to be absolutely safe. All equipment shall be strictly operated and maintained by the Contractor in accordance with manufacturers operation manual and safety instructions and as per any existing Guidelines/Rules in this regard.

Periodical examinations and all tests for all lifting and hoisting equipment and tackle shall be carried out in accordance with the relevant provisions of Factories Act 1948, Indian Electricity (Supply) Act and associated Laws/Rules in force, from time to time. A register of such examinations and tests shall be properly maintained by the Contractor and will be promptly produced as and when desired by Engg Incharge.

The Contractor shall provide suitable safety equipment of prescribed standard to all employees and workmen according to the need, as may be directed by the Engg Incharge who will also have the right to examine such safety equipment to determine its suitability, reliability, acceptability and adaptability.

Where explosives are to be used, the same shall be used under the direct control and supervision of an expert, experienced and qualified competent person, strictly in accordance with the Code of Practices/Rules framed under Indian Explosives Act pertaining to handling, storage and use of explosive.

Contractors employing more than 250 workmen whether temporary, casual, probationer, regular or permanent or on contract, shall employ at least one full time officer exclusively as Safety Officer to supervise safety aspects of the equipment and workmen. Such an officer will co-ordinate with the Project Safety officer of the Employer.

The name and address of the Safety Officer of the Contractor will be promptly informed in writing to the Engg Incharge with a copy to the Safety Officer-in-charge before he starts work or immediately after any change of the incumbent is made during currency of the Contract.

In case any accident occurs during the construction, erection or other associated activities undertaken by the Contractor, thereby causing any minor or major or fatal injury to his employees due to any reason whatsoever, it shall be the responsibility of the Contractor to promptly inform the same to the Engg Incharge and also to all the authorities envisaged under the applicable laws.

The Engg Incharge shall have the right at his sole discretion to stop the work, if in his opinion the work is being carried out in such a way as may cause accidents or endanger the safety of the persons and/or equipment. In such cases, the Contractor shall be informed in writing about the nature of hazards and possible injury/accident and he shall remove shortcomings immediately. The Contractor, after stopping the specific work, can if felt necessary appeal against the order of stoppage of work to the Engg Incharge within three days of such stoppage of work and the decision of the Engg Incharge in this respect shall be conclusive.

The Contractor shall not be entitled for any damages or compensation for stoppage of work due to safety reasons and the period of such stoppage of work will not be taken as an extension of time for completion of work, nor will it be the grounds for waiver of any part of suppliers liability for timely completion of the works.

The Contractor shall follow and comply with all Safety Rules, relevant provisions of applicable laws pertaining to the safety of workmen, employees, plant and equipment as may be prescribed from time to time without any demur, protest or contest or reservation. In case of any conflict between statutory requirement and Safety Rules referred above, the most stringent clause shall be applicable.

If the Contractor fails in providing safe working environment as per Safety Rules or continues the works even after being instructed to stop work by the Engg Incharge, the Contractor shall promptly pay to the Employer on demand, compensation at the rate of Rs. 5,000/- per day or part thereof till the instructions are complied with and so certified by the Employer. However, in case of accident taking place causing injury to any individual, the provision contained in subsequent paragraph as here below shall also apply in addition to the compensation mentioned in this paragraph.

If the Contractor does not take all safety precautions and comply with Safety Rules as prescribed by the Engg Incharge or as prescribed under the applicable law, to safeguard equipment, plant and personnel the Contractor shall be responsible for payment of compensation to the Employer as per the schedule given below.

If the Contractor does not prevent hazardous conditions which may cause injury to his own employees, employees of other Contractors, or the Employer or any other person at Site or adjacent thereto, the Contractor shall be responsible for payment of compensation to the Employer as per the following Schedule:

Fatal injury or accident causing death.	Rs. 100,000/- per person	Applicable for injury or death to any person whomsoever.
---	--------------------------	--

Major injuries or accident causing 25% or more permanent disability. Rs. 20,000/- per person Applicable for injury or death to any person whomsoever.

* As per prevailing Govt. rules.

Permanent disability shall have the same meaning as indicated in Workmen's Compensation Act. The compensation mentioned above shall be in addition to the compensation payable to the workmen/employees under the relevant provisions of the Workmen's Compensation Act and rules framed thereunder or any other applicable law as applicable from time to time. In case the Employer is made to pay such compensation, the Contractor will reimburse the Employer such amount(s) in addition to the compensation indicated above.

18 .0 FOREIGN PERSONNEL

If necessary for the execution of the works, the Contractor shall bring foreign supervisors for the execution of the Contract at his own cost. The Contractor shall submit to the Employer data on all personnel he proposes to bring into India for the performance of the works under the Contract, at least Sixty (60) days prior to their arrival in India. Such data shall include the name of each person, his present address, his assignment and responsibility in connection with the works, and a short resume of his qualifications and experience etc. in relation to the work to be performed by him.

Any person unsuitable and unacceptable to the Employer, shall not be brought to India. Any person brought to India, and found unsuitable or unacceptable to the Employer shall be immediately removed from Site and repatriated. If found necessary, he may be replaced by other personnel acceptable to the Employer.

No person brought to India by the Contractor for the works shall be repatriated without the consent of the Employer in writing, based on a written request from the Supplier for such repatriation giving reasons for such an action to the Employer. The Employer may give permission for such repatriation provided the Employer is satisfied that the progress of work will not suffer due to such repatriation.

The cost of passports, visas and all other travel expenses to and from India, shall be to the Contractor's account. The Employer will not provide any residential accommodation and/or furniture for any of the Contractor's personnel including foreign personnel. Contractor shall make his own arrangements for such facilities.

The Contractor and his expatriate personnel shall respect all Indian Acts, Laws, Rules and Regulations and shall not in any way, interfere with Indian political and religious affairs and shall conform to any other rules and regulations which the Government of India, and the Employer may establish on them. The Contractor's expatriate personnel shall work and live in close co-operation and co-ordination with their co-workers and the community and shall not engage themselves in any other employment either part-time or full-time nor shall they take part in any local politics.

The Employer shall assist the Contractor, to the extent possible, in obtaining necessary certificates and other information needed by the Government agencies.

ODISHA POWER TRANSMISSION CORPORATION LIMITED

TECHNICAL SPECIFICATION

FOR

SYSTEM DATA

SYSTEM DATA

Sl.No	Description of Technical Parameter	Unit	System			
1	Nominal system voltage	kVrms	400kV	220kV	132kV	33kV
2	Maximum system voltage	kVrms	420kV	245kV	145kV	36.kV
3	Power frequency with stand voltage	kVrms	630kV 520kV	460kV	275kV	70kV
4	Switching surge withstand	kVp				

	voltage (for 250/2500 μ s 1. Line to earth 2. Across isolating gap		1050kVp 900kVp+345 kV _{rms}	Not applicable	Not applicable	Not applicable
5	Lightning impulse withstand voltage 1. Line to earth 2. Across isolating gap	kVp (for 1.2 /50 μ s)	1425kVp 1425kV _p + 240kV _{rms}	1050kVp 1200kV _p	650kVp 750kV _p	170kVp 195kV _p
6	One minute power frequency withstand value	Dry kV _{rms} Wet kV _{rms}	630 610	460 530	275 315	70 80
7	System frequency	Hz	50			
8	Variation in frequency	%	±2.5			
7	Corona extinction voltage		320kV	156kV	105kV	
8	Radio interference voltage		500 μ V at 266KV	500 μ V at 167KV	1000 μ V at 93KV	
9	System neutral rating		Solidly earthed			
10	Continuous current rating		2000A	2000A	1250A	800A
11	Symmetrical short circuit current	kA	63/40	40	31.5	25
12	Duration of short circuit fault current	Second	1	1	1	3
12	Dynamic short circuit current rating	kAp	157.5/100	100	79	62.5kA
13	Air clearances Phase to ground Phase to phase System to system within a phase	meters meters meters meters	3.5 4.2 -	2.1 2.4 -	1.3 1.3	480 530
14	Conductor spacing for AIS layouts Phase to ground Phase to phase	meters meters meters	6.5 7.0	4.5 4.5	3 3	1.5 1.5
15	Design ambient temperatures	°C	50			
16	Pollution level as per IEC-815 and 71		III			
17	Creepage distance	mm	10500	6125	3625	900
18	Maximum fault clearing time	ms	≤100	not exceeding ≤100ms		not exceeding ≤150ms
19	Safety clearances 1. Section clearance 2. Ground clearances(between ground and bottom most part of energised object) 3. Horizontal clearance between the fence and energised object 4. Horizontal clearance between the road centre line	metres metres metres metres	6.5 8 As per I.E. Rules As per I.E. Rules	5 5.5 As per I.E. Rules As per I.E.	4 5 As per I.E. Rules As per I.E. Rules	4 4 As per I.E. Rules As per I.E. Rules

	and energised part of the nearby equipment			Rules		
20	Bay width	metres	27	18	11-13.1	5.5
21	Height of bus equipment interconnection from ground	metres	8	5.5	5	4
22	Height of strung busbar	metres	>15	10.5	8.5	5.5

ODISHA POWER TRANSMISSION CORPORATION LIMITED
OFFICE OF THE SR. GENERAL MANAGER,
CENTRAL PROCUREMENT CELL,
JANAPATH, BHUBANESWAR – 751022.

TECHNICAL SPECIFICATION

FOR

GENERAL METEOROLOGICAL DATA

METEROLOGICAL DATA

Description	Data
Annual mean of maximum monthly average temperature.	50

Annual mean of minimum monthly temperature in °C	5
Average rain fall in mm	1500
Average thunder storms days per year	77days
Design ambient temperature in °C	50
Maximum wind velocity in meter/sec.	50
Maximum relative humidity in %	100
Average relative humidity in %	85
Seismic co-efficient	0.06g Hori 0.01g Vert

ODISHA POWER TRANSMISSION CORPORATION LIMITED

TECHNICAL SPECIFICATION

FOR

DESIGN CLAUSES FOR SUBSTATIONS

DESIGN CLAUSES FOR SUBSTATIONS

TABLE OF CONTENTS

ORISSA POWER TRANSMISSION CORPORATION LIMITED..... 1

1. 0 GENERAL.....	3
2. 0 DESIGN PARAMETERS - OPEN TERMINAL.....	3
3.0 BUSBAR CONSTRUCTION.....	4
3. 0 PROVISION OF EARTH SWITCHES	5
4. 0 INTERLOCKING	5
4.1 General.....	5
4.2 Philosophy.....	5
4.3 Principles.....	6
5. 0 DESIGN PHILOSOPHY FOR PROTECTION, CONTROL AND METERING SYSTEM	6
5.1 Protection Philosophy.....	6
5.2 Control Philosophy.....	7
6. 0 EARTHING SYSTEM.....	7

1. 0 GENERAL

The substation shall adopt switching scheme as shown on the attached single line diagrams. The Contractor shall propose the most economical substation layout that meets the desired degree of operational flexibility, reliability, service continuity and expandability. The contractor shall submit design considerations establishing the above and proposals for the Engg Incharge (Divisional Engr.) approval. The attached drawings are intended to show the basic requirements to be satisfied, i.e. switching arrangement, number of busbars, site location, available area, line termination etc. It is the responsibility of the Contractor to prepare a detailed layout showing the manner in which the various items of equipment offered can be accommodated to best advantage within the available area.

The arrangement shown on the attached drawings may be modified as necessary to accommodate the various items, e.g. different types of disconnector, provided the basic principles are maintained.

The Bidder is at liberty to offer substation arrangements based on significantly different principles where it is considered that these offer economies or technical advantages. It is emphasised, however, that the Bidder's main offer should comply with the principles shown in the attached drawings, other arrangements being submitted solely as alternatives to the main offer.

2. 0 DESIGN PARAMETERS - OPEN TERMINAL

The substation design should be such as to minimise the number of levels of conductors and to ensure that the consequences of a failure of one set of high level conductors are limited to the loss of that circuit and a single busbar section. This principle shall also be applied with regard to earth wire conductors. All materials and equipment for use in the substation shall be suitably rated to meet the site conditions specified in the schedules.

All gantry type structures supporting conductors shall include facilities for ready access to all insulator sets. There shall be permanently attached climbing devices with guard-rails and access to high level beams shall not be possible without proper authorisation. Safety screens shall be provided between adjacent circuits to maintain the specified safety clearances and to prevent accidental access to live circuits.

Vehicle access to permit the transport of major switchgear equipment shall be provided. This shall be achieved without the need to de-energise circuits. Access for vehicles which require the de-energisation of circuits shall be kept to a minimum and avoided wherever possible.

Each substation shall be adequately protected against direct lightning strikes, either by the use of spikes or earth wires located on the substation structures, the use of spikes is preferred. The height, location, and number of spikes or earth wires shall be such as to protect all equipment installed within the substation to a failure rate of shielding from direct lightning strikes of not greater than 0.1 per cent per annum.

Where the connection to the substation is by overhead line, overhead line conductors will be terminated either at the substation gantry structures or to anchor blocks adjacent to the overhead line terminal towers. The overhead line conductors complete with tension insulators, line tee off clamps, and compression fittings (bi-metallic where necessary) shall be supplied and erected under a separate contract. The Contractor shall provide facilities on the gantry structure for the fixing of the tension insulators and arrange branching of conductors in to the sub-station from the transmission line conductors.

The overhead line earth wire will be extended into the substation and the substation gantry structure shall be arranged to receive this.

Where line traps are to be located within the substation, these should preferably be mounted integrally with the coupling capacitor. Should this be impracticable, then the use of post type insulators is preferred to suspension mounting.

Where disconnectors are of the pantograph type, the contact arrangements shall cater for conditions of maximum wind loading coincident with either the maximum or minimum ambient temperature and shall conform to the requirements of IEC 129. The Contractor shall also establish, through calculations, the length of arm of each pantograph isolator so that the contact is proper and robust. The Contractor shall also provide the required size and number of sag compensating springs where necessary.

Sub-station equipment, structures, roads, concrete cable troughs, drains etc.. shall be laid out in a neat and organised manner to meet the employers requirement, facilitate movement of vehicles and ensure safety of personnel and equipment.

Each substation shall be provided with safety grounding mat as per clause relevant clauses of this section. While designing the ampacity of the buried conductor suitable corrosion allowance shall be considered for thirty five (35) years. The conductors shall be buried at a depth of 700 mm from finished formation level. The conductors shall be welded suitably for maintaining a high degree of mechanical rigidity and electrical connectivity.

The substation earth mat shall be designed to provide a ground potential rise within safe limits of tolerable touch and step potential. The margins of limits shall confirm the international practices. The design of earthmat shall be in accordance with IEEE-80/1986 and shall be submitted for Engg Incharge (Divisional Engr.) approval.

3.0 BUSBAR CONSTRUCTION.

Busbars shall be made of aluminium tubes in 400 KV side and connection from equipment to equipment & the top bus shall be twin ACSR Moose conductor. Bus bars of aluminium tube in 220 KV side (wherever specifically asked for) or ACSR conductor (**Main Buses shall be Twin Moose ACSR conductor and Reserve /Transfer Bus shall be single Moose ACSR conductor**) and aluminium tube for connection from equipment to equipment . The bus bar capacity shall be designed for maximum ambient temperature conditions and symmetrical short circuit condition of 63 KA for 400 KV side 40kA for 220 KV & 132 KV side. The continuous current rating shall be so designed that no portion of the bus bar is unduly loaded, or over heated. For EHV sub-stations, the bus bar and bus bar fittings shall be made corona free by the provision of corona rings or corona bells. There shall not be any harmful RIV from the constructed bus bars .

Tubular bus bars shall be mounted on support insulators of adequate strength, mounted on support structures above the ground in upright position, or hang from the structures depending upon the chosen lay out.

Strain bus bars shall be made bundled wherever necessary to carry the rated maximum continuous current. The bundle size shall be determined by the Contractor to make such that it is corona free, and fitted with spacers to limit the snatch forces such that no dangerous tensions are passed on to the structures.

Interconnections to equipment shall be made from aluminium tubes or suitable flexible ACSR conductors, through clamps and connectors only. Jumpers shall be made from flexible ACSR conductors only.

There shall be no conductor joints in a span of strung strain busbars. Tubular busbars shall have a maximum of one welded joint and shall be designed for thermal stresses and linear expansion, due to temperature, so as to relieve the support structure and busbar fittings from stress.

The Contractor shall submit design calculations in support of the various dimensions of the busbar for Engg Incharge (Divisional Engr.) approval.

The busbar deflection in respect of tubular busbars shall not exceed 50% of diameter. The stranded conductor sag shall not exceed 1/80th of conductor span.

3. 0 PROVISION OF EARTH SWITCHES

The earth switches shall be provided liberally in compliance to Indian Electricity Rules and as per latest recommendations of CBIP Manual on EHV substations.

However the Employer's practice is to provide earth switches with disconnecter on busbar side and feeder side of the circuit bay for all voltage class substations. For 400kV class substations earth switches shall also be provided with disconnectors on circuit breaker side. In case the Electrical Inspectorate requires provision of any further earth switches the same shall also be provided by the Contractor.

Additional cost payable on account of providing such earth switches shall be mutually agreed between the Contractor and the Employer on the basis of rates quoted by him for spare parts.

Each substation shall be provided with sufficient number of portable earth switches so as to carry out maintenance works for at least two circuit bays.

4. 0 INTERLOCKING

4.1 General

The applicable recommended interlocking facilities of IEC 517 shall be provided. Padlocking to the requirements of this specification shall be provided for operational and maintenance security.

Earth switches on line circuits shall be capable of interrupting the current induced in the line at the voltage specified in the schedules. This current may arise by induction from a fully loaded line in parallel with the earthed line. If earth switches without the rated breaking capacity are provided, the interlocking arrangements shall ensure the interruption of this induced current by the circuit breaker before the earth switch is opened. Interlocking facilities shall be provided to release the circuit breaker for maintenance whilst maintaining the earthing of the incoming line.

4.2 Philosophy

All disconnecting and earthing devices within the substation shall be interlocked in a manner that ensures that they always operate safely. The system employed shall satisfy two distinct categories:

- **Operational interlocking:** Interlocking associated with normal system operation and switching and intended to ensure that a predetermined switching sequence is satisfied. Such interlocking shall be achieved by electrical means in a manner that permits the equipment to perform any safe operation.
- **Maintenance Interlocking:** Interlocking associated with a series of switching operations to render the equipment or sections of the substation safe for access and maintenance by personnel. Such interlocking shall be achieved by mechanical interference type interlocks.

4.3 Principles

The design of the interlocking scheme shall be based upon the following principles:

- a) Disconnectors are capable of switching the capacitive currents of associated connections.
- b) Circuit breakers shall not be used as a point of safety isolation, this is the function of a disconnector.
- c) Disconnectors have neither load making nor breaking capacity.
- d) Disconnectors are not capable of making or breaking transformer magnetising current.
- e) Disconnectors are capable of the duty imposed when operated under parallel switching conditions.

- f) It shall not be possible to close or open any earth switch unless the point of application is disconnected from all possible sources of supply, and the power operating devices of such disconnectors are selected to the local control position.
- g) It shall not be possible to operate any disconnector unless its associated circuit breaker is open.
- h) It shall not be possible to operate any disconnector if an associated earth switch is already closed.
- i) Disconnectors concerned with supplies from a remote point cannot be fully interlocked and shall carry a warning notice to this effect. Similar notices shall be applied to earth switches.

5. 0 DESIGN PHILOSOPHY FOR PROTECTION, CONTROL AND METERING SYSTEM

5.1 Protection Philosophy.

The control and protection system shall be closely inter related in the sub-station.

The protection system shall be designed for the fault clearing time, so that it prevents or limits damage to primary equipment of the transmission system, and stability of the power system shall be protected. The main protective system shall be capable of tripping (excluding circuit breaker operating time) within 10 - 50ms. However, in any case the fault clearing time from the instant of inception of fault to completion of the circuit breaker operation shall not exceed 100ms for 400kV and 220kV systems, 120ms for 132kV system and 150ms for 33kV system. Operating time of breakers to be provided by the Employer are 40ms for 400kV, 50ms for 220kV, 50 ms for 132kV and 60 to 85ms for 33kV.

The protection system shall generally be a dedicated system organised at bay level for lines, transformers etc., and at sub-station level for bus bar and breaker failure protection .

In the highest range of protection functions the protection unit and function shall be segregated as much as possible. The protection shall not be compromised in any way by the requirements of the other functions. The protection shall be permanently on line and shall be capable of tolerating faults in both the hardware and software at bay level and sub-station level. The system shall be so designed that in the event of loss of communication between the bay level and sub-station level, the continuity of protection function shall be ensured.

The protection sub-system (relays) should communicate with control and monitoring system to provide information regarding operation, faulted phase, settings etc.. Information should also be available at station computer level and for transmission to LDC via SCADA.

The protection system may also include new designs of protective relays incorporated with features such as auto reclosing, fault recording , fault locating and synchronising check.

The recommended protection arrangement for different bays shall be in accordance with the protection single line diagrams attached to this Specification.

Busbar protection systems shall be designed to initiate immediate tripping of all circuit breakers connected to the faulted section of the busbar. In the event of non operation of a circuit breaker of a bay all the circuit breakers connected to the associated busbar shall trip under breaker failure protection.

5.2 Control Philosophy.

The control function of the sub-station shall be the following:

- Control of Operation (switching on or off or position change)
- Control of Monitoring (alarms, annunciation, indication etc.)

The system shall efficiently perform the operation of circuit breakers, isolators, tap changers etc.. It shall also perform the interlocking at bay level as well as substation level. The control system shall be

suitable for operating manually, electrically (remote) and via SCADA system from a remote control centre.

Control shall be achieved at bay level, substation level and remote control centre level through conventional MMI or computer based automated system, as specified in this Specification.

The system shall be designed, along with the communication system so that there shall be high availability of bay protection associated with automatic functions such as auto reclosing. The systems shall function autonomously and independently of adjacent bays, substation functions and units etc.

6. 0 EARTHING SYSTEM

Electrical measurements of the subsoil at various depths up to 20 metres shall be made at the site of each substation in order to determine the layered effects of the ground from which the effective ground resistivity and hence the expected resistance of the proposed earth grid system may be predicted. Wagner's 4 - Electrode method as per IEEE-Std 81 may be followed for measurement of earth resistivity.

The earthing system shall comprise a mesh grid formed by hot dip galvanised iron flat bar (GI flat) of 75 X 10 mm (for 220/132 KV & 132/33 KV) and 40 mm MS rod (for 400 KV) buried directly in the ground and arranged so as to utilise fully the available site area. A continuous conductor shall be laid outside the periphery of the substation site at a distance of two metres from the switchyard fence and at a depth of at least 0.7 metres (the earth mat top shall be at 700 mm below the finished ground level) below the surface. A mesh system shall be formed by interconnection at various points to the perimeter conductor. The distance between two buried earth mat (flat/rod) shall be maximum 5 meters both way. The mesh system shall be designed such that the grid potential rise limits the touch voltage to a value not greater than the maximum tolerable touch potential; the fault clearance time to be used in the earthing calculations shall be taken as one second.

The earthing system shall be designed to meet the requirements of this specification and shall be in accordance with IEEE 80 and IS 3043. The Contractor shall present calculations to show the earthing system meets these requirements and can be shown to be safe in terms of touch, step and transferred potentials. The calculations shall be carried out considering a layer of crushed metals of thickness 100mm and without the same; and if applicable recommend suitable site surfacing. The resistance of the earth mat shall not exceed 0.5Ω .

In the event of the substation resistance obtained with the foregoing installation being of a magnitude unacceptable to the Engg Incharge (Divisional Engr.), then where practicable, the ground area enclosed by the earth system should be increased by installing directly in the ground a GI flat /MS rod conductor in the form of a ring around the site at a significant distance from the boundary fence. Alternatively, earth conductors can be directly buried radially outside the substation perimeter fence. The use of earth plates as current carrying electrodes is not acceptable.

The earthing system shall be designed so as to include all overhead line terminal towers, which shall be earthed by extending the system so as to envelope all towers within the earth system. Each tower shall be bonded directly to the earth system from at least two locations. Structures and masts for lighting and security surveillance equipment shall also be within the perimeter of the earth grid. No fixed low voltage equipment, with the exception of a warning or alarm button and intruder alarms which shall be of the double insulation type, shall be erected outside the perimeter of the earth grid.

Where a metal substation fence is provided, this shall be bonded electrically to the earthing grid on each side at spacing not exceeding $0.25r$ (where r is the equivalent circular plate radius), at points adjacent to each corner and immediately below any overhead line entering or leaving the Site. The location of the mesh conductors shall be such as to enable all items of equipment to be connected to the earth system via the shortest possible route.

Gate posts forming part of the substation fence shall be bonded together with below ground connections and the gates themselves shall be electrically bonded to the posts at two points through flexible braids.

The current density of the earth conductor shall be not greater than $100\text{A}/\text{mm}^2$. Single connections between equipment and the earth system shall carry the total short circuit current, but the cross sectional area of branch connections may be reduced to take account of current distribution in two or more conductors. A distribution of 60 per cent shall be assumed for this purpose, i.e. the cross sectional area of branch connections may be reduced to 60 per cent of the corresponding single conductor.

The earth conductor may be sized as per IEEE 80 and sufficient allowance for corrosion may be taken in to account.

The grid voltage rise under fault conditions shall not exceed 15 kV. If the calculated grid voltage rise exceeds 430V, the local Telephone Authority shall be advised, by the Contractor, of the grid voltage rise and the distance of the 650V contour from the substation grid periphery.

The alternative approach of independently earthing the fence and placing it outside the earth grid area shall only be adopted if the above mentioned procedures prove insufficient or impracticable. The Contractor shall provide calculations to show that this approach produces safe touch voltages at the fence and shall ensure that the fence is isolated from all other buried metalwork.

Metal parts of all equipment, other than those forming part of an electrical circuit, shall be connected directly to the main earth system at two points. For the same the size of the G.I flats shall also be 75X10mm. This is the raiser of the earth to the structures of column, beam and all equipment structures. The arrangement of the mesh earth system shall be such as to minimise the length of these connections.

A separate set of earth electrodes (at least two), GI pipe, perforated, 50mm dia, heavy duty having 3000mm long in a treated earth pit, shall be provided for the earthing for high frequency coupling equipment (CVT etc), surge arresters, IVT, each neutral of the transformers and reactors at a position immediately adjacent to the equipment being earthed in addition to the normal earth connection.

All main members of structural steelworks shall be earthed by GI flat (size 75X10mm) earthing connections being bonded to the steelworks. The Contractor shall be responsible for earthing of the transformers and circuit breakers installed on the substation site as per recommended.

Connections to apparatus and structures shall be made clear of ground level, preferably to a vertical face and protected against corrosion.

Earth bars installed directly into the ground should normally be laid bare and the trench back-filled with a fine top soil. Where the soil is of a hostile nature, precautions must be taken to protect the earth bar.

All exposed joints shall be at a minimum height of 150 mm above floor or ground level.

A facility shall be provided on the earth bar run between the equipment and the base of the structure, comprising a looped copper strip (test link), so as to permit the attachment of portable earth connections for maintenance purposes.

After installation of the earth system the Contractor shall measure the resistance of the substation. The method used shall preferably be the "fall of potential" method, requiring the availability of a local low voltage supply, but other methods using an earth resistance meter will be acceptable in the event of a local supply being unavailable.

The fencing of the switch yard also to be earthed by using G.I flats of size 75X10mm to each post and a continuous earth strip of size 50X6mm shall run all through the fence. The periphery of the switch yard shall be provided with non treated earth pit at a distance of 5 mtrs all along the periphery. The size of the non treated pit conductor shall be 40 mm dia MS rod of length 3000mm. The said earth MS Rod to be placed in earth pit as per standard practice and the pit shall be filled with Bentonite powder mixed with lomy soil at a ratio 1:10. There shall be provision of watering into the earth pits. A pipe of adequate size should run all along the periphery and outlets shall be provided to each pit. The pipe shall be connected to the overhead tank provided on the control room building and proper water control valve should be provided. Contractor shall prepare a detail earthing provision considering as per specification and shall obtain approval from OPTCL and the top of the MS rod shall be welded to the buried earth mats.

ODISHA POWER TRANSMISSION CORPORATION LIMITED

**OFFICE OF THE SR. GENERAL MANAGER,
CENTRAL PROCUREMENT CELL,
JANAPATH, BHUBANESWAR – 751022.**

TECHNICAL SPECIFICATION

FOR

CIVIL WORKS

CIVIL WORKS

TABLE OF CONTENTS

DESCRIPTION	PAGE NO.
1. GENERAL	4

2. SITE CLEARANCE	4
3. STANDARDS	5
4. SOIL INVESTIGATION	6
5. MATERIALS AND WORKMANSHIP	10
6. EXCAVATION AND BACKFILL	12
7. SITE SURFACING	14
8. SITE DRAINAGE	15
9. SEWAGE SYSTEM	17
10. ROADS AND CULVERTS	18
11. AUTO TRANSFORMER / REACTOR FOUNDATION , RAIL TRACK / ROAD CUM RAIL TRACK	19
12. FIRE PROTECTION WALLS	21
13. CABLE AND PIPE TRENCHES	23
14. FOUNDATION DESIGN	26
15. FOUNDATIONS AND R CC CONSTRUCTION	29
16. FENCING	39
17. BUILDING	41
18. MISCELLANEOUS GENERAL REQUIREMENTS	47

19. INTERFACING	48
20. WATER SUPPLY	48
21. STATUTORY RULES	49
22. SECURITY WATCH TOWERS	49
23. SECURITY SHED	49
24. STORE SHED,PLATFORM,RAMP & WINCH	49
25. ANTIWEED TREATMENT	50
26. GARDEN & PLANTATION	51
27. RAIN WATER HARVESTING	52

1. 0 GENERAL

1.1 Scope of work

The scope of Civil works includes the following items.

The scope shall generally cover switch yard structures, including gantries and equipment support structures and their foundations, cable trenches along with covers, cable trench crossings of road and rails, sump pits, marshalling box/control cubicle foundations, switch yard levelling, site clearance, soil investigation, roads, drains, fencing, gravel filling, transformer / reactor foundations, firewalls, control room building, other auxiliary buildings. Any other items, not specifically mentioned here but required for the commissioning of switch yard/substation shall be deemed to be included in the scope of this Specification. The scope shall further cover design, engineering, erection, testing and commissioning of all civil works at each substation. All civil works shall also satisfy the General Technical Clauses specified in other sections of this specification and as detailed below.

Excavation, de watering, carriage of excavated earth, plain cement concrete (PCC), casting of reinforced cement concrete (RCC) foundations, super-structures for switch yard structures, equipment supports, their control cubicles, bus post supports, lighting poles and panels, brick and stone masonry, cable trenches, pipe trenches with necessary pre cast RCC removable covers, with lifting facility and sump pits, cable supports and their embodiment in cable trenches and cable trench crossings road or rail track with backfilling complete as per drawings approved by

the OPTCL, shall be carried out by the contractor. The cable trenches inside the control room shall be provided with MS chequered plate with angle stiffeners at the bottom for mechanical strength and painting there of as per the standard practice.

The Contractor shall furnish all designs, (unless otherwise specified) drawings, labour, tools, equipment, materials, temporary works, constructional plant and machinery, fuel supply, transportation and all other incidental items not shown or specified but as may be required for complete performance of the Works in accordance with approved drawings, specifications and as per direction of the Engg Incharge (Divisional Engr.).

The work shall be carried out according to the design/drawings to be developed by the Contractor, and approved by the Engg Incharge (Divisional Engr.) or supplied to the bidder by the Engg Incharge (Divisional Engr.). For all buildings, structures, foundations etc. necessary layout, levels and details shall be developed by the Contractor keeping in view the functional requirement of the plant and facilities and providing enough space and access for operation, use and maintenance based on the input provided by the Engg Incharge (Divisional Engr.). Certain minimum requirements are indicated in this specification for guidance purposes only. However, the Bidder shall quote according to the complete requirements.

2.0 SITE CLEARANCE

2.1 Clearing and Grubbing

The work shall consist of numbering of trees, removing and disposing of all materials such as trees, bushes, woods, shrubs, grass, stumps, rubbish, rank vegetation, roots, foreign materials, etc., which in the opinion of the Engg Incharge (Divisional Engr.) are unsuitable for incorporation in the works, from within the limits and such other areas as may be specified on the drawings or directed by the Engg Incharge (Divisional Engr.). Clearing and grubbing shall be performed in advance of earthwork operations and in accordance with the requirements of these Specifications. During clearing and grubbing, the contractor shall take all adequate precautions against soil erosion, water pollution etc., and where required undertake additional works to that effect.

2.1.1 Provision of plantation and developing a garden inside the sub-station.

At least, 100 nos. of fruit & 100 nos. flowers bearing plants as per the advice of OPTCL to be planted along the road side and in and around the control room and DG room building after making surface treatment. Also, provision of developing a garden in front of the control room building, the land to be developed shall be of size 30mtrs X 20 mtrs. Garden grass with variety of flowering plants and show plants with croutons are to be provided after making proper surface treatment. Provision of water taps facilities at different locations for watering the plants.

2.2 Setting out and making profiles

After the site has been cleared as per Clause 2.1 above, the limits of excavation shall be set out true to lines, curves, slopes, grades and sections as shown on the drawings or as directed by the Engg Incharge (Divisional Engr.). The Contractor shall provide all labour, survey instruments and materials such as strings, pegs, nails, bamboos, stones, lime, mortar, concrete, etc., required in connection with the setting out of works and the establishment of bench marks. A grid system of co-ordinates shall be established by the Contractor at the site.

Masonry or concrete pillars shall be erected suitably at minimum of four places in the area to serve as bench marks for the execution of the work. Each bench mark shall be protected from damage or disturbance. These bench marks shall be connected with G.T.S. of any other permanent bench mark approved by the Engg Incharge (Divisional Engr.). Necessary profiles

with pegs, bamboos and strings or other means shall be made to show the correct formation levels before the work is started and the same shall be approved by the Engg Incharge (Divisional Engr.).

2.3 Programme

The Contractor shall construct the works in compliance with the outline programme appended to the Bidding Document, and shall submit for the approval of the Engg Incharge (Divisional Engr.) a detailed programme in accordance with the requirements of this Specification.

2.4 Inclement weather

As per relevant Code, during hot weather, precautions shall be taken to avoid premature stiffening of the fresh mix and to reduce water absorption and evaporation losses. During hot weather (atmospheric temperature above 40 degree C) or cold weather (atmospheric temperature at or below 5deg.C) concreting shall be done as per the procedure set out in IS 7861.

3. 0 STANDARDS

All Civil works shall be carried out as per applicable Indian Laws, latest revision of International Standards and Codes. All materials shall be of best quality conforming to relevant Indian Standards and Codes.

Civil works shall be designed to the required service conditions and /or loads as specified elsewhere in this Specification or implied as per National and International Standards.

A list of code of practice and standards used for civil works in general is enclosed for reference. In case of any conflict between I.S. Code and the Procedures specified herein, the later shall prevail.

4. 0 SOIL INVESTIGATION

4.1 General

The Contractor shall perform a detailed soil investigation to arrive at sufficiently accurate general as well as specific information about the soil profile/strata and the necessary soil parameters of the site in order that the foundations of the various structures can be designed and constructed safely and rationally. Foundation systems adopted by the contractor shall ensure that relative settlement shall be as per provision in IS 1904 and any latest IS and other Indian Standards.

This Specification covers all the work required for detailed soil investigation and preparation of a detailed report. The work shall include mobilisation of necessary equipment, provision of necessary engineering supervision and technical personnel, skilled and unskilled labour etc., as required to carry out field investigation and tests, laboratory tests, analysis and interpretation of data and results, preparation of detailed soil report including specific recommendations for the type of foundations and the safe bearing capacity for different sizes of foundations at different founding strata for the various structures of the substation. The Contractor shall make his own arrangements for locating the coordinates and various test positions in field and also for determining the reduced level of these locations with respect to the bench mark. All the test are to be carried out before the OPTCL officials or before any agency engaged by OPTCL. Prior intimation in this effect has to be given to OPTCL.

A report to the effect will be submitted by the Contractor for the Engg Incharge (Divisional Engr.) specific approval giving details regarding his assumed data for Civil structures design.

Any variation in soil data shall not constitute a valid reason for any additional cost and shall not affect the terms and condition of the Contract. Nothing extra what so ever shall be paid to the Contractor on account of any variation in subsoil properties /or conditions. Tests must be conducted under all the critical locations i.e. Control room building, autotransformer, lightning mast, 400 kV/220 kV/132 kV column location etc. However, some of the soil parameters given below for substations have to be determined and submitted to Engg Incharge (Divisional Engr.).

- Dry density
- Bulk density
- Angle of internal friction/cohesion
- * Specific gravity
- Natural moisture content.

4.2 Bore holes

Drilling of a specified number of bore holes of 150 mm dia. in accordance with the provisions of IS 1892 at approved locations to specified depths or to refusal which ever occurs earlier. (By refusal it shall mean that a standard penetration blow count (N) of 100 is recorded for 30 cm penetration). However, at least 3 boreholes shall be drilled to the required depth (15 mts. approximately).

Performing Standard Penetration Tests at approximately 2.0 m intervals in the bore hole starting from 0.5 m below ground onwards and at every change of stratum. The disturbed samples from the standard penetrometer shall also be collected for necessary tests.

Collecting undisturbed samples of 100/75 mm diameter 450 mm long from the bore holes at intervals of 2.5 m and every change of stratum starting from 1.0 m below ground level onwards.

The depth of Water Table shall be recorded in each bore hole.

All samples, both disturbed and undisturbed, shall be identified properly with the bore hole number and depth from which they have been taken. The sample shall be sealed at both ends of the sampling tubes with wax immediately after the sampling and shall be packed properly and transported to the Contractor`s laboratory without any damage or loss.

The logging of the bore holes shall be compiled immediately after the boring is completed and a copy of the borelog shall be handed over to the Engg Incharge (Divisional Engr.).

4.3 Dynamic cone penetration test

Two Dynamic cone penetration tests under the locations of auto transformers shall be carried out with the circulation of bentonic slurry at specified location and a continuous record of penetration resistance (NG) upto 15 metre from natural ground level or refusal, shall be maintained by the Contractor.

Dynamic cone penetration tests are conducted to correlate engineering properties such as stratification density, bearing capacity, settlement, etc., of soils which are primarily cohesive in nature. The tests shall be conducted by driving a standard size cone attached loosely or screwed to a string of drill rods. The specification for the equipment and accessories required for performing this test, test procedure, field observations and reporting of results shall confirm to IS 4968 part 11 latest revision. The driving system shall comprise of 65 kg weight having a free fall of 75 cm. The cone size shall be 65 mm diameter, and provided with vents for continuous flow of bentonite slurry through the cone and rods in order to avoid friction between the rods and soil.

The location for tests shall be as directed by the Engg Incharge (Divisional Engr.). On completion of the test, the results shall be presented as a continuous record as the number of blows required for every 300 mm penetration of the cone into the soil.

4.4 Trial pits

Trial pits shall be made at two locations as approved by the Engg Incharge (Divisional Engr.). The trial pits shall two metres square in size extending to (four) metres depth or as specified by the Engg Incharge (Divisional Engr.). Undisturbed samples shall be taken from the trial pits as per the direction of the Engg Incharge (Divisional Engr.).

4.5 Field California Bearing Ratio test

This test shall be carried out to obtain the properties of soil required for the construction of roads. The equipment and accessories required for carrying out the test, test procedure, recording of observations and presentation of results shall confirm to IS 2770 part XXXI. The test locations of CBR test shall be on the road locations as per GA drawing. These tests shall be performed on remoulded and undisturbed, soaked and un soaked samples.

4.6 Electrical resistivity test.

This test shall be conducted to determine the electrical resistivity of soil required for designing safety grounding system for the entire station area. The specifications for the equipment and other accessories required for performing electrical resistivity test, the test procedure, and reporting of field observations shall confirm to IS 3043. The test shall be conducted using Wagner's four electrode method as specified in IS 1892, Appendix-B2. Unless otherwise specified at each test location, the test shall be conducted along two perpendicular lines parallel to the coordinate axis.

4.7 Plate load test

Plate load test shall be conducted to determine the bearing capacity and load/ settlement characteristics of soil at shallow depths by loading a plane and level steel plate kept at the desired depth and measuring the settlement under different loads, until a desired settlement takes place or failure occurs. The specification for the equipment and accessories required for conducting the test, the test procedure, field observations and reporting of results shall conform to IS 1888. The location and depth of the test shall be given by the Contractor and approved by the Engg Incharge (Divisional Engr.). Undisturbed tube samples shall be collected at 1.0 m and 2.5 m depths from the natural ground level for carrying out laboratory tests.

The size of the pit shall not be less than five times the plate size and shall be taken upto the specified depth. All provisions regarding excavation and visual examination of pit shall apply here.

If the ground water table is at a depth higher than the specified test depth, the ground water table shall be lowered and maintained at the test depth for the entire duration of the test. Dewatering shall be at Contractor's cost.

Unless otherwise specified the reaction method of loading shall be adopted. Settlement shall be recorded from dial gauges placed at four diametrically opposite ends of the test plate. The test plate shall be 600 x 600 mm size and at least 25mm thick. The bottom of the pit shall be levelled before placing the plate in position for conducting the test.

A seating load of 70 gm/sq.cm shall be applied and after the dial gauge readings are stabilised, the load shall be released and the initial readings of the dial gauges recorded after they indicate constant reading. The load shall be increased in stages. These stages shall be 20, 40, 70, 100,

150, 200, 250, 300, 400, 500, 600 and 800 KN per sq.m. or as directed by the Engg Incharge (Divisional Engr.). Under each loading stage, record of time versus settlement shall be kept as specified in IS 1888.

The load shall be maintained for a minimum duration of one hour or till the settlement rate reduces to 0.02 mm/m. whichever is latter. No extrapolation of settlement rate from periods less than one hour shall be permitted.

Loading shall be carried out in stages as specified above till one of the following conditions occurs:

- Failure of the soil under the plate i.e. the settlement of the plate at constant load becomes progressive and reaches a value of 40 mm or more.
- Total settlement of the plate is more than 40mm.
- Load intensity of 800 kN/sq.m is reached without failure of the soil.

Backfilling of the pit shall be carried out as per the directions of the Engg Incharge (Divisional Engr.). Unless otherwise specified the excavated soil shall be used for this purpose. The quoted rates shall include backfilling.

Dial gauge readings for settlement shall generally be taken at 1, 2, 4, 6, 9, 16, 25, 60, 90 and 120 minutes from the commencement of each stage of loading. Thereafter the readings shall be taken at hourly intervals upto a further four hours and at two hours intervals thereafter for another six hours.

4.8 Water sample

Representative samples of ground water shall be taken when ground water is first encountered before the addition of water to aid drilling of boreholes. The samples shall be of sufficient quantity for chemical analysis to be carried out and shall be stored in air-tight containers.

4.9 Laboratory Test

The laboratory tests shall be carried out progressively during the field work after a sufficient number of samples have reached the laboratory, in order that the test results of the initial bore holes can be made use of in planning the later stages of the field investigation and quantum of laboratory tests.

All samples brought from field, whether disturbed or undisturbed shall be extracted/prepared and examined by competent technical personnel, and the tests shall be carried out as per the procedures laid out in the latest edition of the relevant IS Codes and Standards.

The following laboratory tests shall be carried out:

- Visual and engineering classification.
- Liquid limit, plastic limit and and shrinkage limit.
- Natural moisture content, bulk density, dry density and specific gravity.
- Grain size distribution.
- Unconfined compression test.
- Unconsolidated undrained test.
- Swell pressure and free swell index determination.
- California bearing ratio.

- Consolidated undrained test.
- Consolidated drained test.
- Chemical tests on soil and water to determine the carbonates, sulphates, nitrates, chlorides, Ph value, and organic matter and any other chemicals harmful to the concrete foundation.

4.10 Test results and reports

The Contractor shall submit the detailed report in four (4) copies wherein information regarding the geological detail of the site, summarised observations and test data, bore logs, and conclusions and recommendations on the type of foundations with supporting calculations for the recommendations. Initially the report shall be submitted by the Contractor in draft form and after the draft report is approved, the final report in eight (8) copies shall be submitted.

The report shall include, but not be limited to the following :

- A plan showing the locations of an exploration work i.e. bore holes, dynamic cone penetration tests, trial pits, plate load test, etc.
- Bore logs: Bore logs of each bore holes clearly identifying the stratification and type of soil stratum with depth upto the refusal. The values of Standard Penetration Test (SPT) at the depths where the tests were conducted on the samples collected shall be clearly shown against that particular stratum.
- Test results of field and laboratory shall be summarised strata wise as well in combined tabular form. All relevant graphs, charts tables, diagrams and photographs, if any, shall be submitted along with report.
- **Recommendation** The report should contain specific recommendations for the type of foundation for the various structures envisaged at site. The Contractor shall acquaint himself about the type of structures and their functions from the Engg Incharge (Divisional Engr.). The observations and recommendations shall include but not be limited to the following :
 - Geological formation of the area, past observations or historical data, if available, for the area and for the structures in the nearby area, fluctuations of water table, etc..
 - Recommended type of foundations for various structures. If piles are recommended the type, size and capacity of pile shall be given.
 - Allowable bearing pressure on the soil at various depths for different sizes of the foundations based on shear strength and settlement characteristics of soil with supporting calculations for the recommendations.
 - Recommendations regarding slope of excavations and dewatering schemes, if required.
 - Comments on the chemical nature of soil and ground water with due regard to protective measures.
 - If expansive soil is met with, recommendation on removal or retainment of the same under the structure/road etc. shall be given. In the latter case detailed specification of any special treatment required including specification for materials to be used, construction method and equipment to be deployed etc. shall be furnished.
- Recommendations for additional investigation beyond the scope of the present work, if Contractor considers such investigation necessary.

5. 0 MATERIALS AND WORKMANSHIP

5.1 General

All materials used in the works shall be new and of the best quality of their respective kinds. They shall comply with the requirements of the latest edition of any relevant Indian Standard or Code of Practice where such exist, and current at the date of tendering.

All workmanship shall be of the highest standard, and shall be executed by competent men skilled in their respective trades.

5.2 Samples

In addition to the special provisions made in this specification for sampling and testing of materials by particular methods, samples of any materials and workmanship proposed to be used in the Works may be called for at any time during the Contract by the Engg Incharge (Divisional Engr.) and shall be furnished by the Contractor without delay and at the expense of the Contractor. Samples when approved, shall be regarded as the acceptable standard, and any material or workmanship subsequently not complying with that standard shall be rejected and replaced by those of acceptable standard at the expense of the Contractor. Sample storage boxes shall be provided by the Contractor free of cost if requested by the Engg Incharge (Divisional Engr.).

5.3 Tests

Whenever considered desirable by the Engg Incharge (Divisional Engr.), Inspectors may be sent to manufacturer's or subcontractor's premises to test materials or supervise their manufacture.

Where specified or requested the Contractor shall obtain from the manufacturer and send to the Engg Incharge (Divisional Engr.) certificates of test, proof sheets, mill sheets, etc., showing that materials have been tested in accordance with this Specification or the relevant Indian Standard.

Notwithstanding any tests which may be directed to be carried out at a manufacturer's and/or subcontractor's works, the Engg Incharge (Divisional Engr.) may carry out any tests or further tests he considers necessary or desirable after delivery of materials to the Site.

The Contractor shall provide all labour, equipment and facilities necessary for carrying out the tests both in works and on site.

The cost of routine tests required by IS and this Specification shall be borne by the Contractor. The cost of other tests shall be borne in accordance with the Conditions of Contract.

5.4 Names of suppliers and copies of orders

If so required, and before ordering material of any description, the Contractor shall submit for approval the names of makers or suppliers proposed. Copies of orders shall also be submitted if so required. The Engg Incharge (Divisional Engr.) may at any time withdraw his previously given approval to obtaining materials from any maker or supplier should such maker or supplier fail to supply materials of the specified quality or quantity in the requisite time.

5.5 Rejection of materials and workmanship

The Engg Incharge (Divisional Engr.) shall at any time have power to reject materials and workmanship not complying with this Specification or with the approved Drawings. Materials so rejected shall be immediately removed from site and replaced by materials of an approved standard at the expense of the Contractor. Rejected workmanship shall be broken out and

replaced by work of an acceptable standard including the supply of new materials by the Contractor, at the expense of the Contractor, and without delay.

5.6 Explosives and Blasting

All rules under the Explosive Act or other local rules in force shall be fully observed. All blasting works shall be done in accordance with the stipulation contained in IS 4081. Written approval shall be obtained from the Engg Incharge (Divisional Engr.) before explosives are used for excavating foundations in rock and the Engg Incharge (Divisional Engr.) may impose conditions for their use. The Contractor shall be responsible for complying with local regulations concerning the use of explosives and for the safe-keeping and handling of explosives. Proper warning shall be given of all blasting operations. During operations involving the handling or use of explosives, the Contractor shall be responsible for the safety of personnel, Site Works and people or properties in the vicinity of the site. The Contractor shall make good at his own expense any damage caused by the use or mishandling of explosives.

6. 0 EXCAVATION AND BACKFILL

Excavation and backfill for foundations shall be in accordance with the relevant Code. The back fill around the foundations shall be compacted according to Clause 6.7 for Compaction.

Whenever water table is met during the excavation, it shall be dewatered and water table shall be maintained below the bottom of the excavation level during excavation, concreting and backfilling.

When embankments are to be constructed on slopes of 15% or greater, benches or steps with horizontal and vertical faces shall be cut in the original slope prior to placement of embankment material. Vertical faces shall measure not more than one metre in height.

Embankments adjacent to abutments, culverts, retaining walls and similar structures shall be constructed by compacting the material in successive uniform horizontal layers not exceeding 15 cm in thickness, (of loose material before compaction). Each layer shall be compacted as required by means of mechanical tampers approved by the Engg Incharge (Divisional Engr.). Rocks larger than ten centimetres shall not be placed in embankment adjacent to structures.

Earth embankments of roadways and site areas adjacent to buildings shall be placed in successive uniform horizontal layers not exceeding 20 cm in thickness in loose stage measurement and compacted to the full width specified. The upper surface of the embankment shall be shaped so as to provide complete drainage of surface water at all times.

6.1 Rock excavation

The rock to be excavated shall be classified under the following categories :

6.1.1 Ordinary rock

Rock which does not require blasting, wedging or similar means for excavation is considered as ordinary rock.. This may be quarried or split with crowbars or pickaxes and includes lime stone, sand stone, hard laterite, hard conglomerate and reinforced cement concrete below ground level. It will also include rock which is normally hard requiring blasting when dry but can be excavated without blasting, wedging or similar means when wet. It may require light blasting for loosening materials, but this will not any way entitle the material to be classified as hard rock.

6.1.2 Hard Rock

Any rock or boulder for the excavation of which blasting is required, for example quartzite stone, granite, basalt, reinforced concrete (reinforcement to cut through but not separated from concrete) below ground level.

6.1.3 Hard Rock (Blasting prohibited)

This shall cover any hard rock requiring blasting as described in above but where blasting is prohibited for any reason and excavation has to be carried out by chieselling, wedging or any other approved method.

6.1.4 Authority for classification

The classification of excavation shall be decided by the Engg Incharge (Divisional Engr.) and his decision shall be final and binding on the Contractor. Merely the use of explosives in excavation will not be considered as a reason for higher classification unless blasting is clearly necessary in the opinion of the Engg Incharge (Divisional Engr.).

6.2 Excavations for foundations and other purposes

Excavations shall be of the minimum sizes necessary for the proper construction of the works, and excavations shall not be kept open for periods longer than that reasonably required to construct the works. The Contractor shall take all precautions necessary to ensure that the bottoms of excavations are protected from deterioration and that the excavations are carried out in such a manner that adjacent foundations, pipes or such like are not undermined, damaged or weakened in any way. Any excavation taken out below the proper level without approval shall be made good at the expense of the Contractor using concrete or other material as directed.

All excavated materials obtained from excavation shall remain OPTCL's property. The useful portion shall be separated from the useless one and deposited in regular stacks at places indicated and as directed by the Engg Incharge (Divisional Engr.).

6.3 Support of excavations

The Contractor shall be responsible for the stability of the sides of the excavations. Excavations shall be close timbered or sheeted, planked and strutted as and when necessary during the course of the work and shall ensure the safety of personnel working within them. If any slips occur, they shall, as soon as practicable, be made good in an approved manner at the expense of the Contractor. Shoring shall not be removed until the possibility of damaging the works by earth pressure has passed. No payment for shoring or timber left in shall be made, unless agreed in writing by the Engg Incharge (Divisional Engr.).

6.4 Works to be in dry

All excavations shall be kept free from water and the Contractor shall take whatever action is necessary to achieve this. Pumping, well pointing and other means necessary to maintain the excavations free from water shall be at the expense of the Contractor, and carried out in an approved manner.

6.5 Backfill

As soon as possible after the permanent works are sufficiently hard and have been inspected and approved, backfill shall be placed where necessary and thoroughly consolidated in layers not exceeding two hundred (200) millimetres in depth.

On completion of structures, the earth surrounding them shall be accurately finished to the line and grade as shown on the drawings. Finished surfaces shall be free of irregularities and depressions.

The soil to be used for back filling purposes shall be from the excavated earth or from borrow pits, as directed by the Engg Incharge (Divisional Engr.).

6.6 Disposal of surplus

Surplus excavated material not required or not approved for fill or backfill shall be loaded and deposited either on or off site as directed. The Contractor shall not delay disposal of surplus material after receipt of instructions from the Engg Incharge (Divisional Engr.). The contractor shall arrange to transport the excavated earth by mechanical transport, not necessarily on Pucca roads. The soil so transported shall be stacked and levelled neatly and dressed. The location where the soil is to be stacked / disposed shall be as directed by the Engg Incharge (Divisional Engr.).

6.7 Compaction

The method and equipment used to compact the fill material to a density that will give the allowable soil bearing pressure required for the foundations, roads, etc. in each layer of fill material. Each layer of earth embankment when compacted shall be as close to optimum moisture content (OMC) as practicable. Embankment material which does not contain sufficient moisture to obtain proper compaction shall be wetted. If the material contains an excess of moisture, then it shall be allowed to dry before rolling. The rolling shall begin at the edges overlapping half the width of the roller each time and progress to the center of the road or towards the building as applicable. Rolling will also be required on rockfills. No compaction shall be carried out in rainy weather.

At all times unfinished construction shall have adequate drainage. Upon completion of the road's surface course, adjacent shoulders shall be given a final shaping, true alignment and grade.

The density to which fill material shall be compacted shall be as per relevant IS and as per direction of Engg Incharge (Divisional Engr.). All compacted sand filling shall be confined as far as practicable. Backfilled earth shall be compacted to minimum 95% of the Standard Proctor's density at OMC. The subgrade for the roads and embankment filling shall be compacted to minimum 95% of the Standard Proctor's density at OMC

6.8 Requirement for fill material under foundations

The thickness of fill material under the foundations shall be such that the maximum pressure from the footing, transferred through the fill material and distributed onto the original undisturbed soil will not exceed the allowable soil bearing pressure of the original undisturbed soil.

Where compacted fill is required it shall consist of suitable sand, or other selective inorganic material, subject to approval by the Engg Incharge (Divisional Engr.). The filling shall be done with locally available sand. The filled in sand shall be kept immersed in water for sufficient time to ensure compaction, if so desired by the Engg Incharge (Divisional Engr.).

7.0 SITE SURFACING

7.1 Scope of Work

The contractor shall furnish all labour, equipment and materials required for complete performance of the work in accordance with the drawings, specification and direction of the Engg Incharge (Divisional Engr.).

7.2 General Requirement

The material required for site surfacing/gravel filling shall be free from all types of organic materials and shall be of standard approved quality, and as directed by the Engg Incharge (Divisional Engr.).

The Contractor shall furnish and install the site surfacing to the lines and grades as shown in the drawing and in accordance with the requirements and direction of the Engg Incharge (Divisional Engr.). The soil of the entire switchyard area shall be levelled before placing the site surfacing/gravel fill material. After all the structures and equipment have been erected and accepted the site shall be maintained to the lines and grades indicated in the drawing and rolled or compacted by using three ton roller with suitable water sprinkling to form a smooth and compact surface condition, which shall be matching with finished ground level of the switchyard area. After due compaction of the surface of the entire switchyard area shall be provided with plain cement concrete of 75 mm thickness after proper compaction, and antiweed treatment having cement concrete ratio 1:4:8. Care shall be taken for proper gradient for easy discharge of storm water.

After the PCC is applied and surface prepared to the required slope and grade a base layer of uncrushed/crushed broken gravel of 20 mm nominal size shall be spread, rolled and compacted by using 1/2 ton roller (30" width and 24" dia) with 4 to 5 passes and water sprinkling to form a minimum 50 mm layer on the designed finished formation level of the entire switchyard area.

As a final surface course minimum 50 mm. uniform layers of un crushed /crushed broken metals (gravel) of 20 mm. nominal size shall be spread over the base layer/course. This final surface course shall be applied in all areas exclusive of roadways and shall extend beyond the fenced area as indicated in the drawing. This surface course shall then be compacted by light roller using 1/2 ton steel roller (width 30" x dia 24") and 4 to 5 passes or any other means with water sprinkling as directed by the Engg Incharge (Divisional Engr.). Water shall be sprinkled in such a manner that bulking does not take place. The 20 mm. nominal size (for both layers) shall pass 100% through IS sieve designation 37.5 mm and nothing through 16.0 mm. IS sieve.

In areas that are considered by the Engg Incharge (Divisional Engr.) to be too congested with foundations and structures for proper rolling of the site base course material by normal rolling equipments, the material shall be compacted by hand, if necessary. Due care shall be exercised so as not to damage any foundation structure or equipment during rolling or compaction.

Engg Incharge (Divisional Engr.) by no means shall relieve the contractor of their contractual obligations as stipulated in General and Special Conditions of Contract.

7.3 Measurements

7.2.1 Payment of gravel filling

The measurement shall be based on square metre of finished area of minimum specified compacted thickness of 100 mm above finished ground level. Nothing shall be paid extra for any

additional material labour etc. used for achieving the specified compacted thickness of 100 mm. above finished ground level.

8. 0 SITE DRAINAGE

8.1 General

Adequate site drainage system shall be provided by the Contractor. The Contractor shall obtain rainfall data and design the storm water drainage system, (culverts, ditches, drains etc.) to accommodate the most intense rainfall that is likely to occur over the catchment area in one hour period on an average of once per ten years. The surfaces of the site shall be sloped to prevent the ponding of water.

The maximum velocity for pipe drains and open drains shall be limited to 2.4m/sec and 1.8m/sec respectively. However, minimum non silting velocity of 0.6m/sec shall be ensured. Longitudinal bed slope not milder than 1:1000 shall be provided.

For design of RCC pipes for drains and culverts, IS 456 and IS 783 shall be followed.

The Contractor shall ensure that water drains are away from the site area and shall prevent damage to adjacent property by this water. Adequate protection shall be given to site surfaces, roads, ditches, culverts, etc., to prevent erosion of material by water.

The drainage system shall be adequate without the use of cable or pipe trenches.

For pipe drains, concrete pipes of class NP2 shall be used. However, for road crossings higher strength pipe of class NP3 shall be provided. For rail crossings, pipes conforming to railway loading standards or at least NP4 class shall be provided. Manholes shall be provided at 30 m intervals, at connection points and at every change of alignment. All manholes deeper than 1.2 m shall be provided with galvanised M.S. foot rests. Foot rests shall be of 20 mm M.S. square bars.

Open surface drains shall comprise walls with bricks of class designation 75 in cement mortar 1:4 and 100 mm thick bed concrete of grade 1:3:6, and surface with 12 mm thick cement plaster 1:4 with a floating coat of neat cement on the drain bed and exposed sides. Design and drawings shall have the approval of the Engg Incharge (Divisional Engr.). For expansive soils, the guide lines of IS 9451 shall be followed.

In general, all plant effluent drainage shall be through buried concrete pipes and all storm water drainage shall be through open drains/pipe drains. Open storm water drains shall be provided on both sides of the roads and shall be designed to drain the road surface as well as all the free and covered areas.

Pipe drains shall be connected through manholes at an interval of maximum 30 m. Plant effluents shall be suitably treated by the Contractor to meet all the prevalent statutory requirements and local pollution control norms and treated effluents shall be conveyed to the storm water drainage system at a suitable location for their final disposal.

Invert of the drainage system shall be decided in such a way that the water can easily be discharged above the High Flood Level (HFL) outside substation boundary at suitable location and approved by Engg Incharge (Divisional Engr.). Pumping of drainage water, if required, shall be provided by Contractor.

All internal site drainage systems, including the final connection and disposal to Engg Incharge (Divisional Engr.) acceptance points shall be part of Contractor's scope including all required civil work, mechanical and electrical systems. The Contractor shall connect his drain(s) at one or more points.

Precast manholes shall be preferred against cast-in-situ type. The drainage scheme may either employ open drain system or underground pipe system or a combination of both. A man hole shall be provided at every turn or corner in case of underground type in addition to the normal requirement.

Suitable pumping arrangement shall be provided by the Contractor to pump out the water from sump to the open channel; automatic float valve type pump shall be provided and installed by Contractor.

The Contractor shall locate the outfall point outside the substation vicinity and the substation storm drainage must be connected to this point.

The drainage scheme and associated drawings shall be subject to approval of the Engg Incharge (Divisional Engr.).

8.2 Excavation and backfill

Trench excavations for drains shall be carried out with the minimum disturbance to adjacent ground and in such a way that existing or new work shall not be undermined. No backfill shall be placed until pipes, etc. have been inspected, tested and approved. Backfill shall be carefully placed by hand tools round pipes, etc. and rammed in layers not exceeding one hundred (100) millimetres thick in a manner which will not cause damage. When a minimum thickness of three hundred (300) millimetres above the pipes has been so placed, normal methods of backfilling and ramming may be adopted.

8.3 Laying Of Pipes

Pipes and fittings shall be of the types, qualities and sizes specified and shown on the approved drawings. They shall be laid to the lines and levels shown, and the barrel of each pipe shall bear firmly and uniformly on the trench bottom or prepared foundation bed, any projections in the trench bottom which could cause damage to pipes being first removed. Pipes shall be kept clean during and after laying, and open ends shall be provided with the temporary plugs to prevent entry of foreign matter. Each pipe shall be accurately bonded to gradient between sight rails and drain. Laying shall commence at the lowest end and proceed uphill. Pipes shall be laid with the sockets leading uphill.

8.4 Testing of drains

All drains, other than open channels, stone filled drains and porous drains, shall be of watertight construction, and all soil drains shall be subjected to a water test before backfilling of trenches is commenced. Drains may be tested in sections, and manholes may be tested separately. The Contractor shall submit to the Engg Incharge (Divisional Engr.) for approval his proposals for testing. The drains shall withstand, without leakage, a water pressure of not less than one and one half (1.5) metres at any point for a period of 20 minutes or such other time as the Engg Incharge (Divisional Engr.) may direct. All necessary plugs, temporary connections and other equipment and all labour required for the tests shall be provided by the Contractor and at the expense of the Contractor. For testing of pipes in areas where an adequate supply of water is not readily available, the Engg Incharge (Divisional Engr.) will accept an air (smoke) pressure test, provided that the method of testing is approved by the Engg Incharge (Divisional Engr.). Further testing may be called for after backfilling of trenches to ensure that pipes have not been damaged during that operation.

8.5 Regulations

The regulations and recommendations of any relevant drainage or sanitary authority shall be fully observed, and the Contractor shall be responsible for acquainting himself with any such regulations.

9.0 SEWAGE SYSTEM

A sewage system shall be provided for all utility buildings including the Control room building and other auxiliary buildings.

The Contractor shall construct suitable septic tank and soak pit for the discharge of effluents.

Sewers shall be designed for a minimum self cleansing velocity of 0.6m/sec and the maximum velocity shall not exceed 2.4m/sec.

The sewage system shall consist of all necessary piping, pumps, if required, fittings, manholes, clean - outs, piping connections and all other materials required for safe and efficient sewage collection. Sewer pipes and fittings shall conform to the relevant Indian Standards.

Cast iron pipes shall be used below ground level for sewage disposal.

Manholes shall be provided at every 20 metres along the length, at connection points, and at every change of alignment, gradient or diameter of a sewer pipe line.

10.0 ROADS AND CULVERTS

The Contractor shall be responsible for constructing approach roads, sub-station roads and service roads etc. within the substation area. Layout of the roads shall be based on general details and arrangement drawings for the substation. Parking areas shall be provided for Site personnel and a minimum of twenty numbers of visitors at convenient locations. Adequate turning space for vehicles shall be provided and bend radii shall be set accordingly. Roads to the transformer bays shall be as short and straight as possible. Where the substation layout warrants headroom safety barriers shall be installed to prevent vehicles coming into contact with overlying conductors. Such barriers shall be included as part of the scope of the work.

All substation roads shall be constructed so as to permit transportation of all heavy equipment. A minimum seven metres black topping with 1.6 m wide shoulders on either side of the road shall be constructed for double lane roads. The other service roads shall be with 3.75 m black topping and 1.3 m wide shoulders on either side of the road.

Finished top (crest) of roads shall be a minimum of 300 mm above the surrounding grade level (Formation level).

Road construction shall be as per Indian Road Congress (IRC) standards.

Adequate provision shall be made for road drainage.

All culverts and allied structures required for road/rail, drain, trench crossings etc. shall be designed for class AA loading as per IRC standard.

All roads shall be designed for class 'E' of traffic i.e. traffic intensity of 450-1500 vehicles per day (heavy vehicles exceeding 3 tonnes laden weight) as per IRC-37-1984, Guide-lines for the design of flexible pavements.'

California Bearing Ratio (CBR) method shall be followed for the design of roads. A detailed CBR test which is an adhoc penetration test shall be carried out as per the procedure outlined in IS 2720 (Part XVI).

The surface of the hardstanding shall be laid with falls to the drainage system. Care shall be taken during the construction that no materials enter the drainage system.

At the junction of the hard standing and roads due to different thickness of foundations, precautions shall be taken to ensure that sub-surface drainage from the hard standing does not have a detrimental affect upon the road foundations.

A) CONCRETE ROAD:

All the roads except the main, approach and periphery roads shall be of concrete road. The side shoulder of all the roads shall be with kerb stone at two sides. The kerb stones shall be painted yellow and black alternatively. In case of switch yard road (concrete road) the shoulder would be compacted earth 600 mm wide on the sides of the road. The concrete road shall have 100 mm thick PCC (1:2:4 nominal ratio). Below it 100 mm thick PCC (1:4:8) shall be provided. 300 mm thick water bound macadam (WBM) in three equal layers of 100 mm each at the bottom.

PCC and WBM shall extend upto the shoulder width on both sides of the road outside switch yard area as per drawing. In case of road within the switch yard area the PCC and WBM shall be placed only up to the width of the road. Polythene sheet of 125 microns shall be placed between the RCC and PCC slab. Expansion joints (12mm thick) shall be provided at every 8 mtrs. In addition, in case of 7 mtrs wide roads 100 mm Dia hume pipe (NP-3) shall be provided at every 100 mtrs interval across the length of the road for cable crossing.

B) BITUMINOUS ROAD:

The approach road, main road, periphery road and colony road shall be bituminous type. The following procedure shall be followed for the construction of bituminous roads.

1. Compacted WBM at the bottom end of the road up to a thickness of 300 mm in three equal layers 100 mm each. The compaction shall be done by laying stone aggregates of size 100mm. Each layer shall be laid and compacted with water spreading and using rollers as per the standard practice adopted in the CPWD guide line.
2. Above, the compacted WBM 1st layer as stated under (1), 200 mm thick consolidated WBM in two layers with stone aggregates of size 90 to 45mm shall be laid. Each layer shall be laid and compacted with water spreading and using rollers as per recommended.
3. Above the compacted 2nd layer of WBM, 75 mm thick consolidated WBM in two layers with stone aggregates of size 63mm-45mm shall be laid. Each layer shall be compacted with water spreading and using rollers as per recommended.
4. Above the compacted 3rd layer of WBM, 75 mm thick consolidated WBM in two layers with stone aggregates of size 53mm-22.4mm shall be laid. Each layer shall be compacted with water spreading and using rollers as per recommended.
5. Above the 4th layer of compacted WBM, 25mm thick pre mix carpet surfacing has to be done. The carpet surfacing shall be done with 2.25 cum and 1.12 cum of stone chippings of 13.2 mm size and 11.2 mm size respectively per 100 sq mtrs and 52 Kgs of hot bitumen per cum of stone chippings. Complete with paving ASPHALT 80/100 heated and thin mixed with solvent @70g/Kg of ASPHALT. Hot bitumen of grade 80/100 shall be spread on road surface @750g/Kg per sqmtr. There shall be shoulder on both side of the roads as per given data. The curvature of the road shall be R=7M and additional metalling for turning has to be maintained. The shoulder shall also be made compacted morrum filling and other as specified.

1.1 Periphery roads out side the fencing:

Periphery roads to be constructed out side the fencing. The width of the road is 3.5 mtrs having borm of 1 mtr each at both sides of the roads. The roads shall be bitumen grading and as per Indian Road congress standards.

1.2 The width and type of other roads are:

- a) Bituminous road:-Approach and main roads shall be 7 mtr wide with both side shoulder of 1.75 mtrs. The roads shall be of bitumen grade type.
- b) Other roads shall be (peripheral and colony) 3.75 mtrs width having shoulder of 1.3 mtr at both the side. The roads shall be of bituminous type.

11. 0 AUTO TRANSFORMER / TRANSFORMER/REACTOR FOUNDATION, RAIL TRACK / ROAD CUM RAIL TRACK

11.1 General

The Contractor shall provide a permanent transfer track system integrated with the auto transformer foundation to enable installation and the replacement of any failed unit with a spare unit. The transfer track system shall be suitable to permit the movement of any failed unit fully assembled (including OLTC, bushings) with integral radiators and oil, without the de-energization of any other equipment in the station. The system shall enable the removal of any failed unit from its foundation to a repair area and the installation of a spare unit. The system shall not interfere with the normal internal road and trench system. If trench or drain crossings are required then suitable R.C.C culverts shall be provided in accordance with IRC Code and /or relevant IS.

Rail tracks shall be of RCC, M20(1:1.5:3 mix) grade. The space between the tracks shall be suitably filled with local sand and 75 mm thick PCC of grade 1:3:6 placed over sand filling. The top of PCC shall be up to the formation level. In case of road cum rail track, 75mm thick PCC of grade 1:1.5:3 shall be placed up to the road level. Suitable drainage system between the tracks shall be provided.

The rails shall be first quality 52 kg/m medium manganese steel as per Indian Railway specification T-12-64 and its subsequent revision, joined together by fish plates as per Indian Railway specification T-1/57, and 27 mm diameter fish bolts.

A pylon support system shall be provided for supporting the fire fighting system by the Contractor.

For design of foundation for transformer refer the weightage of the transformer indicated in the BPS (civil works)

11.2 Oil Recovery System

11.2.1 General

An oil recovery system shall be provided for all transformers (containing insulating oil or any flammable or polluting liquid) in order to avoid spread of fire by the oil, and for environmental protection.

11.2.2 Description

Each auto transformer/transformer including oil conservator tank and cooler banks etc. shall be placed in a transformer pit surrounded by retaining walls (pit walls). The clear distance of the retaining wall from the transformer shall be 20% of the transformer height or 0.8 m whichever is greater. The transformer pit thus formed shall have a capacity equal to volume of oil, usually 125%, in the transformers. The MS grating placed at the formation level shall be covered with 100mm thick gravel of 40 mm nominal size which acts as an extinguisher for flaming oil. The bottom of the pit shall have a uniform slope towards the sump pit.

Each transformer pit shall be drained towards a common sump pit whose role is to recover the infiltrating water and the drained oil from of the pit. The sump pit shall have sufficient capacity to receive, without overflowing, the oil content of large transformers plus the water content of any fixed fire fighting system and a certain quantity of rain water collected from the pit connected to it. The system shall be provided with air vents large enough to avoid over-pressure during operation. The whole internal surface of the sump pit should be impermeable.

11.2.3 Materials

The retaining walls which make up the transformer pit shall be made of fire resistant material such as reinforced cement concrete, fire brick etc., and shall be impervious to oil.

The minimum height of the retaining walls shall be 15 cm above the finished level of the ground to avoid ingress of water from outside.

The floor of the transformer pit shall be of plain cement concrete of concrete grade 1:2:4

11.2.4 Drainage

A device showing level of sump pit shall be fitted along with an automatic pumping system which shall have sufficient capacity to evacuate the fire fighting and rain water from the sump pit. The water/oil separation and drainage scheme shall be provided as described in the paper (23-07/1972 Cigre Session) presented by working group 23.04 regarding oil pollution. The Contractor may propose an alternative better scheme, which will be subject to the approval of the Engg Incharge (Divisional Engr.).

11.2.5 Particular Specification

If the height of the retaining walls which form the transformer pit exceed 60 cm, steps shall be provided to facilitate access to the transformer or auto transformer and reactor

When designing the transformer pit, the movement of the auto transformer must be taken into account.

It must be assured that the coefficient of crushed stone (granular material) penetration which fills the transformer pit will be retained regardless of the climatic conditions.

12. 0 FIRE PROTECTION WALLS

12.1 General

Fire protection walls shall be provided in accordance with Tariff Advisory Committee (TAC) recommendations.

12.2 Application criteria

A fire wall shall be erected between the transformers and or the reactors if the free distance between the various pieces of equipment is less than 10 m, to protect each one from the effects of fire on another.

Fire walls shall also be erected between the transformers, reactors, and auxiliary services transformers if the free distance is less than ten metres.

12.3 Fire resistance

The fire wall shall have a minimum fire resistance of three hours. Partitions which are made to reduce the noise level of the transformers shall have the same fire resistance where they are also used as fire walls. The walls of buildings which are used as fire walls, shall also have a minimum fire resistance of three hours.

Fire walls shall be designed in order to protect against the effect of radiant heat and flying debris from an adjacent fire. The column of the fire walls shall be type RCC, M20 (1:1.5:3 mix).

12.4 Mechanical resistance

Fire walls shall have the mechanical resistance to withstand local atmospheric conditions. If the wall is intended to serve as a support for equipment such as insulators etc., its mechanical rigidity must be increased accordingly.

Connecting the walls by steel or other structures, which may produce a reversing torque if overheated, shall be avoided.

12.5 Dimensions

Fire walls shall extend at least two metres on each side of the power transformers or reactors and at least one metre above the conservator tank or safety vent.

These dimensions might be reduced in special cases, and if TAC permits so, where there is lack of space. A minimum of two metres clearance shall be provided between the equipments e.g. reactors, transformers and fire walls.

Building walls which act as fire walls shall extend at least one metre above the roof in order to protect it.

12.6 Materials

Fire walls may be made of reinforced concrete (M20 grade), fire brick, concrete blocks or corrugated iron on a steel structure as per the system requirements. Materials used must conform to the standards of the National Fire Prevention Association and TAC norms.

12.7 BOUNDARY WALL/COMPOUND WALL:

The scope includes the design, engineering and construction of the boundary wall all along the property line of the OPTCL on each sub-station.

The one and half brick wide boundary shall be constructed to a height of 2 mtrs above finished ground level of the substation area and below virgin soil a minimum of 900 mm depth. Galvanised barbed wire fencing shall be provided on top of the boundary wall to a height of 0.5 mtr. G.I Barbed wires(12 SWG) of 3-rows each limb of Y shaped frame (Total 6 nos) shall be provided . A minimum length of 300 mm (bottom portion of the Y shaped frame) shall be grouted and a clear height of 500 mm from the finished portion of the top of the wall shall be maintained

for the Y shaped frame with GI barbed wires. A 50mm height of finished concrete (ratio 1:2:4) shall be provided on the top of the boundary wall.

A) The below mentioned brick works is for construction of pillar where the Y shaped frame shall be grouted.

Inside the Virgin soil:-

The masonry work in foundation and plinth shall be done in 1:5 cement mortar above a layer (height of 75mm and width of 900 mm as per requirement) of cement concrete 1:3:6.The Brick work shall be as per below.

- 1) First layer above the PCC of 75 mm: Height: 300mm & Width: 750 mm (as per requirement)
- 2) Second layer above first layer brick: Height: 300mm & Width: 625 mm (as per requirement)
- 3) Third layer above second layer brick: Height: 300mm & Width:500 mm (as per requirement)

Above ground level:

- 1) DPC of 50 mm above the third layer of Brick work.
- 2) Brick work of thickness of 375 mm having height of 2 mtrs.

B) The below mentioned brick works is for the walls.

Inside the Virgin soil:-

The masonry work in foundation and plinth shall be done in 1:5 cement mortar above a layer (height of 75mm and width of 775 mm as per requirement) of cement concrete 1:3:6.The Brick work shall be as per below.

- 1) First layer above the PCC of 75 mm: Height: 300mm & Width: 625 mm (as per requirement)
- 2) Second layer above first layer brick: Height: 300mm & Width: 500 mm (as per requirement)
- 3) Third layer above second layer brick: Height: 300mm & Width: 375 mm (as per requirement)

Above ground level:

- 1) DPC of 50 mm above the third layer of Brick work.
- 2) Brick work of thickness of 250 mm having height of 2 mtrs.

The masonry work in super structure shall be done with 1:6 cement sand mortar, above 50 mm thick layer of DPC at plinth level. Expansion joint shall be provided at 30 mtr interval of the boundary wall.

The even face of the brick work shall be plastered with 12mm thick in 1:6 cement sand and uneven face shall be plastered with 18mm thick in 1:6 cement sand (in two layers) above the ground level.

Both faces of the walls shall be provided with two coats of cement painting (weather proof) using approved quality of cement paint.

The δYö post shall be galvanised one. The Y shape GI frame shall be grouted on the top of wall inside a pocket of size 100 Sq mm X 300 mm deep with !:2:4 Cement concrete. The size of the GI angle shall be 50X50X6 mm. The height of the Y shaped frame shall be

Boundary shall have one main gate as per stipulation elsewhere in the spec. The gate shall be supported by gate pillars of RCC (1:1.5:3).A separate wicket gate shall be provided adjacent to the main gate.

In case the stability of the boundary wall as mentioned is not suitable for the soil, the bidder has to consider for putting RCC(1:1.5:3) tie beam to be rested on the RCC pillars. The size of the beam and pillar has to be carried out as per the soil condition for proper stability of the boundary walls.

12.8 CABLE AND PIPE TRENCHES

12.8.1 General

Cable trenches and pre-cast removable RCC covers (with lifting arrangement) shall be constructed using RCC of M20 grade.

The cable trenches shall be designed for the following loads.

- Dead load of 155 kg/ m length of cable support plus 75 kg on one tier at the end.
- Triangular earth pressure plus uniform surcharge pressure of 2 tonnes per sq.metre.
- Cable trench covers shall be designed for (i) self weight of top slab plus concentrated load of 200 kg at centre of span on each panel and a surcharge load of 2 tonnes per sq. metre.

Cable trench crossings of road and rails shall be designed for class AA, class A and class 7OR loading of IRC or relevant IS Code and should be checked for transformer loading.

Trenches shall be drained. Necessary sumps be constructed and sump pumps shall be supplied. Cable trenches shall not be used as storm water drains.

The top of trenches shall be kept at least 250 mm above the finished ground level. The top of cable trench shall be such that the surface rain water does not enter the trench.

All metal parts inside the trench shall be connected to the earthing system.

Cables from trench to equipments shall run in hard conduit pipes(GI pipe and necessary G.I bends and sockets)

A suitable clear gap shall be maintained between trench walls and foundations.

A clear (vertical) space of at least 300 mm shall be available for each tier in cable trench. From trench bed to lowest tier, a minimum clearance of 200 mm shall be available for one tier trench and 300 mm for trenches having more than one tier. The spacing between stands shall be 400mm.

The trench bed shall have a slope of 1/500 along the run and 1/250 perpendicular to the run.

All construction joints of cable trenches i.e. between base slab to base slab and the junction of vertical wall to base slab, as well as from vertical wall to wall, and all expansion joints shall be provided with approved quality PVC water stops of approximately 230 x 5 mm size for those sections where the ground water table is expected to rise above the junction of base slab and vertical wall of cable trenches.

Cable trenches shall be blocked at the ends if required with brick masonry in cement sand mortar 1:6 and plaster with 12mm thick 1:6 cement sand mortar.

Cable tray supports(all galvanised structures) shall be designed and constructed to be a single complete fabrication or assembly such that every layer of the horizontal cable tray supports are fixed, either bolted or welded, to a vertical steel support that is embedded in the concrete wall of the cable trough. It shall not be permitted to embed a horizontal support beam directly into the wall of the trough in order to use the concrete wall as a means of load bearing.

Concrete troughs shall be provided with concrete covers of suitable load bearing strength. Where the cable troughs are run across or within 3 m of substation roads, the trough covers shall be capable of bearing an accidental wheel load of 20 kN.

MORE ON CABLE TRENCH.

All the cable trenches shall be RCC type with mixing ratio 1:1.5:3. The size of MS rod to be used for the same are of 8mm tor and 6mm. All the vertical rod shall be 8 mm continuous and the wall and raft shall contain 2 nos 8 mm rods at two layers and spacing shall be 150mm. The horizontal binders shall be of 6mm rod two nos in two layers and to be placed at 200mm centre to centre for both on the wall and raft portion of the trench. The mentioned rod placements are for section 1-1, 2-2, and 3-3. For section 4-4 instead of two 8mm and 6mm rods single rods can be used.

A frame of hot dip galvanized angles of size 50X50X6 mm having provision of MS chairs on the grouting side on to the walls of the trench preferably at two locations(at top and bottom) of the frame (these chairs have to be welded with the rods of the wall for better rigidity). For section 1-1 there shall be of 4 tier mechanism for fixing of cable tray having width of the angle 450mm (3 nos) and the top angle shall be of 300 mm, and the quantity of such type of frame shall be 2 (for both way). For section 2-2 only one frame of the above mentioned one shall be used. For section 3-3 there shall be one frame but with three tier mechanism for fixing the cable trays. For section 4-4 two tier system of angle width shall be 200 mm width at the bottom and 100 mm width at the top. Fixing of the cable tray support stand (Frame) is to be fixed at a distance of 1 mtrs from one frame to the other.

The thickness of the RCC wall of the trench shall be 100mm and thickness of the raft shall be 75mm. All the frames for fixing of cable trays shall be of hot dip galvanized. A running earth strip has to run all through the cable trench for proper earthing of the cable trays and stand (frame). The size of the earth strip is of 50X6mm G.I flats. Welding the GI flats to the frame to be carried out. Earthing strips to be welded with the running earth mat at 10mtrs interval

The bidder also to supply and fix G.I perforated cable trays (of thickness 2mm) of appropriate size before laying of cables on the cable tray stand.

The other dimensions of the cable trench are as below.

Sl No	Section	No of tiers in each frame/ and no of such frame	Gap between the two angles in mm	Inside clearance in mm		Outside clearance in mm		Concrete thickness in mm	
				Top to	Wall to	Top to bottom	Raft width	Wall	Raft

				Bottom	wall	of wall			
1	1-1	Four tiers/Two (both way)	200	1275	1400	1350	1750	100	75
2	2-2	Four tiers/single(one way)	200	1275	900	1350	1450	100	75
3	3-3	Three/single	200	1075	900	1150	1450	100	75
4	4-4	Two/single	200	545	250	620	350	100	75

The covers of the slab are also of RCC with ratio mixing 1:1.5:3. The thickness of the slab shall be 75mm for section 1-1 (MS Rods to be used 10mm & 8mm), section 2-2, 3-3 shall be 60mm (MS Rod to be used 8mm) and section 4-4 shall be 50mm (MS Rods to be used 8mm & 6mm). The MS rods to be used shall be placed at 100 mm centre to centre both way and properly binded. The cover slab shall have provision of lifting hooks at two points for easy lifting of the slabs. Slabs having lifting hooks shall be placed at every 10th slabs. The lengths of the cable trench cover slabs are as below.

Section	Length of the slab	Thickness of the slab
1-1	1600mm	75mm
2-2	1100mm	60mm
3-3	1100mm	60mm
4-4	400mm	50mm

The covers for the cable trench inside the control room shall be provided with MS chequered plate with MS angle stiffeners at the bottom for proper mechanical strength.

12.9 Excavation

Excavation for cable ducts shall generally be carried out in accordance with Clause no. 6.2 of this specification.

12.10 Back fill

Except where ducts are to be encased in concrete, sand is to be packed and well tamped round the duct until it is covered to a depth of 75 mm above the upper surface of the duct. Filling above this level is to be with suitable excavated material free from large stones. In multiple duct runs the interstices between the ducts are to be filled with sand and compacted. A cover of 75 mm above the uppermost ducts shall be maintained. The sand used shall be the same quality as approved for use in making concrete.

12.11 Laying of ducts

Telephone and electrical cable ducts shall be laid and jointed in accordance with the Manufacturer's instructions.

12.12 Multiple runs to ducts

Electrical cable ducts in multiple runs whether encased in concrete or not, shall be laid at approved centres vertically and/or horizontally. The minimum concrete encasement where required is to be 150 mm. The final jointing of ducts in multiple runs shall be done in the trench, i.e. the duct shall be lowered and jointed singly not in groups, and duct joints shall be staggered by approximately half the duct length in alternate lines.

12.13 Cutting of ducts

The Contractor shall carry out any necessary cutting of pipe ducts according to the requirements of the work. Except where ducts enter the cable trench at an angle, they shall be cut at right angles to the length of the duct. The inside edges of cut ducts shall be thoroughly rounded off or so dressed before being placed in position so that there can be no possibility of damage to cables from the edges of the ducts. All electrical ducts entering draw pits shall be provided with suitable bellmouths.

12.14 Cleaning and testing of ducts

On completion of all electrical cable ducting, two mops of appropriate size connected one to each end of an iron mandrel shall be passed twice through each way to clean the conduit and to remove any foreign matter which may have entered. If any obstruction or other defect be discovered it shall be removed or rectified forthwith.

12.15 Sealing of electrical ducts

As soon as every duct or set of ducts has been proved and its draw wire material installed, the ends of the cut or its bellmouth where provided, shall be sealed to a depth of 5 mm with an appropriate sealer, and a single coat of bitumastic paint shall then be applied over the end of the ducts and the seal. The length of draw wire installed shall be such that at least one metre of draw wire extends from each end of each duct. After the ends of ducts have been sealed the free ends of draw wires shall be neatly coiled.

12.16 Concrete cable and pipe trenches

In-situ concrete trenches are to be provided inside and outside the Substation. The trenches are to have falls in the floor and must be drained at regular intervals.

All trenches must have trench covers suitable for their location and loading. Any beams or supporting covers must be as shallow as possible to avoid interfering with the pipes and cables in the trench.

Once the trench covers have been made they are to be stored and not laid until all trench cabling, piping, etc. is finished. Any covers laid before this time which become damaged shall be replaced at the Contractor's expense.

Trench covers and bridging beams for covers, except where heavy duty, shall be light enough for two men to lift.

12.17 Buried cables

Cables are to be laid in neat lines and at suitable levels. Their depth below ground level will depend upon the voltage associated with the cables but in all cases the excavation must provide a clear trench. Sand filling below, around and above the cables will always be required and protection covers or tiles will be placed in position over the sand filling before final backfilling to the ground level. The line of the cable trenches shall be marked with suitable posts as required by relevant section of this Specification.

13. 0 FOUNDATION/RCC DESIGN

13.1 General

All foundations/RCC Design shall be of reinforced cement concrete. The design and construction of RCC structures shall be carried out as per IS 456 and minimum grade of concrete shall be M20 corresponding to 1:1.5:3 (M20) nominal mix ratio with 12-20 mm coarse aggregate. Higher grades of concrete than specified above may be used at the discretion of the Bidder without any financial implication to the owner. Work covered under this clause of the specification comprises the construction of foundations and other RCC constructions for switchyard structures, equipment support, trenches, drains, jacking pad, pulling block, control cubicles, bus supports, Auto transformer/power transformer/reactors, marshalling kiosks, auxiliary equipments and system buildings, tank or for any other equipment or service and any other foundation required to complete the work. Also applicable to other RCC constructions.

If the site is sloping, the foundation height will be adjusted to maintain the exact level of the top of structures to compensate such slopes.

The switchyard foundations plinths and building plinths shall be minimum 300mm above finished ground level respectively. Minimum 75 mm thick lean concrete shall be provided below underground structures, foundations, trenches etc to provide a base for construction.

The design and detailing of foundations shall be done based on the approved soil data and sub-soil conditions as well as for all possible critical loads and the combinations thereof. The special footing or pile foundations as may be required based on soil/sub-soil conditions and superimposed loads shall be provided.

Admixtures in concrete shall conform to IS:9103. The water proofing cement additives shall conform to IS:2645. Concrete Admixtures/Additives shall be approved by the owner.

Limit state method of design shall be adopted unless stated otherwise in the Specification.

For design and construction of steel-concrete composite beams IS 11384 shall be followed.

For detailing of reinforcement IS 2502 and SP:34 shall be followed. Cold twisted deformed bars (Fe= 415 N/sq mm) conforming to IS 1786 shall be used as reinforcement. However, in specific areas, mild steel (Grade1) conforming to IS 432 can also be used. Two layers of reinforcement (on inner and outer face) shall be provided for wall and slab sections having thickness of 150 mm and above. Clear cover to reinforcement towards the earth face shall be minimum 40 mm.

RCC water retaining structures such as storage tanks, cooling water basin etc. shall be designed as uncracked sections in accordance with IS 3370 (Part 1 to IV) by working stress method and shall also be tested for water tightness at full water level. However, water channels shall be designed as cracked sections with limited steel stresses as per IS 3370 (Part 1 to IV) by working stress method.

The procedure used for the design of the foundations shall be the most critical loading combination of the steel structure and /or equipment and /or superstructure, and other conditions which produce the maximum stresses in the foundation or the foundation component, and as per the relevant IS Codes of foundation design. The design calculations shall be submitted by the bidder showing complete details of piles/pile groups proposed to be used.

All foundations shall rest below virgin ground level and the minimum depth of foundation below the virgin ground level shall be maintained.

Design shall consider any sub-soil water pressure that may be encountered.

Necessary protection to the foundation work, if required, shall be provided to take care of any special requirements for aggressive alkaline soil, black cotton soil or any other type of soil which is detrimental or harmful to the concrete foundations.

RCC columns shall be provided with rigid connection at the base.

All building sub-structures shall be checked for sliding and overturning stability during both construction and operating conditions for various combinations of loads. Factors of safety for these cases shall be as stated in relevant IS Codes or as stipulated elsewhere in the Specifications.

Earth pressure for all underground structures shall be calculated using coefficient of earth pressure at rest, coefficient of active or passive earth pressure (whichever is applicable). However, for the design of substructures of any underground enclosures, earth pressure at rest shall be considered.

In addition to earth pressure and ground water pressure etc., a surcharge load of 2T/sq.m shall also be considered for the design of all underground structures including channels, sumps, tanks, trenches, and substructures of any underground hollow enclosure etc., to allow for vehicular traffic in the vicinity of the structure.

The following conditions shall be considered for the design of water tanks, pump houses, channels, sumps, trenches and other underground concrete structures such as basements etc.

- Full water pressure from inside and no earth pressure, ground water pressure and surcharge pressure from outside (applicable only to structures which are liable to be filled with water or any other liquid).
- Full earth pressure, surcharge pressure and ground water pressure from outside and no water pressure from inside.

Design shall also be checked against buoyancy due to the ground water during construction and maintenance stages. Minimum factor of safety of 1.5 against buoyancy shall be ensured ignoring the superimposed loadings.

Base slabs of any underground enclosures shall be designed for empty condition during construction and maintenance stages with maximum ground water table (GWT). Minimum factor of safety of 1.5 against buoyancy shall be ensured ignoring the super-imposed loadings.

Base slab of underground enclosures such as water storage tank shall also be designed for the condition of different combination of pump sumps being empty during maintenance stages with maximum GWT. Intermediate dividing piers of such enclosures shall be designed considering water in one pump sump only and the other pump sump being empty for maintenance.

The foundations shall be proportioned so that the estimated total and differential movements of the foundations are not greater than the movements that the structure or equipment is designed to accommodate.

The foundation of the transformer and circuit breaker shall be of block type foundation. Minimum reinforcement shall be governed by IS:2974 and IS:456.

The tower and equipment foundations shall be checked for a factor of safety of 2.2 for normal condition and 1.65 for short circuit condition against sliding, overturning and pullout. The same factor shall be used as partial safety factor over loads in limit state design also.

All underground concrete structures such as basements, pump houses, water retaining structures etc. shall have plasticizer cum water proofing cement additive conforming to IS 9103. In addition, the limit on permeability as given in IS 2645 shall also be met. The concrete surface of these structures in contact with earth shall also be provided with two coats of bituminous painting for water /damp proofing.

In case of water leakage in the above structures, leakage repair shall be achieved by the injection method.

13.2 Machine Foundations

All machine foundations shall be designed in accordance the provisions of the relevant parts of the latest revisions of IS 2974, IS 456 and IS 2911. The provisions of DIN 4024 (latest) shall also be followed.

All block foundations resting on soil or piles shall be designed using the elastic half space theory.

The mass of the RCC block shall not be less than three times the mass of the machine. Dynamic analysis shall be carried out to calculate natural frequencies in all the modes including coupled modes, and to calculate vibration amplitudes. Frequency and amplitude criteria as laid down by the relevant IS codes and/or machine manufacturers, shall be satisfied. Minimum reinforcement shall be governed by IS 2974 and IS 456.

For the foundations supporting minor equipments weighing less than one tonne, or if the mass of the rotating parts is less than one-hundredth of the mass of the foundation, no dynamic analysis is necessary. However, if such minor equipment is to be supported on building structures, floors etc. suitable vibration isolation shall be provided by means of springs, neoprene pads etc. and such vibration isolation system shall be designed suitably.

13.3 Other Foundations

All foundations shall be designed in accordance with the provisions of the relevant parts of latest revisions of IS 2911 and IS 456.

Type of foundation system i.e. isolated footing, raft or piling shall be decided based on the load intensity and soil strata.

A minimum three piles shall be provided in any pile group.

Gantry and tower foundations shall be designed for an additional factor of safety of 1.1 for normal/ broken wire conditions and for short circuit condition.

Circuit breaker foundations shall be designed for impact loading and shall be strictly in accordance with the Manufacturer`s recommendations.

14. 0 FOUNDATIONS AND R CC CONSTRUCTION

14.1 General

Work covered under this Clause of this Specification comprises the design, supply and installation of foundations and other RCC constructions for switchyard structures, equipment supports, trenches, rains, jacking pads, pulling blocks, fencing, control cubicles, bus supports, transformers, marshalling kiosks, auxiliary equipments and systems, buildings and tanks, or for any other equipment or service and any other foundation required to complete the work. This clause is as well applicable to the other RCC constructions.

Concrete shall conform to the requirements of IS 456 and all the tests shall be conducted as per relevant Indian Standard Codes.

If the site is sloping, the foundation height will be adjusted to maintain the exact level of the top of structures to compensate for such slopes.

Switchyard foundation plinths and building plinths shall be minimum 300 mm and 500 mm above finished ground level respectively.

A minimum of 75 mm thick lean mix concrete (1:3:6) shall be provided below all underground structures, foundations, trenches etc. to provide a base for construction.

Concrete made with portland cement(OPC-43 grade) shall be carefully cured and special consideration shall be given during the placing of concrete and removal of shuttering.

The design and detailing of foundations shall be done based on the approved soil data and sub-soil conditions as well as for all possible critical loads and combinations thereof. Spread footing foundations or pile foundations as may be required based on soil and subsoil conditions and superimposed loads shall be provided.

If pile foundations are adopted, the same shall be cast-in-situ, driven, bored, precast or underreamed type as per relevant IS. Only RCC piles shall be provided. Suitability of the adopted pile foundations shall be justified by way of full design calculations. Detailed design calculations shall be submitted by the contractor showing complete details of piles and pile groups proposed to be used. Necessary initial load tests shall also be carried out by the contractor at their entire cost to establish the pile design capacity. Only after the design capacity of piles has been established, shall the Contractor commence of piling. All the design and testing work shall be planned in such a way that these shall not cause any delay in project completion.

14.2 Cement

The cement to be used shall be the best quality of its type.

All cement shall be sampled and tested in accordance with Indian Standards.

The Portland cement(OPC-43 grade) used in concrete shall confirm to IS 269.

Requirement of sulphate resistant cement (SRC) for substructural works shall be decided in accordance with the Indian Standards based on the findings of the detailed soil investigation to be carried out by the contractor.

High Alumina cement shall NOT be used.

14.3 Delivery and storage of cement

Cement shall be delivered to the site in bulk or in sound and properly sealed bags and while being loaded or unloaded whether conveyed in vehicles or by mechanical means, and during transit to

the concrete mixers, must be protected from the weather by effective coverings. Efficient screens are to be supplied and erected to prevent wastage of cement during strong winds.

If the cement is delivered in bulk, the Contractor shall provide at his own cost approved silos of adequate size and number to store sufficient cement to ensure continuity of work. The cement shall be placed in these silos immediately it has been delivered on the site. Suitable precautions shall be taken during unloading to ensure that the resulting dust does not constitute a nuisance.

If the cement is delivered in bags, the Contractor shall provide at his own cost perfectly waterproof and well-ventilated sheds having a floor of wood or concrete raised at least 150 mm above the ground. The sheds shall be large enough to store sufficient cement to ensure continuity of work. Each consignment of each type of cement shall be stacked separately therein. On delivery at site the cement shall at once be placed in these sheds and shall be used in the order in which it has been delivered.

All cement shall be used within 3 months of the date of manufacture.

14.4 Aggregate

Coarse and fine aggregate shall conform to the requirements of IS 383-1970.

Sampling and testing of aggregates shall be in accordance with the relevant Indian Standard.

Fine and coarse aggregates shall be obtained from the same source and the Contractor shall ensure that material from the source is known to have a good service record over a long period of time.

Aggregate shall be hard and dense and free from earth, clay, loam and soft, clayey, shaley or decomposed stone, organic matter and other impurities.

14.5 Storage of aggregates

Coarse and fine aggregates shall be stored on site in bins or on clean, dry, hard surfaces, and be kept free from all sources of contamination. Aggregates of different gradings shall be stored separately, and no new aggregate shall be mixed with existing stocks until tested, and approved by the Engg Incharge (Divisional Engr.).

14.6 Approval of Supplies

As soon as possible after the Contract has been placed the Contractor shall submit a list giving details of the sources from which he proposes to obtain concrete and mortar materials. Only materials from approved sources shall be brought to site, but the Engg Incharge (Divisional Engr.) will be prepared to extend his approval to other satisfactory sources of supply which may be proposed by the Contractor. Approval of a source of supply shall not imply acceptance of material found not to conform to this Specification

14.7 Water

Water used for mixing concrete and mortar shall be clean, fresh water obtained from an approved source and free from harmful chemicals, oils, organic matter and other impurities. Normally potable water may be considered satisfactorily for mixing and curing concrete and masonry work.

14.8 Steel bar reinforcement

Reinforcement shall comply with the appropriate Indian Standards.

All bar reinforcement shall be hot rolled steel except where the use of cold worked steel is specified on the drawings or otherwise approved.

The bars shall be round and free from corrosion, cracks, surface flaws, laminations, rough, jagged and imperfect edges and other defects.

The bar reinforcement shall be new, clean and of the lengths and diameters described on the Drawings and Schedules. Bars shall be transported and stored so that they remain clean, straight, undamaged and free from corrosion, rust or scale. Bars of different diameters shall be separately bundled.

14.9 Bending of reinforcement

All steel bars are to be accurately bent cold to the shapes and sizes indicated on the Drawings and Schedules unless otherwise approved. Re-bending of bars and bending in position in the works shall not generally be allowed.

14.10 Welding of reinforcement

Spot or tack welding for positioning bars in heavily reinforced areas will only be allowed with the express permission of the Engg Incharge (Divisional Engr.). Extension of lengths of reinforcement by welding will not be permitted.

Welding will be approved only in low stress members, and lap welding will not be approved in any circumstances.

14.11 Fixing of reinforcement

Before fixing in the works bars shall be seen to be free from pitting, mud, oil, paint, loose rust or scale or other adherents harmful to the bond or strength of the reinforcement. Bars shall be fixed rigidly and accurately in position in accordance with the working drawings, unless otherwise approved by the Engg Incharge (Divisional Engr.). Reinforcement at all intersections shall be securely tied together with 1.5 mm soft annealed tying wire the ends of which shall be cut and bent inwards. Cover to the reinforcement shall be in accordance with Clause 15.12 of this specification and sufficient spacers and chairs of precast concrete of approved design shall be provided to maintain the specified cover and position. No insertion of bars in previously placed concrete shall be permitted. Projecting bars shall be adequately protected from displacement. The fixing of reinforcement in the works shall be approved by the Engg Incharge (Divisional Engr.) before concrete is placed. Measurement will be based on the calculated weights of steel actually used in tonnes corrected to second place of decimal.

14.12 Concrete cover to reinforcement

For durability the minimum concrete cover to any reinforcing bar shall be as follows:

Concrete above ground.

- Internal faces of slabs 25 mm
- Internal faces of beams and walls 30 mm
- Exposed faces of slabs, beams and walls 50 mm
- All faces of columns 50 mm

Concrete below ground (including piles).

- Faces in contact with soil including blinding concrete 75 mm
- All other faces (i.e. internal faces of basement wall) 50 mm

Only concrete or steel spacers shall be used to achieve the required minimum thickness of concrete cover to reinforcement. Concrete spacers shall have non metallic ties. Timber blocks for wedging the steel off the formwork will not be allowed.

14.13 Formwork

Form work shall be constructed from timber, metal, lined as necessary for special finishes and designed with the quality and strength required to ensure rigidity throughout placing, ramming, vibration and setting of the concrete, without detrimental effect.

Form work shall be erected true to line, level and shapes required using a minimum of approved internal ties. Faces in contact with the concrete shall be true and free from defect, jointed to prevent loss of water or fines, in panels or units which permit easy handling, and designed to permit side forms to be struck independently of soffit shuttering. Ties or spaces remaining embedded shall have the minimum cover specified for reinforcement. Forms for exposed concrete beams, girder casings and columns shall provide for a twenty five millimetre chamfer on external corners.

Wedges and clamps shall be kept tight during vibration operations. Before commencement or resumption of concreting, the interior of forms shall be cleaned and free of sawdust, shavings, dust, mud or other debris and openings shall be formed to facilitate this cleaning and inspection. The inside of the forms shall be treated with a coating of an approved substance to prevent adhesion. Care shall be taken to prevent this substance being in contact with the reinforcement.

14.14 Grades of concrete

Concrete shall be either ordinary or controlled and in grades designated M10, M15, M20 and M25 as specified in IS 456 (latest edition). In addition, nominal mixes of 1:3: 6 and 1: 4: 8 of nominal size 40 mm maximum, or as indicated on drawings, or any other mix without any strength requirements as per mix design shall be used where specified.

14.15 Ordinary concrete

Ordinary concrete shall be used for all plain cement concrete work and where shown on drawings or allowed by the Engg Incharge (Divisional Engr.). Ordinary concrete shall not require preparation of trial mixes.

In proportioning concrete, the minimum quantity of cement shall be as specified in Table 15.15.1 of this clause and the amount to be used shall be determined by actual weight. The quantities of fine and coarse aggregate may be determined by volume, but preferably by weight.

The water cement ratio shall not be more than those specified in IS 456.

Grade of Concrete	Minimum cement content per c.m. of finished concrete
M 10	236 kg
M 15	323 kg
M 20	410 kg

M 25	530 kg
------	--------

Table - 15.15 Minimum Cement content.

14.16 Controlled concrete

14.16.1 Mix proportions

The mix proportions for all grades of concrete shall be designed to obtain strength corresponding to the values specified in IS 456 for respective grade of concrete. Preliminary tests as specified in the IS Code or as required by the Engg Incharge (Divisional Engr.), shall be carried out, sufficiently ahead of the actual commencement of the work, with different grades of concrete made from representative samples of aggregate and cement expected to be used on the job. The purpose of this test is to ascertain the water cement ratio required to produce a concrete having specified strength, and to demonstrate sufficient workability to enable it to be well consolidated and to be worked into corners of shuttering and around the reinforcement.

14.16.2 Mix design

As a guide to perform the mix design properly, the relationship between water cement ratio, aggregate to cement ratio, workability and strength of concrete will be as per relevant IS.

The cement /total aggregate ratio is not to be increased beyond 1: 9.0 without specific permission of the Engg Incharge (Divisional Engr.). It should be noted that such high aggregate/cement ratios will be required for concretes of very low slump and high water cement ratios which may be required to be used in mass concrete work only.

The actual cement aggregate ratios are to be worked out from the specific gravities of coarse aggregates and sand being used, and from trial mixes.

14.17 Strength requirements

The mix proportions for all grades of concrete shall be designed to produce the grade of concrete having the required workability and a characteristic strength not less than the value given table 15.17.

Grade Designation	Characteristic Compressive Strength at 28 days
M 10	10 N / sq. mm
M 15	15 N / sq. mm
M 20	20 N / sq. mm
M 25	25 N / sq. mm

Table - 15.17 Strength Characteristic

The strength of concrete given above is the 28 days characteristic compressive strength of 15 cm cube.

14.18 Workability

The workability of concrete shall be checked at frequent intervals by slump test, where facilities exist and if required by the Engg Incharge (Divisional Engr.), alternatively the compaction factor test in accordance with IS 1199 shall be carried out.

14.19 Mixing of Concrete

Unless otherwise approved, concrete for foundations will be M 20 grade, corresponding to nominal mix of 1:1.5:3 as per IS 456. The proportions of fine and coarse aggregate, cement and water shall be as determined by the mix design or according to fixed proportions in case of nominal mix concrete and shall always be approved by the Engg Incharge (Divisional Engr.). The quantities of the cement, fine and coarse aggregates shall be determined by weight, the water shall be measured accurately after giving proper allowance for surface water present in the aggregate. Water shall be added to make a workable mix and it is important to maintain the water-cement ratio at its correct value of 0.55 in accordance with the requirements of IS 456.

Water shall not be added to the mix until all the cement and aggregates constituting the batch are already in the drum and dry mix for at least one minute. Mixing of each batch shall be continued until there is uniform distribution of materials and the mass done for less than 2 minutes and at least 40 revolutions after all the materials and water are in the drum.

When hand mixing is permitted by the Engg Incharge (Divisional Engr.) for concrete to be used in unimportant locations it shall be carried out on a water tight platform and care shall be taken to ensure that mixing is continued until the mass is uniform in colour and consistency. In case of hand mixing, an extra 10% of cement shall be added to each batch and additional cost due to extra cement will be borne by the Contractor.

14.20 Conveying Concrete

Concrete shall be handled and conveyed from the place of mixing to the place of final laying as rapidly as practicable by approved means before the initial setting cement starts. Concrete should be conveyed in such a way which will prevent segregation or loss of any of the ingredients. If segregation does occur during the transport of concrete same shall be re-mixed. The requirements to be fulfilled during transportation are :

- No segregation or separation of materials in the concrete, and
- Concrete delivered at the point of placing should be uniform and of proper consistency.

14.21 Placing Concrete

Form work and reinforcement shall be approved in writing by the Engg Incharge (Divisional Engr.) before concrete is placed. The forms shall be well wetted and all shavings, dirt and water that may have collected at the bottom shall be removed before concrete is placed. Concrete shall be deposited in its final position without segregation, re-handling or flowing. As far as possible concrete shall be placed in the formwork by means approved by the Engg Incharge (Divisional Engr.) and shall not be dropped from a height or handled in a manner which may cause segregation. Any drop over 180 cm. shall have to be approved by the Engg Incharge (Divisional Engr.). Once the concrete is deposited in its final position, it shall not be disturbed. Care should be taken to avoid displacement of reinforcement or movement of formwork.

The placing of concrete shall be a continuous operation with no interruption in excess of 30 minutes between the placing of continuous portions of concrete. When fresh concrete is required to be placed on previously placed and hardened concrete, special care should be taken to clean the surface of all foreign matter. For securing a good bond and water tight joint, the receiving surface should be made rough and a rich mortar placed on it unless it has been poured

just before. The mortar layer should be about 15 mm thick with cement and sand proportion as that of the mix in use, and have the same water-cement ratio as the concrete to be placed.

After the concrete has been placed it shall be thoroughly compacted by approved mechanical vibration to a maximum subsidence without segregation and thoroughly worked around reinforcement or other embedded fixtures into the correct form and shape. Vibrators must be operated by experienced men and over vibration shall not be permitted. Care should be taken to ensure that the inserts, fixtures, reinforcement and formwork are not displaced or disturbed during placing of concrete. No concrete shall be placed in open while it rains. If there is any sign of washing of cement and sand, the concrete shall be entirely removed immediately. Slabs, beams and similar structure shall be poured in one operation normally. In special circumstances with the approval of Engg Incharge (Divisional Engr.) these can be poured in horizontal layers not exceeding 50 cm. in depth. When poured in layers, it must be ensured that the under layer is not hardened. Bleeding of under layer if any shall be effectively removed.

14.22 Compaction of Concrete

Compaction is necessary for production of good concrete. After the concrete has been placed it shall be thoroughly compacted by approved mechanical vibrator to a maximum subsidence without segregation and thoroughly worked around reinforcement or other embedded fixtures into the correct form and shape. Vibrators must be operated by experienced men. Care should be taken to ensure that the inserts, fixtures, reinforcement and formwork are not displaced or disturbed during the vibration of the concrete. The Contractors shall provide standby vibrators. Vibration is commonly used method of compaction of concrete, the use of mechanical vibrators complying with IS 2505, IS 2506, IS 2514 and IS 4656 for compacting concrete is recommended

For all practical purposes, the vibration can be considered to be sufficient when the air bubbles cease to appear and sufficient mortar appears to close the surface and facilitate easy finishing operations. The period of vibration required for a mix depends upon the workability of the mix.

14.23 Curing of Concrete

In order to achieve proper and complete strength of the concrete, the loss of water from evaporation should be prevented. Eighty to eighty five per cent of the strength is attained in the first 28 days and hence this 28-day strength is considered to be the criterion for the design and is called characteristic strength. The concrete after setting for 24 hours shall be cured by keeping the concrete wet continuously for a period of 10 days after laying.

The curing increases compressive strength, improves durability, impermeability and abrasion resistance. Failure to carry out satisfactory curing can lead to cracking in the concrete. This in turn can lead to salt attack of the reinforcement and consequential failure of the structure. If cracks occur in a structure which are severe enough to affect the structure, the Contractor shall cut out and replace the defective concrete at his own cost. The Contractor's attention is, therefore, drawn to this particular aspect of proper and adequate curing

14.24 Construction joints

Construction joints are a potential source of weakness and should be located and formed with care and their number is kept to a minimum.

When the work is to be interrupted, the concrete shall be rebated at the joint to such shape and size as may be required by the Engg Incharge (Divisional Engr.) or as shown on the drawings. All vertical construction joints shall be made with water bars which are rigidly fixed and shall provide a positive barrier against movement of water through the joint. Great care shall be taken when placing concrete around water bars because the space is often congested. Concreting shall

be carried out continuously up to construction joints. Construction joints, if not described on the drawings, shall be in accordance with the following:

- In a column, the joint shall be formed about 75 mm below the lowest soffit of the beams framing into it, at the meeting points of the columns and the raft, and at the point of contraflexure in the columns.
- Concrete in a beam shall be placed throughout without a joint. However if the provision of a joint is unavoidable, the joint shall be vertical and at the middle of the span.
- A joint in a suspended floor slab shall be vertical at one of the quarter points of the span and at right angle to the principal reinforcement.
- Additional reinforcements and shear keys shall be provided at the construction joints.

In forming a joint, concrete shall not be allowed to slope away to thin edge. The locations of construction joints shall be planned by the contractor well in advance of pouring and be approved by the Engg Incharge (Divisional Engr.).

Construction joints in foundation of equipment shall not be provided without the approval of Engg Incharge (Divisional Engr.).

14.25 Expansion and separation joints

Expansion joints shall be as shown on the drawings or as specified in the schedules. Expansion joint filler boards conforming to IS 1838 and sealing strips shall have minimum transverse joints. Joints shall be vertical and straight except where otherwise approved and concrete surfaces and faces shall be flush on bothsides of the joint.

Separation joints shall be with standard water proof paper or with as alkathene sheets about 1 mm in thickness. Lap length and sealing of laps shall be to the satisfaction of the Engg Incharge (Divisional Engr.).

14.26 Removal of form work

Form work shall be kept in position fully supported, until the concrete has hardened and gained sufficient strength to carry itself and any loads likely to be imposed upon it. Stripping must be effected in such a manner and at such a time that no shock or other injury is caused to the concrete. The responsibility for safe removal rests with the Contractor but the Engg Incharge (Divisional Engr.) may delay the time of striking if he deems it necessary.

Minimum periods, in the absence of agreement to the contrary, between completion of concreting and removal of forms are given below but due regard must be paid to the method of curing and prevailing conditions during this period.

- Removal of shuttering to sides of rafts, walls, beams and columns
2 days
- Removal of shuttering to slabs, beams and arches (props left under)
6 days
- Removal of props to slabs, beams and arches
16 days
- Lifting of pre cast members
16 days

14.27 Pre cast concrete members

Pre cast concrete members shall be used in the works only where specified on the Drawings or approved by the Engg Incharge (Divisional Engr.).

The technical specifications for cement concrete, formwork and reinforcement covered under earlier clauses shall form a part of these specifications and shall be followed for carrying out pre cast concrete work.

Pre cast members shall not be disturbed or lifted until the minimum periods specified for formwork removal have elapsed.

14.28 Load Test on Parts of Structures

The load test on concrete , if desired by the Engg Incharge (Divisional Engr.) shall be carried as soon as possible after the expiry of 28 days from the time of placing of concrete as per the clause 16.5 to 16.6 of IS : 456. The structure shall be subjected to a load equal to full dead load of the structure plus 1.25 times the imposed load for a period of 24 hours and then the imposed load shall be removed. The entire cost of load testing shall be borne by the contractor and if any portion of the structure found unacceptable under the relevant clause of IS : 456, the same shall be dismantled and replaced by a new structure as per specification at no extra cost to the Employer. If during dismantling any of the adjacent structure is damaged, the same shall be made good free of charge by the contractor to the satisfaction of the Engg Incharge (Divisional Engr.).

14.29 Finish of concrete surface

14.29.1 Concrete cast against formwork.

The following finishes to concrete surfaces, unless otherwise specified or shown on the drawings, shall be as follows

- **Class A1:** All permanently exposed surfaces, including exposed sides of foundations.
- **Class A2:** Surfaces to be covered by backfill, plasters or the like.

Class A1 surfaces shall be dense, fair, smooth, even, free from honeycombing, water and air holes and other blemishes, true to line and surface and free from board or panel marking. They shall be of uniform colour. Rendering of defective surfaces shall not be permitted, and, if ordered by the Engg Incharge (Divisional Engr.), the Contractor shall at his own expense cut out to expose reinforcement and make good any unsatisfactory work. All areas so treated shall be rubbed down and kept moist for several days.

Class A2 surfaces shall be dense, even, free from honeycombing and true to line and surface.

Any special finishes will be to details or instructions given by the Engg Incharge (Divisional Engr.).

14.29.2 Concrete not cast against form work.

The following finishes shall be provided unless otherwise specified or shown on the drawings

- **Class B1:** All permanently exposed surfaces, including tops of equipment foundations, wall copings, window sills, precast items (except paving flags).
- **Class B2:** Paving flags and paths. Floors and slabs to be surfaced with blocks, tiles or waterproofing materials.

- **Class B3:** Roads, buried concrete and floors or slabs to be covered by screed.

Class B1 surfaces shall first be levelled and screened to produce a true surface. After the moisture film has disappeared, and the concrete has hardened sufficiently, the surface shall be finished with a steel trowel under firm pressure to give a smooth, dense, even and hard surface free from all marks and defects.

Class B2 surfaces shall be levelled and screened to produce a true surface, and be finished with wooden or steel float to give a level surface free from screed marks. Excessive floating shall be avoided.

Class B3 surfaces shall be levelled and screened to produce a true and uniform surface.

14.30 Holes, pockets, threaded inserts, etc.

The threaded inserts for casting into concrete shall be electro-galvanized and of malleable iron or mild steel. Holes, cavities and fixings shall be provided in the works only at the positions indicated on the drawings or as directed and they shall be incorporated as necessary during the work of concreting. Unless otherwise agreed a tolerance in position of plus or minus five millimetres shall be allowed. Inserts and bolts shall be fixed square in the works by means of temporary bolts or nuts, and then concrete cast around them. The projecting portions of such fixings, and concrete within fifty millimetres of them, shall be bitumastic painted and all threads well greased on completion of the work. Holes and pockets shall be stripped down clean on completion.

14.31 Blinding

Blinding concrete shall be made with nominal aggregate sizes of both 20mm and 40mm diameter. They shall be referred to respectively as grade M 10/20 and M 10/40.

Under all foundations and elsewhere as indicated on the drawings a layer of concrete grade M10 (1:3:6) shall be laid immediately the excavation is carried down to foundation level. The blinding surface shall be thoroughly cleaned before foundation concrete is deposited thereon. Sumps shall be provided where necessary to facilitate the control of drained water. The grade shall be applied as shown in Table 15.31.1

Location	Grade	Thickness of layer
Foundations and bases	M 10 / 1:3:6	75 mm
Floors of ducts, trough and reinforced slabs not exceeding 100 mm	M 10 / 1:3:6	50 mm

Table 15.31.1. Blinding layer thickness values

14.32 Admixtures and Additives

Only approved admixtures shall be used in the concrete for the Works. When more than one admixture is to be used, each admixture shall be batched in its own batch and added to the mixing water separately before discharging into the mixer. Admixtures shall be delivered in suitably labelled containers to enable identification.

Admixtures in concrete shall conform to IS:9103. The water proofing cement additives shall conform to IS:2645. Concrete admixtures and additives shall be approved by the Engg Incharge (Divisional Engr.).

The Contractor shall use an approved neutralized vinsol resin air-entraining agent in all concrete. The Air entraining agent shall be supplied and batched as a solution with a solids content not exceeding 15 percent by weight with suitable, stable and consistent pH.

The Contractor may propose and the Engg Incharge (Divisional Engr.) may approve the use of a water-reducing set-retarding admixture in some of the concrete. The use of such an admixture will not be approved to overcome problems associated with inadequate concrete plant capacity or improperly planned placing operations and shall only be approved as an aid overcoming unusual circumstances and placing conditions.

Water-reducing set-retarding admixture shall be an approved brand of Igno-sulphonate type admixture.

Water proofing cement additives shall be used as required or advised by the Engg Incharge (Divisional Engr.).

15. 0 FENCING

15.1 General

Fencing shall be designed for the most critical loading combination taking into account wind forces, stability, tension on wires, minimum requirements as per this clause and relevant IS recommendations.

The un climbable or security, or anti-intruder fencing shall consist of chain link mesh, all as soon on the drawings and as specified below, supported on approved sections of structural steel. The posts shall be erected truly vertical, and all posts and struts shall be set in concrete block foundations.

Concrete kerbing shall be provided between the fence posts as shown on the drawings.

15.2 Areas requiring fencing

Fencing shall be provided for the following areas:

- Site fencing for the complete station, complete with barbed wires on top. Separate gates shall be provided for men and equipment.
- Internal fence surrounding the various equipments (if) mounted on ground or a height lower than 2.5 m, without barbed wires on top. Necessary gates shall be provided for each area so surrounded.
- Wherever necessary anti-reptile fixture/arrangement shall be provided along with fencing.

15.3 Product materials

15.3.1 General

Chain Link fence fabric in accordance to IS :2721, and shall also meet the following requirements.

- Size of mesh 75 mm
- Size of coated wire 3.15 mm diameter

- Width of chain link 2000 mm
- Class of zinc coating medium
- Zinc coated after weaving

Posts shall be as shown in Table.

The posts shall be of medium M.S tube of 50 mm diameter confirming to Yst-22 (Kg / sq. mm). The tubes shall be also confirm to IS:1161/IS 806. The length of the tubular post shall be 3200mm.

An M.S base plate of size 160X160X6mm thick shall be welded with the tubular post. The post shall be provided on the top with M.S plate.

The tubular post shall be welded with 8 numbers of M.S flat of size 50X6mm ó 75 mm long. Two numbers of 13.5 mm dia holes on each cleats shall be provided to bolt the fence fabric panel. The cleats shall be welded at equal spacing in such a way that 4 nos of cleats are on the opposite side and remaining 4 nos cleats are on the opposite side of the post. The cleats on the corner posts shall be welded in such a way that it suits the site requirement.

The whole assembly of tubular post shall be hot dip galvanised. The zinc coating shall be minimum 615 gram per sq mm. The purity of the zinc shall be 99.95% as per IS:209.

Fence fabric panel:

Chain link fencing shall be fabricated in the form of panel 2000X2928 mm. An MS flat of at least 50X6 mm size shall be welded all round fence fabric to form a panel. Four pairs of 13.5 mm diameter holes on the vertical MS flat matching the spacing of holes in cleats fixed with pipe shall be provided to fix the fence panel with tubular posts. A washer shall also be provided below each nut. 12 mm diameter bolts and nuts including washers **shall also be supplied. All bolts, nuts and washer shall be hot dip galvanised.** The fence panel shall be provided with two GI flats of size 50X6 mm placed cross wise for rigidity of chain link.

Installations:

Fence shall be installed along switch yard line as per the approved GA drawing. Post holes shall be excavated by approved method. All posts shall be 3 mtrs apart measured parallel to ground surface.

Posts shall be set in 1:2:4 plain cement concrete block of minimum 0.4X0.4X1.2mtr depth. 75 mm thick PCC 1:4:8 shall be provided below concrete block.

Fence posts shall be erected in vertical and kept for minimum 7 days curing before fence fabri erection.

Fence fabric panel shall be fixed to the post at 4 nos. M.S flat each of 50X6 mm,75mm long through 2 nos of 12 mm dia bolts on each flat.

Paintings as per decision of the Engineer in charge have to be carried out.

Continuous running earth by using 50 X 6 mm GI flats to be provided for safety purpose.

A 345/380 mm thick (one and a half brick size) toe wall of Brick/Rubble masonry, or concrete with notches shall be provided below all fencing and shall be minimum 200 mm above and 500 mm below finished ground level. All exposed surfaces for brick toe wall shall be provided with 15 mm 1:6 cement sand plaster and coated with two coats of water proofing snowcem cement paint. In case if rubble masonry is provided suitable pointing shall be done.

GATES:

Gates shall be installed in locations shown on drawings. Next to the main gate, a men gate (1.25 m wide, single leaf) shall also be provided.

Bottom of gates shall be set approximately 40 mm above ground surface and necessary guiding mechanism (with roller on the bottom of the gate and fixed guider in the road) shall be fitted to avoid hanging of the main gate.

15.3.2 Gates

Gate frames shall be of galvanized steel of 40 mm dia main pipe and vertical pipes of 15mm dia @ 125 mm spacing (pipe to relevant IS) welded to the main pipe for frames or Black steel pipe to relevant IS for frames with welded joints and shall be painted with one coat of steel primer and two coats of synthetic enamel paints.

Gates shall be fabricated with welded joints or other approved methods to achieve rigid connections. The gate frames shall be hot dip galvanized after welding.

Gates shall be fitted with galvanized malleable iron hinges, latch and latch catch. Latch and latch catch shall be suitable for attachment and operation of padlock from either side of gates. Hinges shall permit gates to swing through 180 degree back against fence.

Gates shall be fitted with galvanized chain hook or gate hold back to hold gates open. Double gates shall be fitted with centre rest and drop bolt to secure gates in closed position.

15.3.3 Patching

Damaged galvanized surfaces shall be repaired. Damaged surfaces shall be cleaned with wire brush removing loose and cracked spelter coating. Two coats of approved zinc pigmented paint shall be applied to damaged areas in accordance with manufacturers instructions.

There shall be one gate located on boundary wall as main gate having wicket gate and one gate as switchyard gate, located on the fencing.

16. 0 BUILDING

16.1 General

The scope includes the design, engineering and construction of control room and colony quarters building. For control room and colony quarter building the tentative layout showing the facilities to be provided is indicated some where and also to be proposed by the bidders for better utility and aesthetic view. However, the size and layout of the building may be modified as per requirements of Single Line Diagram (SLD) with the approval of the Engg Incharge (Divisional Engr.).

16.2 Dimensions

An open space of one metre minimum shall be provided on the periphery of the rows of panels, and equipment generally, in order to allow easy operator movement and access as well as maintenance.

The building design shall also take into consideration the layout of the panels, switchboards, switchgear and other equipment in order to allow enough area for the future extension of switchyard depending upon the availability of substation area.

16.3 Design

The buildings shall be designed:

- to the requirements of the National Building Code of India. and the standards quoted therein
- for the specified climatic and loading conditions
- to adequately suit the requirements of the equipment and apparatus contained in the buildings and in all respects to be compatible with the intended use and occupancy
- with a functional and economical space arrangement
- for a life expectancy of structure, systems and components not less than that of the equipment which is contained in the buildings, provided regular maintenance is carried out
- to be aesthetically pleasing. Different buildings shall show a uniformity and consistency in architectural design
- to allow for easy access to equipment and maintenance of the equipment
- with, wherever required, fire retarding materials for walls, ceilings and doors, which would prevent supporting or spreading of fire
- with material preventing dust accumulation

Suitable expansion joints shall be provided in the longitudinal direction wherever necessary with provision of twin columns.

Individual members of the building frame shall be designed for the worst combination of forces such as bending moment, axial force, shear force, torsion etc.

Permissible stresses for different load combinations shall be taken as per relevant IS Codes.

All cable vaults shall be located above ground level i.e. cable vaults shall not be provided as basements in the buildings.

The building lighting shall be designed in accordance with the requirements of relevant section.

The building auxiliary services such as air conditioning and ventilation systems, fire protection and detection systems and all other miscellaneous services shall be designed in accordance with the requirements specified in relevant sections of this Specifications.

The doors and windows of the building shall be of aluminium extruded channels, angles etc. The windows shall be provided with sliding shuttering facilities and also to be provided with aluminium make grills.

16.4 Design Loads

Building structures shall be designed for the most critical combinations of dead loads, super-imposed loads, equipment loads, crane loads, wind loads, seismic loads, and temperature loads. In addition, loads and forces developed due to differential settlement shall also be considered.

Dead loads shall include the weight of structures, complete finishes, fixtures and partitions and should be taken as per IS:1911 (latest revision).

Super-imposed loads in different areas shall include live loads, minor equipment loads, cable trays, small pipe racks/hangers, and erection, operation and maintenance loads. Equipment loads shall constitute, if applicable, all load of equipments to be supported on the building frame.

For crane loads an impact factor of 30% and lateral crane surge of 10% of (lifted weight plus trolley weight) shall be considered in the analysis of frame according to provisions of IS:875 (latest revision). The horizontal surge shall be 5% of the static wheel load.

For temperature loading, the total temperature variation shall be considered as two thirds of the average maximum annual variation in temperature. The average maximum annual variation in temperature for the purpose shall be taken as the difference between the mean of the daily minimum temperature during the coldest month of the year and mean of daily maximum temperature during the hottest month of the year. The structure shall be designed to withstand stresses due to 50% of the total temperature variation.

Wind loads shall be computed as per IS:875. Seismic coefficient method shall be used for the seismic analysis as per IS 1893 (latest revision), wind and seismic forces shall not be considered to act simultaneously.

Floors/slabs shall be designed to carry loads imposed by equipment, cables, piping travel of maintenance trucks and equipment and other loads associated with the building. In general, floors shall be designed for live loads as per relevant IS and cable and piping loads not less than 5 kN/ sq.m hanging from the underside. In addition, beams shall be designed for incidental point loads of 20 kN to be applied at any point along the beams. The floor loads shall be subject to the approval of the Engg Incharge (Divisional Engr.).

For consideration of loads on structures, IS 875, Code of practice for structural safety of buildings shall be followed. The minimum superimposed live loads shown in Table 17.4.1. shall be considered for the design.

Roof	150 kg / sq m.	for accessible roofs.
	75 kg / sq m.	for non - accessible roof.
R C C Floors.	500 kg / sq m.	for offices and minimum 1000 kg / sq m. for equipment floors or actual requirement, if higher than 1000 kg / sq m., based on equipment component weight and layout plans.
Stairs and balconies.	500 kg / m.	
Toilet Rooms.	200 kg / m.	
Chequered plate floor.	400 kg /sq. m	
Walkways.	300 kg /sq. m.	

Table 17.4.1. Superimposed live loads

16.5 Submission of data for approval

The following information shall be submitted for review and approval to the Engg Incharge (Divisional Engr.):

- Design criteria for structural steel and reinforced concrete design. The criteria shall comprise the codes and standards used, applicable climatic data including wind loads, earthquake factors and maximum and minimum temperatures applicable to the building locations, assumptions of dead and live loads, including equipment loads, impact factors, safety factors and other relevant information.
- Structural design calculations and drawings including those for construction and fabrication for all reinforced concrete and structural steel structures.
- Fully dimensioned floor plans, cross sections, longitudinal sections and elevations of each building. These drawings shall be drawn at a scale not less than 1:50 and shall identify the major building components.
- Fully dimensioned drawings showing details and sections, drawn to scales of sufficient size to clearly show sizes and configuration of the building components and the relationship between them.
- Product information of building components and materials, including walls, partitions, flooring, ceilings, roofing, doors and windows and building finishes.
- A detailed schedule of building finishes including colour schemes.
- A door and window schedule showing door types and locations, door lock sets and latch sets and other door hardware.

Approval of the above information shall be obtained before ordering materials or starting fabrication or construction as applicable.

16.6 Electrostatic radio interference shielding

The building inside the energized area of the stations shall be electrostatically shielded to limit the exposure of the equipment and personnel to specified electric field strengths. The shielding system shall be grounded properly.

16.7 Control Room Building/Colony quarters

Design and construction, including anti termite treatment of control room building and colony quarters for each sub- station or switchyard shall be in the scope of the contract. The control room buildings and colony quarters shall be of RCC framed structure of concrete M20 grade. The control room and some other rooms of the control room building shall be fully air conditioned.

16.8 Finish Schedule

The preliminary indicative finishing schedule is given in subsequent clauses. However, at the time of detailed engineering, the Engg Incharge (Divisional Engr.) reserves the right to alter the finishing schedule and specifications and such changes shall have no additional financial implication whatsoever to the Employer.

16.9 Flooring (52 mm Thick)

50mm thick cement concrete 1:2:4. & finishing with vitrified tiles in the main control room area, conference room and MCCDB (AC & DC) room. The other area flooring shall be with vitrified tiles of reputed make. There shall be dado of 9 inches by the same. The toilets and bath rooms shall be provided with antiskid ceramic tiles and the walls are also to be provided with ceramic tiles of adequate height as per standard practice. The battery room floorings and walls (up to

3mtrs height) shall be provided with acid proof industrial based tiles. The left over portion of the walls shall be painted with acid proof paints.

16.10 Walls

Control room buildings shall have framed superstructure. All walls shall be non-load bearing walls. Minimum thickness of external walls shall be 230 mm with 1:6 cement sand mortar. A 50 mm thick DPC shall be provided at plinth level before starting masonry work.

16.11 Plastering

All internal walls shall have minimum 12mm thick 1:6 cement sand plaster. The ceiling shall have 6mm thick 1:4 cement sand plaster.

16.12 External Finish

All external surfaces shall have painted with weather proof synthetic paints over 18mm thick cement sand plaster in two layers. Under layer 12mm thick cement plaster 1:5 (1 cement:5 coarse sand) and a top layer 6mm thick cement plaster 1:3 (1 cement:3 coarse sand) finished rough with sponge.

All ceilings shall be white based plastic emulsion paints and the internal walls are also to be provided with plastic emulsion synthetic paints. The outer of the building shall be provided with weather seal coats of synthetic paints.

16.13 Roof

Roof of the building shall consist of cast in situ R.C.C. slabs. Extra heavy water proofing treatment shall be done after grading underbed with 1:4 cement sand plaster of 25mm thickness. The under bed shall be laid to provide an ultimate run off gradient of 1:120. The extra heavy treatment shall be concrete based with water proof treatment as per the standard to protect the roof from damage due to water logging. Proper slope and adequate no of water drains outlets shall be provided for easy discharge of water from the roof. These drains shall be connected to the main drain.

16.14 Glazing (glass)

Minimum thickness of glazing shall be 6 mm. The glazing for the control room area, which will be air-conditioned shall be provided with double toughened glass each of 6mm thickness.

16.15 False Ceiling

The control room and all other air conditioned areas shall have closed aluminium ceiling system comprising 84mm wide, 12.5mm deep panels of approved colour with a recessed flange of 23.9mm roll formed out of 0.5mm thick aluminium alloy 5050/5052/3003 or equivalent, coated with chromatised and stone enamelled on both sides, panels to be fixed on roll formed carriers 32 mm wide 39 mm deep out of minimum 0.9 mm thick aluminium alloy strip with cut outs to hold panels in a module of 100mm minimum at maximum 1.6 mc/c carrier suspended from roof by 4mm diameter galvanised steel wire rod hangers with special height adjustment springs/clips made out of spring steel at maximum spacing of 1.5 m c/c hangers fixed to roof, J'hooks and nylon insert including providing laying and fixing 25mm thick resin bonded mineral wool of approved quality, encased in 100 G black polythene and laid over top of places panels, all complete. The system is subject to approval by the Engg Incharge (Divisional Engr.) before installation.

16.16 Doors and Windows

The doors and windows of the control room building shall be of aluminium with aluminium grill and all the frames of doors and windows also of aluminium sections in accordance with the relevant IS Codes. Size and shapes shall be adequate for entering in to the room. In the Air conditioned area shall be double glass (toughened) and doors suitably made to have efficient air conditioning. The windows shall be of sliding type. Anodised aluminium work for doors and windows, ventilators and partitions shall be provided and fixed in the building with extruded built up standard tubular and other sections approved make confirming to IS:733 and IS:1285, anodised transparent or dyed to required shade according to IS:1868 (minimum anodic coating of grade AC 15) fixed with rawl plugs and screws with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions at top, bottom and sides with required PVC/neoprene felt etc and joined mechanically wherever required including cleat angle, Aluminium snap beading for glazing/panelling, C.P brass/stainless steel screws including glazing and fittings as specified.

16.17 Plumbing And Sanitation

All plumbing and sanitation work shall be executed to comply with the requirements of the appropriate bye laws, rules and regulations of the Local Authority having jurisdiction over such matters. The Contractor shall arrange for all necessary formalities to be met in regard to inspection, testing, obtaining approval and giving notices etc.

An overhead water tank of adequate capacity depending on the number of users for 24 hours storage shall be provided.

Galvanised MS pipe of medium class conforming to IS : 1239 shall be used for internal piping works for portable water supply.

Sand C I pipes with lead joints conforming to IS:1729 shall be used for sanitary works above ground level.

A list of toilet fittings will be approved by the Engg Incharge (Divisional Engr.), before procurement by the contractor and same will be inspected by the Engg Incharge (Divisional Engr.) before installation. Sufficient nos of toilets and bath rooms including separate urinal provision shall be provided at both ground and first floors. Required nos of wash basins (stand type) with good quality mirrors and other accessories as required are also to be provided at both ground and first floor of control room building. Same procedure for colony quarters also.

16.18 Building storm water drainage

The building design shall provide for the collection of storm water from the roofs. This water shall be collected in junction boxes and these boxes shall drain to the main drainage system of the station.

Cast iron rain water downcomers conforming to IS:1230 with water tight lead joints or medium class galvanised mild steel pipes conforming to IS:1239/ IS:3589, shall be provided to drain off the rain water from the roof. These shall be suitably concealed with masonry work of cement concrete or cladding material. The number and size of downcomers shall be governed by IS:1742 and IS:2527.

All drains inside the buildings shall have minimum 40 mm thick grating covers and in areas subject to movement heavy equipment loads, precast RCC covers shall be provided in place of steel grating.

For all buildings, suitable arrangement for draining water collected from equipment blowdowns, leakages, floor washings, fire fighting etc. shall be provided for each floor.

1.3 Flooring

Entire area around the control room building (out side) shall be provided with PCC paving starting from the building upto 2 mtrs clear distance for the full length of the building.

The above specified PCC paving shall be with M15 mix grade concrete over suitable under bed arrangement as specified for other ground floor slab.

Above the PCC paving suitable Cement pavers chequered plate of size as per the standard to be provided. The colour of the chequered plate shall be fixed over the PCC paving by using cement mortar and the colour of such plate shall be red.

The cable vault below the main control room shall have 50 mm thick smooth floor finish units of cement concrete.

1.4 Provision of rooms in the control room building.

a) 220/132/33 KV S/S Building:

>The plinth area for the control room building shall be as below:-

Ground floor: 50mtrX25mtr

Ground floor portico: 5mtrX5mtr (at two locations)

First floor: 25 mtr X 25 mtr

i) Ground floor shall have cable vault, Battery room, Office rooms(3 nos), MCCB room, Library, Conference room, Testing lab, Pantry room, Toilets and bath room(two nos and one attached), Corridor with lounge, Portico at front and side, Ramp etc.

ii) First floor shall have control room, PLCC room, office room, toilets and bath room etc.

* All internal walls shall 125 mm thick. (Excluding cement plastering)

* All external walls shall 250 mm thick. (Excluding cement plastering)

* For RCC works refer the relevant specification.

* The quarter shall be of framed RCC structure based.

* Concrete grade shall be 1:1.5:3 for all RCC works

* Reinforcement shall be Fe 415 Grade, confirming to IS:1786. All hooks, bands, laps shall be as per IS:456-2000. All laps shall be staggered and minimum lap length shall be 50X Dia of Bar.

* Clear cover to main reinforcement for footing = 50mm, column=50mm, beam=25mm & slab=20mm.

* Rain water pipes 100 sq mm to be provided at suitable location.

* The stair case width=1100mm, Tread=300mm, riser=148/150mm and suitable platform at different level.

- * The height of the ground floor of the building from the finished plinth level (0.5 mtr from the finished ground level) shall be 3.9 mtrs and the height of the parapet wall shall be 750mm. The height of the first floor from the top of the roof of the first floor shall be 3.4 mtrs and the height of the parapet wall shall be 750mm. The stair case top shall be at a height of 2.75 mtrs from the top of the parapet top.
- * The stair case shall be RCC having Kotta stone fixing.

b) 132/33 KV & 220/33 KV S/S Building:

>The plinth area for the control room building shall be as below:-

Ground floor: 38mtrX13 mtr

Ground floor portico: 5mtrX5mtr

First floor: 19 mtr X 13 mtr.

i) Ground floor shall have Control room(also can be kept on the first floor for better visibility of switch yard area), PLCC room, Battery room, MCCDB room, Toilets and bath room, Verandah & Portico etc.. One no. room shall be used for ladies rest room & should have attached toilet facility meant for ladies staff is to be included in ground floor of the Control room building

ii) First floor shall have office rooms (3 Nos), a Library, a Conference room, a Rest room, Pantry room, toilets(2 No.) and toilet cum bath room (1 no.) etc.

- * All internal walls shall 125 mm thick. (Excluding cement plastering)
- * All external walls shall 250 mm thick. (Excluding cement plastering)
- * For RCC works refer the relevant specification.
- * The quarter shall be of framed RCC structure based.
- * Concrete grade shall be 1:1.5:3 for all RCC works
- * Reinforcement shall be Fe 415 Grade, confirming to IS:1786. All hooks, bands, laps shall be as per IS:456-2000. All laps shall be staggered and minimum lap length shall be 50XDia of Bar.
- * Clear cover to main reinforcement for footing = 50mm, column=50mm, beam=25mm & slab=20mm.
- * Rain water pipes 100 sq mm to be provided at suitable location.
- * The stair case width=1100mm, Tread=300mm, riser=148/150mm and suitable platform at different level.
- * The stair case shall be RCC having Kotta stone fixing.
- * The height of the ground floor of the building from the finished plinth level (0.5 mtr from the finished ground level) shall be 3.9 mtrs and the height of the parapet wall shall be 750mm. The height of the first floor from the top of the roof of the first floor shall be 3.4 mtrs and the height of the parapet wall shall be 750mm. The stair case top shall be at a height of 2.75 mtrs from the top of the parapet top.

1.5 Provision of rooms in the colony quarter (building).

a) **“D” Type quarter:** Tentative plinth area shall be **1075 sq ft (100 sq mtrs)**. D type quarter shall have two bed rooms of size 3.6 mtrX3.6 mtr having porticos; one bed rooms of size 3.9 mtrX3.3 mtr having portico; one living room of size 4.2 mtrX3.6 mtr; one dining cum lobby of size 4.2 mtrX4.7 mtr; one kitchen of size 2.75mtrX3.3 mtr; Two nos attached toilet cum bath room of size 2.15 mtr X 1.5mtr, one no common toilet cum bath room of size 1.5mtr X 2.2 mtr, Portico and space for vehicle parking. The kitchen shall have provision of Kitchen platform (granite one) two sides of the wall with stainless steel sink having water tap provision as per standard practice. Kitchen room shall have provision of cupboard for storing the kitchen utensils and other items including locking arrangement of the cup board. Provision of cup-boards in all other rooms as per standard practice shall be provided. Shall have stair case to go to the top of the roof and have stair case head room. A portico of adequate size in front of the quarter/flat to be provided to park the four & two wheeler vehicle.

b) **“E” Type quarter:** Tentative plinth area shall be 650 sq ft (61 sq mtrs). E type quarter shall have two bed rooms of size 3.3 mtrX3.3 mtr having porticos; one no attached toilet cum bath room of size 2.15 mtr X 1.5mtr, one no common toilet cum bath room of size 1.5mtr X 2.2 mtr, one living room of size 4.5 mtrX3.3 mtr Portico and space for vehicle parking. The kitchen shall have provision of Kitchen platform (granite one) two sides of the wall with stainless steel sink having water tap provision as per standard practice. Kitchen room shall have provision of cupboard for storing the kitchen utensils and other items including locking arrangement of the cup board. Provision of cup-boards in all other rooms as per standard practice shall be provided. Shall have stair case to go to the top of the roof and have stair case head room. A portico of adequate size in front of the quarter/flat to be provided to park the four & two wheeler vehicle.

- * All internal walls shall 125 mm thick. (Excluding cement plastering)
- * All external walls shall 250 mm thick. (Excluding cement plastering)
- * For RCC works refer the relevant specification.
- * The quarter shall be of framed RCC structure based.
- * Concrete grade shall be 1:1.5:3 for all RCC works
- * Reinforcement shall be Fe 500 Grade, confirming to IS:1786. All hooks,bands,laps shall be as per IS:456-2000.All laps shall be staggered and minimum lap length shall be 50XDia of Bar.
- * Clear cover to main reinforcement for footing = 50mm,column=50mm,beam=25mm & slab=20mm.
- * Rain water pipes 100 sq mm to be provided at suitable location.
- * The stair case width=1100mm,Tread=300mm, riser=148/150mm and suitable platform at different level.
- * The stair case shall be RCC having Kotta stone fixing.
- * The height of the building from the finished plinth level (0.5 mtr from the finished ground level) shall be 3.15 mtrs i.e. up to the terrace level. A clear 1.15 mtrs shall be above the terrace and up to the top of the parapet. The stair case top shall be at a height of 2.75 mtrs from the top of the parapet top.
- * Details of doors & windows to be provided in the colony quarters are as indicated below.

All the frame of doors & windows shall be of M.S as per below.

The doors and windows of the colony quarters shall be of M.S with M.S grill and all the frames of doors and windows also of M.S sections in accordance with the relevant latest IS Codes for construction of building. Size and shapes shall be adequate for entering in to the room. The windows shall be centre open & twin panel type, rigidly hinged on the frame with minimum three hinges on one side for windows & minimum four hinges for doors. All the panel of the external doors and windows shall also be of M.S sheet having minimum thickness of 03 mm, with proper support on the frame of the door for rigidity & the support shall also be of M.S flat having minimum size of 25X5 mm. The Door frames & Chaukat shall be of 45X45X6 mm M.S (G.I) sections. The window frame & Chaukat shall be of 25X25X6 mm M.S (G.I) sections. Proper locking arrangement with stoppers to be provided on the door and windows. Surface cleaning, application of red oxide primer paint and two coats of synthetic enamel paint (Asian paints/Berger/Nerolac) of the doors, windows & grill are to be provided. All the windows shall be provided with M.S grill and care should be taken while designing the grill frame that the entering of cat should be restricted.

The inside doors of the quarters shall be one side open & the panels shall be of flush type, water, termite & weather proof resistant hard board of minimum 32 mm thickness (reputed make of ISI brand hard board flush type door) & the door shall be hinged with the door frame with suitable support for rigidity. The Door frames / Chaukat shall be of extruded aluminium sections suitably anodised. Surface cleaning, application of red oxide primer paint and two coats of synthetic enamel paint (Asian paints/Berger/Nerolac) of the inside doors are to be provided. Proper locking arrangement with stoppers to be provided on the door. The size of the door frame/chaukat shall be as indicated in the specification. Size of the door frame/ chaukat shall be 39 inchX78 inch (inside to inside). The flush door panel shall be of size 39 inchX78 inch. The door for the kitchen and toiletcum bath room shall be of standard adequate size PVC door shall be provided.

Anodised aluminum work for inside doors and ventilators shall be provided and fixed in the quarters with extruded built up standard sections of approved make conforming to IS: 7333 and IS:1285, anodized transparent or dyed to required shade according to IS:1868 (Minimum anodic coating of grade AC 15) fixed with raw plugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions at top, bottom and sides with required PVC/neoprene felt etc and joined mechanically wherever required including cleat angle, Aluminium snap beading for glazing/paneling, C.P. brass/stainless steel screws including glazing and fittings as specified.

ventilators shall be provided and fixed with hinges/pivots fittings wherever required including PVC/neoprene gasket.

The building design shall provide for the collection of storm water from the roofs. This water shall be collected in junction boxes and these boxes shall drain to the main drainage system of the station.

Cast iron rain water downcomers conforming to IS:1230 with water tight lead joints or medium class galvanised mild steel pipes conforming to IS:1239/ IS:3589, shall be provided to drain off the rain water from the roof. These shall be suitably concealed with masonry work of cement concrete or cladding material. The number and size of downcomers shall be governed by IS:1742 and IS:2527.

All drains inside the buildings shall have minimum 40 mm thick grating covers and in areas subject to movement heavy equipment loads, precast RCC covers shall be provided in place of steel grating.

For all buildings, suitable arrangement for draining water collected from equipment blowdowns, leakages, floor washings, fire fighting etc. shall be provided for each floor.

17. 0 MISCELLANEOUS GENERAL REQUIREMENTS

Dense concrete with controlled water cement ratio, preferably 0.45, shall be used for all underground concrete structures such as pump-house, tanks, water retaining structures, cable and pipe trenches etc. for achieving water-tightness.

All joints including construction and expansion joints for the water retaining structures shall be made water tight by using PVC ribbed water stops with general bulb. However, kicker type (externally placed) PVC water stops shall be used for the base slab and in other areas where it is required to facilitate concreting. The minimum thickness of PVC water stops shall be 5 mm and minimum width shall be 230 mm.

All steel sections and fabricated structures which are required to be transported by sea shall be provided with anti corrosives paint.

All mild steel parts used in the water retaining structure shall be hot-dip galvanised. The minimum coating of the zinc shall be 750 gm/sq.m. for galvanised structures and shall comply with IS:2629 and IS:2633. Galvanizing shall be checked and tested in accordance with IS:2629. The galvanizing shall be followed by the application of an etching primer and dipping in black bitumen.

A screed concrete layer not less than 100 mm thick and of grade not weaker than M10 conforming to IS:456- 1978, shall be provided below all water retaining structures. A sliding layer of bitumen paper or craft paper shall be provided over the screed layer to destroy the bond between the screed and the base slab concrete of the water retaining structures.

Bricks having minimum 75kg/sq.cm compressive strength can only be used for masonry work. Bidder shall ascertain himself at site regarding the availability of bricks of minimum 75kg/ sq.cm compressive strength before submitting his offer.

Monorails, monorail girders and fixtures shall be provided, wherever required.

Doors and windows on external walls of buildings other than areas provided with insulated metal claddings shall be provided with a RCC sun-shade over the openings with 300 mm projection on either side of the openings. Projection of sunshade from the wall shall be minimum 450 mm over window openings and 750 mm over door openings.

All stairs shall have maximum riser height of 180 mm and a minimum tread width of 250 mm. Minimum width of stairs shall be 1200 mm. There shall be provision of of stair case to the roof of the building.

Angles of 50x50x6 mm minimum with lugs shall be provided for edge protection all round cut out and openings in floor slab, edges of drains with grating covers, edges of RCC cable/pipe trenches with covers, edges of manholes with covers, edges of precast covers and any other place where breakage of corners of concrete is expected.

Anti termite chemical treatment shall be given to column pits, wall trenches, foundations of buildings, filling below the floors etc. as per IS:6313 and other relevant Indian Standards.

Handrailing of a minimum height of 900 mm shall be provided around all floor or roof openings, projections and balconies walk ways, platforms, steel stairs etc. All handrails and ladder pipes shall be The railing of the staircase shall be made of proper aluminium sections. All rungs for ladders shall also be of aluminium as per IS:.

For RCC stairs, also handrailing with aluminium sections are to be provided.

18. 0 INTERFACING

Proper coordination and execution of all interfacing civil works activities such as fixing of conduits in roofs/walls/floors, fixing of foundation bolts, fixing of lighting fixtures, fixing of supports/embodiments, provision of cut-outs etc. shall be the sole responsibility of the contractor. He shall plan all such activities in advance and execute in such a manner that interfacing activities do not become bottlenecks and such that dismantling, breakage etc. is reduced to minimum.

19. WATER SUPPLY

The Contractor shall be overall responsible for supply of water within switch yard for fire fighting, drinking purposes and other miscellaneous purposes. Water shall be made available at a single point by the Employer. The scope is also inclusive of supply and erection of all tanks, pipes, fittings etc. required for the water supply to be taken from the terminal point to the respective buildings. A scheme shall be prepared by the contractor indicating the layout and details of water supply which shall subject to the approval of the Engg Incharge (Divisional Engr.) before actual start of work. Any extra bore holes required shall be within the scope of the contractor.

There shall be separate bore wells for the control room building and colony quarters. There shall be pump houses for the bore wells and approach road to the pump houses shall be provided.

The Contractor shall have overall responsibility to provide a suitable arrangement for permanent supply for and retention of water within switch yard building and to the yard for watering to the earth pits, drinking purposes as well as for township and other miscellaneous purposes. The scope is inclusive of supply and erection of all tanks, pipes, fittings etc. required for the water supply to be taken from the terminal point/points to the respective buildings. A scheme shall be prepared by the contractor indicating layout and details of water supply which shall subject to the approval of the Engg Incharge (Divisional Engr.) before commencement of work. Any extra bore holes required shall be within the scope of this contract. The capacity of each submersible pump shall be 5 HP and all control as per standard has to be provided. The no of bore holes shall be two nos , one for colony township and the other one for the switch yard building. Two nos pump house as per standard are also within the scope of this contract. The height of the pump house (LXW=3mtrsX3mtrs) shall be 3 mtrs and shall have RCC roof and brick walls having MS doors. The capacity of RCC overhead tank for control room building shall be 2000 liters each .Two nos of overhead water tank for control room building and for colony quarters each quarter shall have 1000 liters capacity.

There shall be interconnection between tow pump sections in order to meet any exigencies.

20. 0 STATUTORY RULES

The Contractor shall comply with all the applicable statutory rules pertaining to Factories Act (as applicable for ORISSA State), Fire Safety Rules of Tariff Advisory Committee, Water Act for pollution control etc.

Provisions for fire proof doors, numbers of staircases, fire separation wall, plastering on structural members (in fire prone areas) etc. shall be made according to the recommendations of Tariff Advisory Committee.

Statutory clearance and norms of State Pollution Control Board shall be followed as per Water Act for effluent quality from plant.

21.0 SECURITY WATCH TOWERS:

There shall be provision of security watch tower at the corners of the switch yard. These watch towers shall be of RCC type. Standard practice in this effect shall be followed. The maximum numbers of such towers shall be 4. The size of the tower platform shall be 2.5mtrsX2.5mtrs and height as per standard practice.

22.0 SECURITY SHED NEAR THE MAIN GATE.

There shall be one RCC type security shed near the main gate to be provided. The shed shall have also provision of sitting arrangement for the guests. The shed shall be provided with telephone internal, electrical lighting, ceiling fan, water supply and toilet facilities. There shall be provision of gate lights. The size of the security cum guest shed shall be 5mtrsX3.5mtrsX3.5mtr (LengthXwidthXHeight). A portion of the shed shall be used for the guest who comes for visit the sub-station. Adequate no of MS doors and windows are also to be provided. Necessary paintings as per standard are also to be done.

23.0 PROVISION OF STORE SHED, PLAT FORM, RAMP AND WINCH FOR LIFTING MATERIALS & VEHICLE PARKING SHED.

23.1 One no store shed of size 15X15 mtr having brick walls and plastering with RCC roof of 15X15 meters. The flooring shall be of 75 mm thickness PCC (mix ratio 1:2:4) over RR masonry works (as per standard practice of flooring). Provision of adequate nos of MS racks (proper paintings also to be done as per the direction of site in charge) for keeping the spare materials. The height of the shed shall be 4mtrs above the plinth.

23.2 One no platform outside the store shed RR masonry (compacted) with PCC at the top for storing the transformer bushings, Instrument transformers, transformer oil drums etc. The size of the platform shall be 20mtrX15 mtr. Details of flooring as mentioned under 24.1. The platform shall have top covers by using TATA GC sheets.

23.3 Provision of a RCC based ramp of adequate size for loading and unloading of the materials from the lorry near the store shed.

23.4 A winch is to be provided near the ramp for lifting and lowering of materials up to 5 tons capacity. The two side vertical pillars shall be by MS Rail/joist and the top horizontal also of same type. A chain pulley of 5 ton capacity is to be provided at the centre of the frame on the horizontal bar.

23.5 Erection of Isolator Mechanism Box.

Separate RCC foundation to be provided for the Isolator Mechanism boxes.

23.6 There shall be one no vehicle parking shed inside the sub-station area. The size of the parking area shall be 15mtrs X 15 mtrs, out of the entire area there shall be provision

of shed for 5 mtrs X 15 mtrs and rest of the area shall be without shed. The flooring of the entire area of the vehicle parking shall be as mentioned under 24.1.

24.0 ANTIWEED TREATMENT AND SITE SURFACING

SCOPE OF WORK

The contractor shall furnish all labour, equipment and materials required for complete performance of the work in accordance with the drawings, specification and direction of the Engg Incharge (Divisional Engr.).

General Requirement

The material required for site surfacing/gravel filling shall be free from all types of organic materials and shall be of standard approved quality, and as directed by the Engg Incharge (Divisional Engr.).

The Contractor shall furnish and install the site surfacing to the lines and grades as shown in the drawing and in accordance with the requirements and direction of the Engg Incharge (Divisional Engr.). The soil of the periphery area of the switchyard area shall be subjected to sterilisation or anti-weed treatment before placing the site surfacing/gravel fill material or strictly as per instruction or requirement of the manufacturer of the chemical required for soil sterilisation or anti-weed treatment. After all the structures and equipment have been erected and accepted, and soil sterilisation of the peripheral area (except the switch yard area) as specified is complete, the site shall be maintained to the lines and grades indicated in the drawing and rolled or compacted by using three ton roller with suitable water sprinkling to form a smooth and compact surface condition which shall be matching with finished ground level of the switchyard area.

Chemical to be used for soil sterilisation /anti-weed treatment:

The details of quantities and method of application of chemicals used for soil sterilisation /and anti-weed treatment shall be as per manufacturer`s recommendations. Bidders are required to submit the details of chemicals proposed to be used and recommendations of manufacturer with required guarantee alongwith their bids for necessary approval of the Engg Incharge (Divisional Engr.). Approval of the Engg Incharge (Divisional Engr.) by no means shall relieve the contractor of their contractual obligations as stipulated in General and Special Conditions of Contract.

25.0 PROVISION OF GARDEN INFRONT OF CONTROL ROOM BUILDING AND PLANTATION OF PLANTS (FRUIT BEARING & OTHER SHOW PLANTS):

A garden in front of the control room building is to be developed. It includes treatment of the land of size (30mtrsX10mtrs), manuring, and plantations of sufficient flower based, show based, crotons and entire portion shall be provided with garden grass. Proper land slope also to be maintained for better and aesthetic looking. Provision of water taps and garden lights at different locations are to be provided for watering the plants and lighting of the garden.

100 nos fruit bearing plants and 100 nos other show plants along the road side, near colony quarters and near control room building are required to be planted. Treatment of the soil and manuring are to be done before plantation of these plants. Water taps at different locations are to be provided for watering the plants.

26.0 RAINWATER HARVESTING:

In addition to drainage of rainwater, the contractor shall make arrangement for rainwater harvesting also.

Rainwater harvesting shall be done by providing two numbers recharge structures with bore wells. The recharge structures shall be suitably located within the S/S. Branch drains from the main drain carrying rainwater from entire switchyard shall be connected to the recharge structures.

The internal diameter of recharge shafts shall be 4.5 meter with 230mm thick lining of brick work upto a depth of 2.0 meter from ground level and 345mm thick brickwork below 2.0 meter depth. The brickwork shall be constructed with cement mortar 1:6 (1 cement : 6 coarse sand). The overall depth of shaft shall be 5.0 meter below invert level of drain. The shaft shall be covered with RCC slab for a live load of 300Kg. per Sq.m. two openings of sizes 0.7X0.7 meter shall be provided in the RCC cover slab as shown in the drawing. An iron cover made of 5mm thick chequered plate with hinges shall be provided in the openings. Galvanized M.S. rungs of 20mm diameter at spacing of 300mm shall be provided in the wall of the shaft below the opening of the RCC slab to facilitate cleaning of shaft.

A 300mm diameter bore well shall be drilled in the centre of the shaft. The depth of bore well shall be 5.0 meter more than the depth of the sub soil water.

A 100mm diameter medium duty MS pipe conforming to IS 1161 shall be lowered in the bore well keeping bail plug towards bottom of bore well. The pipe shall have 1.58mm holes for 4.0 meter length starting from 1.0 meter from bottom of bore well. Holes of 3.0mm dia. shall be provided for a length of 2.0 meter starting from the bottom level of coarse sand and downwards. The overall length of the pipe shall be equal to the total depth of the bore well plus depth of shaft.

Gravel of size 3mm to 6mm shall be filled around 100 dia MS pipe in the bore well. The shaft shall be filled with 500mm thick layers each from the bottom of shaft with boulders of size 50mm to 150mm, gravel of size 5mm to 10mm, coarse sand having particle size 1.5mm to 2.0mm and boulders of size not less than 200mm respectively.

27.0 Fire water Tank: This is a lump-sum item. The contractor shall be required to complete the work in all respect as per requirement. All the items including excavation, compaction, brick work, roof truss, corrugated A.C. Sheet roofing, all types of miscellaneous steel internal and external plastering, painting, etc shall be deemed to be included in this lump-sum water tank. However the concrete (all types), reinforcement and the steel embedments (except roof truss & purlins) shall be measured and paid on lumpsum basis.

MORE ON CIVIL WORKS

I) WATER SUPPLY (EXTERNAL)

- (i) Water shall be made available by Owner (unless stated otherwise elsewhere) at any feasible point near scope boundary at single point to the contractor. Contractor shall state the total water requirement both in terms of quantity and head to the Owner.
- (ii) The contractor shall carry out all the external plumbing/erection works required for supply of water to the control room building beyond the single point as at (i).
- (iii) The contractor shall carry out all the plumbing/erection works required for supply of water to fire water tank beyond the single point as at (i).
- (iv) A scheme shall be prepared by the contractor indicating the layout and details of water supply which shall be got approved from the Owner before actual start of work including all other incidental items not shown or specified but as may be required for complete performance of the works.
- (v) Bore wells and pumps for water supply is not in the scope of contractor.

II) TECHNICAL DETAILS OF THE BUILDINGS

1. 12mm cement plaster of mix 1:6 (1 cement: 6 fine sand) shall be provided on the smooth side of internal walls.
2. 6mm cement plaster of mix 1:3 (1 cement: 3 fine sand) to all ceiling.
3. 15mm cement plaster of mix 1:6 (1 cement: 6 fine sand) on rough side of single or half brick wall.
4. 12mm thick per-laminated three layer medium density (exterior grade) particle board Grdel, Type II conforming to IS: 12823 bonded with phenol formaldehyde synthetic resin, of approved brand and manufacture shall be provided in paneling fixed in aluminium doors, windows shutters and partition frames with C.P. brass/stainless steel screws etc. complete as per architectural drawings and directions of engineer-in charge.
5. Distemping on all internal walls and ceilings with oil bound washable distemper of approved brand and manufacture to give an even shade (two or more coats) over and including priming coat with cement primer.
6. Enamel Painting with synthetic enamel paint of approved brand and manufacturer of required colour to give an even shade shall be provided on the steel glazed doors, windows, ventilators and rolling shutters in various buildings as

specified in drawings. Two or more coats over an under coat of suitable shade with primer paint of approved brand and manufacture.

7. Two or more coats of French spirit polishing with a coat of wood filler shall be provided on the wooden doors of Control Room building.

8. ACDB and DCDB room in Control Room building and FPH building shall be provided 52mm thick cement concrete flooring with hardcrete+ concrete hardener topping under layer 40mm thick cement concrete 1:2:4 (1 cement :2 coarse sand : 4 graded stone aggregate 20mm nominal size) and top layer 12mm thick metallic concrete hardener consisting of mix 1:2 (1 cement hardener mix:2 stone aggregate 6mm nominal size) by volume with which hardcrete+ hardening compound of Snowcem India Ltd+ or equivalent is mixed @ litre hardcrete+ per 50kg of cement including cement slurry, complete. (In ACDB/DCDB Room and FPH building only).

9. Cement plaster skirting (up to 15 cm height) with cement mortar 1:3 (1 cement:3 coarse sand) mixed with metallic concrete hardener in same ratio as for floor finished with a floating coat of heat cement. 21 mm thick in ACDB/DCDB room.

10. Floor tiles of Polished porcelain (vitrified) in different sizes with water absorption less than 1% and flexural strength not less than 30 N/mm² in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement: 4 coarse sand) including grouting the joints with white cement and matching pigments shall be provided as mentioned in drawings. Size of Tile shall be 50X50 cm.

11. 1st Quality Ceramic glazed floor tiles (anti-skid) 300 x 300mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS:13755 of NITCO, ORIENT, SOMANY, KAJARIA or equivalent shall be provided in toilet/pantry area in all colour shades as approved by Engg-incharge laid on 20mm thick cement mortar 1:4 (1 cement: 4 coarse sand) including pointing the joints with white cement and matching pigment etc complete.

12. 1st quality ceramic glazed tiles conforming to IS:13753 of minimum thickness 5mm of approved make like NITCO, ORIENT, SOMANY, KAJARIA or equivalent make shall be provided in toilet/pantry area in all colours shades of any size as approved by Engg-incharge in dados (height as specified in drawings) over 12mm thick bed of cement mortar 1:3 (1 cement:3 coarse sand) and jointing with grey cement slurry @3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete.

13. 13mm polished granite in cement mortar 1:4, 20mm thick made to a level cut to size shall be provided and laid as specified in drawings. The joints are filled with jointing compound matching to the tiles. Wherever granite tiles are specified for the floor, 100mm granite skirting shall be provided with the walls. The granite outer surface shall be flushed to the plaster finish of the wall.

14. Granite counter shall be provided and fixed in the pantry with 18mm granite slab mounted on 75mm RCC slab supported by 115mm brick wall plastered on all sides as per the drawing. The shelves are made of 18mm thick well cut and polished white marble slabs. The outer side of the brick wall and the RCC slab visible in the front is finished with 18mm granite with edges molded on the exposed end. The shutters shall

be finished with 19mm particle finished laminate edge lapping. The shutters are to be provided with 100mm handleless and shutter locks. The inside of the shutter shall be painted with synthetic enamel paint.

15. All Brick work shall be with cement mortar 1:6 (1 cement :6 coarse sand). Half brick work masonry shall be with cement mortar 1:4 (1 cement: 4 coarse sand). Bricks used shall be of class-75.

16. Anti termite treatment shall be carried out for all buildings.

17. M.S. Rolling shutters as per drawing shall be provided and fixed interlocked together through their entire length and jointed together at the end by end locks mounted on specially designed pipe shaft with brackets along with ball bearing for rolling shutter, side guides and arrangements for inside and outside locking with push & pull operation including the cost of providing and fixing necessary 15.5 cm long wire springs grade No.2 and M.S. top cover of required thickness for rolling shutters. 80 x 1.25mm M.S. laths with 1.25mm thick top cover.

18. Circular/hexagonal M.S. sheet ceiling fan box shall be provided in the ceiling with clam p of internal dia. 140mm, 73mm height, 3mm thick rim, top and bottom lid of 1.5mm M.S. sheet. Lids shall be screwed in to M.S. box by means of 3mm round headed screws, clamps shall be made of 12mm dia M.S bar bent to shape s peer standard drawing with over all length as 80 cm.

19. Anodised aluminum work for doors, windows, ventilators and partitions shall be provided and fixed in control room building with extruded built up standard tubular and other sections of approved make conforming to IS: 7333 and IS:1285, anodized transparent or dyed to required shade according to IS:1868 (Minimum anodic coating of grade AC 15) fixed with raw plugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions at top, bottom and sides with required PVC/neoprene felt etc and joined mechanically wherever required including cleat angle, Aluminium snap beading for glazing/paneling, C.P. brass/stainless steel screws including glazing and fittings as specified.

Shutters of doors, windows and ventilators shall be provided and fixed with hinges/pivots fittings wherever required including PVC/neoprene gasket.

(a) SPECTION FOR AL. WINDOWS:

Shutters bottom section-61.85x37x45.5 WS 1027, 1.058 Kg/mt, side and top section 61.85X31.75, WS 1029, 0.650 Kg/mt, shutter sections, one side and both side open 40X18X10 WS 1023, 0.433 Kg/mt, Interlock sections 40X18X26.5X10, WS 1022, 0.530 Kg/mt, with 4 mm plain float glasses, PVC gaskets, Nylon wheels, Aluminium handles cum locks. Indal/Indal/Hinalco make as per drawing.

(b) SECTION FOR AL. DOORS:

Anodised aluminum work for doors, windows, ventilators and partitions shall be provided and fixed in control room building with extruded built up standard tubular and other sections of approved make conforming to IS: 7333 and IS:1285, anodized transparent or dyed to required shade according to IS:1868 (Minimum anodic coating

of grade AC 15) fixed with raw plugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions at top, bottom and sides with required PVC/neoprene felt etc and joined mechanically wherever required including cleat angle, Aluminium snap beading for glazing/paneling, C.P. brass/stainless steel screws including glazing and fittings as specified.

Shutters of doors, windows and ventilators shall be provided and fixed with hinges/pivots fittings wherever required including PVC/neoprene gasket. Anodised aluminum work for doors, windows, ventilators and partitions shall be provided and fixed in control room building with extruded built up standard tubular and other sections of approved make conforming to IS: 7333 and IS:1285, anodized transparent or dyed to required shade according to IS:1868 (Minimum anodic coating of grade AC 15) fixed with raw plugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions at top, bottom and sides with required PVC/neoprene felt etc and joined mechanically wherever required including cleat angle, Aluminium snap beading for glazing/paneling, C.P. brass/stainless steel screws including glazing and fittings as specified.

Shutters of doors, windows and ventilators shall be provided and fixed with hinges/pivots fittings wherever required including PVC/neoprene gasket. with 5.5 mm plain float glasses and rubber gasket with bottom three feet pre-laminated sheet of 12mm thick of colour grey, ivory Jindal/Indal/Hindalco make as per drawing.

(c) SECTION FOR AL. PARTITION:

Outer frames 2-1/2 x 1-1/2, 63.5 x 38.10 X 1.5mm, DP 1212, 0.700 Kg/mt, to work as fixed partition & door with door verticals 44.45 x 47.62 x 1.5mm, DP 2022, 0.850 Kg/mt, top and center pieces as per drawing.

20. Cement based water proofing treatment of roofs, balconies, terraces etc. shall be provided with average thickness of 120 mm and minimum thickness at Khurra as 65 mm and laid consisting of following operations:

- (a) A slurry coat of neat cement using 2.75 kg/m² of cement admixed with proprietary water proofing compounds conforming to IS: 2645 shall be applied and grouted over the RCC slab including cleaning the surface before treatment.
- (b) Plain Cement concrete 1:5:10 (1 Cement : 5 fine sand : 10 burnt brick aggregate of 40 mm nominal size) admixed with proprietary water proofing compound conforming to IS:2645 over 20 mm thick layer of cement mortar of min :5 (Cement :5 coarse sand) admixed with proprietary water proofing compound conforming to IS: 2645 to required slope and treating similarly the adjoining walls upto 300 mm height including rounding of junctions of walls and slabs.
- (c) After two day of proper curing, a second coat of cement slurry admixed with proprietary water proofing compound conforming to IS:2645 shall be applied.
- (d) The surface shall be finished with 20 mm thick joint less cement mortar of mix 1:4 (1 cement :4 coarse sand) admixed with proprietary water proofing compound conforming to IS : 2645 and finally the surface shall be finished with trowel with neat cement slurry and making of 300 x 300 mm square.

- (e) The whole terrace so finished shall be flooded with water for a minimum period of two weeks for curing and for final test. All above operations shall be done in order as directed and specified by the Engineer-in charge.

21. Unplasticised rigid PVC rain water pipes 110 mm dia shall be provided and fixed on the wall face conforming to IS : 13592 type A as per drawing including jointing with seat ring conforming to IS:5382 leaving 10 mm gap for thermal expansion single socketed pipes.

22. Unplasticised PVC Moulded fittings / accessories including 110 mm bend and 110 mm shoes shall be provided and fixed for unplasticised rigid PVC rain water pipes conforming to IS : 13592 type A including jointing with seat ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion.

- Unplasticised PVC pipe clips of approved design shall be provided and fixed to unplasticised 110 mm PVC rain water pipes by means of 50x50x50 mm hard wood plugs, screwed with MS screws of required length including cutting brick work and fixing in cement mortar 1:4 (1 cement : 4 coarse sand) and making good the wall etc.
- Double action hydraulic floor spring of approved brand and manufacture IS: 6315 marked %hardwyn+make (model 3000) or equivalent for doors shall be provided and fixed at the following door including cost of cutting floors as required, embedding in floors and cover plates with brass pivot and single piece MS sheet outer box with slide plate etc. as per the direction of Engineer- in charge. With stainless steel cover plate:
 - (a) Main Entrance to Control Room Building.
 - (b) Sub-Station In charge room
 - (c) Conference Room
 - (d) Control Room.
- Plinth protection 50 mm thick of cement concrete 1:2:4 (1 cement :2 coarse sand : 4 graded stone) aggregate 20 mm nominal size) shall be laid over 75 mm bed of dry brick ballast 40 mm nominal size well rammed and consolidated and shall be grouted with fine sand including finishing the top smooth.
- Coloured vitreous china pedestal type water closet (European type) with seat and lid, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design including painting of fittings and brackets, cutting and making good the walls and floors shall be provided for all toilets.
- Coloured vitreous china wash basin of size 630 x 450 mm with C.I / M.S brackets alongwith single 15 mm C.P brass pillar taps, Kingston / Gem / Techno / Parko. 32 mm C.P brass waste of standard pattern, shall be provided and fixed in the toilets including painting of fittings and brackets, cutting and making good the walls wherever required alongwith C.P brass trap and C.P brass union.

- All urinals shall be coloured vitreous china flat back half stall urinal of 580 x380x350 mm with 10 litre PVC automatic flushing cistern, Parryware / Hindware / Seabird / Orient (Coral) with fittings, standard size C.P. brass flush pipe, speaders with unions and clamps (all in C.P. brass) with waste fitting as per IS : 2556 C.I. trap with outlet grating and other couplings in C.P brass including painting of fittings and cutting and making good the walls and floors wherever required.
- Following fittings shall be provided in all the toilets :
 - (a) Toilet paper roll holder.
 - (b) Double type coat & hat hooks with flanges, fixed to wall / shutter, etc. with necessary screws, washers & plugs.
 - (c) CP / PP liquid soap holder of approved make fixed with each wash basin to the wall with necessary CP / PP brackets, CP screws, washers, plugs etc.
 - (d) 100 mm dia vitreous chinaware half round channel of approved make fixed to correct grade, level, opening for floor trap below urinals set in CM 1:3 & pointed using white cement etc.
 - (e) CP brass bid cock 15 mm nominal bore of approved quality conforming to IS : 8931.
 - (f) CP brass angle valve of 15 mm nominal bore provided and fixed in position for basin and cistern points of approved quality conforming IS : 8931.
 - (g) Best quality marble partition slab provided and fixed in position for urinals, of size 610 x 1150 mm, 20 mm thick, polished on both sides & machine cut, exposed corners rounded etc.
 - (h) Towel rail of approved make of 600 mm length, 25 mm dia with a pair of brackets or flanges provided and fixed to wall beside each wash basin / set of wash basin with necessary screws, plugs, etc.
 - (i) 6 mm thick beveled edge mirror 1000 x 600 mm shall be provided and fixed mounted on 12 mm thick water proof plywood backing and hardwood beading all-round and mirror fixed to the backing with 4 Nos. of CP cap screws & washers, including fixing the mirror to the wall with necessary screws, plugs & washers etc, with each wash basin.
 - (j) Salem Stainless steel A ISI 304 (18/8) Kitchen sink of 510 x 1040 mm Bowl depth 178 mm with drain board shall be provided and fixed as per IS: 13983 with C.I. Brackets and stainless steel plug 40 mm including painting of fittings and brackets, cutting and making good the wall.

23) GI Pipe work for Internal and External works:

- i) All concealed GI pipe shall be painted with anticorrosive bitumastic paint including cutting of chases and making good the wall.

- ii) All exposed GI pipes and fittings shall be painted with synthetic enamel paint of desired shade over a ready mixed priming coat, both of approved quality for new work.
- iii) Wherever GI pipe are buried the same shall be provided and laid in position including trenching sand cushion and refilling, painted with anticorrosive bitumastic paint etc.
- iv) Gun metal ball valve with operating levers, non-return valves conforming to IS specification shall be provided and fixed in position as per drawing or direction of Engineer-in-charge.

24) Masonry chamber for sluice valve shall be 600x600mm size in plan and depth 750mm, or matching with the site condition inside with 50 class designation brick work in cement mortar 1:5 (1 cement :5 fine sand) with CI surface box 100mm. Top diameter, 160mm bottom dia and 180mm deep (inside) with chained lid and RCC top slab 1:2 :4 mix (1 cement :2 coarse sand: 4 graded stone aggregate 20 mm nominal size) necessary excavation foundation concrete 1:5:10 (1 cement:5 fine sand :10 graded stone aggregate 40mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12 mm thick finished with a floating coat of neat cement complete as per standard design with FPS bricks of class 75.

25) Polyethylene water storage tanks (2 nos. of 2000 litres capacity each) shall be provided and placed on roof of control room building of approved brand and manufacturer with cover and suitable locking arrangement, float valve and making necessary holes for inlet, outlet and overflow pipes.

- 26) PVC floor traps of self cleansing design shall be provided & fixed in position with outlet size of 75mm diameter of approved make, including making connection with PVC soil/waste pipes using rubber gaskets, embedding the trap in 150mm thick PCC 1:2:4, providing & fixing of top tile & strainer of CP or PVC on top of the trap etc.

- 27) Square-mouth SW gully trap grade $\frac{1}{4}$ +100x100mm size P type with FPS Bricks class designation 75 shall be provided and fixed complete with CI grating brick masonry chamber with water tight C.I. cover with frame of 300x300mm size (inside) the weight of cover to be not less than 4.5 Kg and frame to be not less than 2.70 Kg as per standard design.

28) Glazed stoneware pipes of 150mm diameter grade $\frac{1}{4}$ shall be provided, laid and jointed with stiff mixture of cement mortar in the proportion of 1:1 (1 cement: 1 fine sand) including testing of joints etc. complete.

29) Cement concrete 1:3:6 (1 cement:3 coarse sand:6 graded stone aggregate 40 mm nominal size) shall be provided and laid around S.W. pipes including bed concrete.

30) Brick masonry manhole shall be constructed in cement mortar 1:4 (1 cement:4 coarse sand) RCC top slab with 1:2:4 mix (1 cement:2 coarse sand: 4 graded stone aggregate 20mm nominal size) foundation concrete 1:4:8 mix (1 cement:4 coarse sand:8 graded stone aggregate 40mm nominal size) inside plastering 12mm thick with cement mortar 1:3 (1 cement:3 coarse sand) finished with floating cot of neat cement and making channels in cement concrete 1:2:4 (1 cement:2 coarse sand:4 graded stone aggregate 20mm nominal size) finished with a floating coat of neat cement complete³ as per standard design.

- a) Inside size shall be 90 x 80 cm and 60 cm deep including CI cover with frame (light duty) 455 x 610 mm internal dimensions total weight of cover and frame shall not be less than 38 kg (weight of cover 23 kg and weight of frame 15 kg) and shall be constructed with F.P.S. bricks with class designation 75.
- b) Inside size shall be 120 x 90 cm and 90 cm or more deep including CI cover with frame (medium duty) 500 mm internal diameter total weight of cover and frame to be not less than 116 kg (weight of cover 58 Kg and weight of frame 58 kg) with FPS Bricks class designation 75.
- 31) MS foot of 20 x 20 mm square rests shall be provided and fixed in manholes with 20 x 20 x 10 cm cement concrete blocks 1:3:6 (cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) as per standard design.
- 32) Steel glazed doors, windows and ventilators of standard rolled steel section shall be provided and fixed in FFPH building, joints mitred and welded with 15 x 3 mm lugs, 10cm long, embedded in cement concrete blocks 10 x 10 x 10 cm of 1:3:6 (1 cement 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) or with wooden plugs and screws or rawls plus and screws or with fixing clips or with bolts and nuts as required, including providing and fixing of glass panes with glazing clips and special metal sash putty of approved make complete including applying a priming coat of approved steel primer, necessary hinges or pivots as required.
- 33) Pressed steel door frames manufactured from commercial mild steel sheet of 1.25 mm thickness shall be provided and fixed in FFPH building including hinges jamb, lock jamb, bead and if required angle threshold of mild steel angle of section 50x 25 mm or base ties of 1.25 mm pressed mild steel welded or rigidly mixed together by mechanical means, adjustable lugs with split end tail to each jamb including steel butt hinges 2.5 mm thick with mortar guards, lock strike-plate and shock absorbers as specified and applying a coat of approved steel primer after pre-treatment of the surface as directed by Engineer-in-charge.
- 34) Asbestos cement 6 mm thick corrugated sheets roofing shall be provided and fixed with G, I, J or L hooks, bolts and nuts 8 mm diameter G, I plain and bitumen washers complete excluding the cost of purlins, rafters and trusses for water tank.

(III) MODE OF MEASUREMENT

(a) Earthwork

This shall include excavation in all kinds of soil including rock, all leads and lifts including back filling, compacting, de-watering (if required) and disposal of surplus earth to a suitable location. The quantity of excavation for foundations of towers, equipment structures, all transformers, rail-cum-road, firewall, cable trenches, water tank, reactors and buildings shall only be measured. The quantity of excavation for roads, drains, rainwater harvesting, septic tank, soak pit, external water supply system, site surfacing (graveling), chain link fencing (including gate) shall not be measured separately and shall be deemed to be included in the composite rates quoted by the bidder for the respective works. All other excavation required for the completion of the work including fixing of lamp posts, plinth protection, flooring sewerage system, manholes, pipes, earthmat etc. shall also not be paid for. The measurement of excavation of all concrete works shall be made considering dimension of the pit leaving 150 mm gap around the

base pad (lean concrete) or actually excavated pit, whichever is less. The quantity shall be measured in cubic meters.

(b) PCC

Providing and laying Plain Cement Concrete of all types and at all locations including all leads and lifts. The quantity shall be measured in cubic meters as per lines and levels indicated in the drawings.

(i) PCC 1:2:4 (1 cement : 2 sand : 4 coarse aggregate 20 mm nominal size) shall be measured in flooring of buildings, plinth protection, fencing, transformer foundation, reactor foundation, rail track, drain, culverts, septic tank, chain link fencing, gate etc. as indicated in the drawings.

(ii) PCC 1:4:8 (1 cement : 4 coarse sand : 8 stone aggregate, 40 mm nominal size) shall be measured below all foundations of buildings, cable trench, roads, under flooring, rail-cum-road, transformer foundation, reactor foundation, drain, water tank, culverts, gate etc. as indicated in the drawings.

(iii) All other PCC required for the completion of the work including hold fasts of doors / windows / rolling shutters, fixing of plumbing pipes, bedding concrete for sewer lines, embedment of electrical conduits etc. shall not be measured and deemed included in the composite rates quoted by the bidder for respective works. Water proofing compound wherever specified shall be added without any extra cost.

(c) RCC

Measurement of reinforced cement concrete at all locations shall be made and shall include all leads, lifts, formwork, grouting of pockets and underpinning, (but shall exclude reinforcement) of mix 1:1.5:3 (1 cement : 1.5 coarse sand : 3 stone aggregate 20 mm nominal size). This shall also include pre-cast RCC work and addition of water proofing compound wherever required for which no additional payment shall be made. The quantity shall be measured in cubic meters as per lines and levels indicated in the drawings. No deduction shall be made for volume occupied by reinforcement / inserts sleeves and for openings having cross-sectional area up to 0.1 sq.m.

(d) Steel Reinforcement

Reinforcement shall be measured in length (actual of theoretical as per drawing whichever is less) including hooks, if any, separately for different diameters as actually used in work, excluding overlaps. From the length so measured, the weight of reinforcement shall be calculated in tones on the basis of sectional weights as adopted by Indian Standards. Wastage, overlaps, couplings, welded joints, spacer bars, chairs, stays, hangers and annealed steel wire or other methods for binding and placing shall not be measured and cost of these items shall be deemed to be included in the rates for reinforcement.

(e) Stone filling

Measurement of stone (40mm nominal size) for transformer foundations shall be made as per theoretical volume of the space to be filled in the transformer foundation as per drawings. This shall be measured in cu.m.

1.1 Miscellaneous structural steel.

Measurement for Supply, fabrication, transportation and erection of all miscellaneous structural steel work for mono rails (RS joists), rails for transformers/reactors, trusses, frame work, purlins, gratings, steel tubes, built up sections along with

all other steel fittings and fixtures, inserts and embedment in concrete shall be made as per drawings. The unit rate for this item shall be inclusive of cutting, grinding, drilling, bolting, welding, pre-heating of the welded joints, applying a priming coat of steel primer and anti corrosive bitumastic paint/ synthetic enamel paint etc. (wherever specified), setting of all types of embedment in concrete, etc. steel required for foundation bolts, nuts and bolt, doors, windows, ventilators, louvers, rolling shutters, chain link fencing, gratings in drains, soil pipes, plumbing pipes, floor traps, embedments required for rainwater harvesting, septic tank, soak pit, roof truss and purloins required for fire water tank, etc. shall not be considered for payment and measurement.

Quantity shall be measured in Kg.

1.2 Roads

The measurement for the concrete roads shall be measured on LOT basis along with the entire line of the road and shall include all items such as excavation, compaction, rolling, watering, WBM, Kerb stone, grating, inter locking tiles etc. complete as per drawing but excluding concrete and reinforcement.

The measurement of bituminous road shall be measured on LOT basis along the center line of the road and shall include all items such as excavation, compaction, rolling, watering, sub case course, WBM, Bitumen, pre mix carpet complete as per drawing.

1.3 Drain

The measurement of drains shall be measured on LOT basis along the center line of the drain and shall include excavation, compaction, brickwork, plastering, grating, weep holes etc. complete as per drawing but excluding concrete.

(f) Antiweed Treatment and Stone Spreading

The measurement shall be done on LOT basis for the actual area in square meters of stone spreading provided in the switchyard and shall include anti weed treatment including material and providing and spreading of 100mm thickness of uncrushed/crushed/broken stone of 40mm nominal size as per the specification for the specified area.

(g) Chain Link Fencing and gate.

The measurement shall be made in running meters of the fence provided as per drawing. The rate shall be including the post, fencing, MS Flat etc. complete but excluding the concrete. The gate shall be measured in numbers.

(h) Fire Fighting Pump House

This is lump sum item, Contractor has to assess the quantity as per drawings of control room cum administrative building, Fire Fighting Pump House and quote for the same for each building separately. This shall include following items.

- 1) External plastering: 18 mm cement plaster of mix: 1:4 (1 cement : 4 coarse sand) including all grooves as specified.
- 2) Providing and applying two or more coats of Novakote exterior flat paint over an under coat of suitable pliolite based primer nova prime on new cement plaster surfaces of the buildings inclusive of required tools, scaffolding, materials and other painting accessories etc. as per recommendations of manufacturer.

(i) Hume Pipe

Hume pipe shall be measured diameter-wise and laid as per the drawings and shall be measured in running metres. The item shall be inclusive of excavation, laying, back filling, jointing etc. excluding concrete and reinforcement (if any).

(j) Building.

This is a lump sum item for each building. However, the quantity of excavation, concrete, reinforcement below the plinth level shall be measured as per described above. Quantity of concrete and reinforcement above the plinth level of the buildings shall be measured and paid under item mentioned above respectively. External finishing shall be measured and paid as mentioned in the BPS. The rest of the entire work required to complete the building in all respect as per the drawings furnished by the Owner shall be deemed to be included in this lump sum rate.

(k) Rain Water Harvesting:

This is a lump sum item. The contractor shall be required to complete the work in all respect as per drawings furnished by the Owner. All the items including excavation, miscellaneous steel, bricks work, fillings of boulders, gravel, sand, pipe etc. shall be deemed to be included in this lump sum rate. However, the concrete (all types) and the reinforcement shall be measured and paid under the item mentioned above.

(l) Septic Tank and Soak Pit.

This is a lump sum item. The contractor shall be required to complete the work in all respect as per drawings furnished by the Owner. All the items including excavation, masonry work, all types of fillings all types of pipes including plumbing and vent pipes, all type of fittings etc. shall be deemed to be included in this lump sum rate. However, the concrete (all types) and the reinforcement shall be measured and paid under the item mentioned above.

(m) Fire Water Tank.

This is a lump sum item. The contractor shall be required to complete the work in all respect as per drawings furnished by the Owner. All the items including excavation, compaction, brick work, roof truss, corrugated AC Sheet roofing, all types of miscellaneous steel, internal and external plastering, painting etc. shall be deemed to be included in this lump sum cost. However, the concrete (all types), reinforcement and the steel embodiments (except roof truss and purlins) shall be measured and paid under the item mentioned above.

(n) External water supply from Bore-well to Fire water tank.

The external water supply from Bore-well shall be on LOT basis. It shall include all the items such as excavation, piping, fittings, painting, brick work, sand filling, concrete, valves, chambers cutting chases in walls, openings in RCC and repairs etc. required to complete the job.

(III) MISCELLANEOUS GENERAL REQUIREMENTS:

(a) Dense concrete with controlled water cement ratio as per IS-code shall be used for all underground concrete structures such as pump-house, tanks, water retaining structures, cable and pipe trenches etc. for achieving water-tightness.

(b) All joints including construction and expansion joints for the water retaining structures shall be made water tight by using PVC ribbed water stops with central bulb. However, kicker type (externally placed) PVC water stops shall be used for the base slab and in other areas where it is required to facilitate concreting. The minimum thickness of PVC water stops shall be 5 mm and minimum width shall be 1230 mm.

(c) All mild steel parts used in the water retaining structures shall be hot-double dip galvanized. The minimum coating of the zinc shall be 750 gm/sq.m. for galvanized structures and shall comply with IS:2629 and IS:2633. Galvanizing shall be checked and tested in accordance with IS:2633. The galvanizing shall be followed by the application of an etching primer and dipping in black bitumen in accordance with BS:3416.

(d) Bricks having minimum 75 kg/cm² compressive strength can only be used for masonry work. Contractor shall ascertain himself at site regarding the availability of bricks of minimum 75 kg/cm² compressive strength before submitting his offer.

(e) Angles 50x50x5 mm (minimum) with lugs shall be provided for edge protection all round cut outs/openings in floor slab, edges of drains supporting grating covers, edges of RCC cable/pipe trenches supporting covers, edges of manholes supporting covers, supporting edges of manhole precast cover and any other place where breakage of comers of concrete is expected.

(f) Anti termite chemical treatment shall be given to column pits, wall trenches, foundations of buildings, filling below the floors etc. as per IS:6313 and other relevant Indian Standards.

(g) For all civil works covered under this specification, nominal mix by volume batching as per CPWD specification is intended. The relationship of grade of concrete and ratio of ingredients shall be below:

	Nom Mix.	Cement	Sand	Coarse aggregate of 20mm down grade as per IS: 383
1.	M 10	1	3	6
2.	M 15	1	2	4
3.	M 20	1	1.5	3

(h) The material specification, workmanship and acceptance criteria shall be as per relevant clauses of CPWD specification and approved standard Field Quality Plan,. Items/components of buildings not explicitly covered in the specification but required for completion of the project shall be deemed to be included in the scope.

(IV) INTERFACING

The proper coordination & execution of all interfacing civil works activities like fixing of conduits in roofs/walls/floors, fixing of foundation bolts, fixing of lighting fixtures, fixing of supports/embedment, provision of cut cuts etc. shall be the sole responsibility of the Contractor. He shall plan all such activities in advance and execute in such a manner that interfacing activities do not become bottlenecks and dismantling, breakage etc is reduced to minimum.

(V) STATUTORY RULES.

* Contractor shall comply with all the applicable statutory rules pertaining to factories act (as applicable for the State). Fire safety Rules of Tariff Advisory Committee. Water Act for pollution control etc.

* Statutory clearance and norms of State Pollution Control Board shall be followed as per Water Act for effluent quality from plant.

* Requirement of sulphate resistant cement (SRC) for sub structural works shall be decided in accordance with the Indian Standards based on the findings of the detailed soil investigation.

* All building/construction materials shall conform to the best quality specified in CPWD specifications if not otherwise mentioned in this specification.

* All tests as required in the standard field quality plans have to be carried out.

1. ORISSA POWER TRANSMISSION CORPORATION LIMITED

STANDARD FIELD QUALITY PLAN FOR SWITCHYARD CIVIL WORKS.
--

Section: FOUNDATION MATERIALS

Sl. No.	Component/Operation & Description of Test	Sampling Plan with basis	Ref. Document & acceptance	Testing Agency.	Remarks	Check
1.	CHECKING OF FOUNDATION MATERIAL					
A)	CEMENT					
i)	Fineness	One sample per lot of 100 MTR or part thereof from each source for MTCs and one sample per lot of 200 MT or part thereof from each source for site testing.	IS:456, IS:269, IS: 8112 IS:122 69, IS:1489 & OPTCL specification.	Manufacturer/ As per OPTCL approved lab.	Review of manufacturers test certificates (MTCs) and laboratory test results by OPTCL	
ii)	Compressive Strength					
iii)	Initial & final setting time					
iv)	Soundness					
v)	Heat of Hydration for low heat cement (Not applicable for OPC & PPC)					
vi)	Chemical Composition of Cement.	One sample per lot of 100 MT or part thereof from each for MTCs	IS:456, IS:269, IS: 8112 IS:1489 & OPTCL specification.	Manufacturer	Review of manufacturers test certificates by OPTCL	
B)	COARSE AGGREGATES					
i)	Determination of Particle size (Sieve Analysis)	One sample per lot of	IS:383, IS:2386 and	OPTCL approved lab.	Each source to be	
ii)	Flakiness Index					

iii) iv) v) vi) vii) viii) ix)	Crushing Value Specific Gravity* Bulk Density* Absorption Value* Moisture Content* Soundness of Aggregate** Presence of deleterious materials. * Applicable Design concretes only	100 cubic meter or part thereof from each source for each size. ** Applicable to concrete work subject to frost action.	OPTCL specification	However , Moisture content test for design mix concrete shall be done on all day of concreting at site.	approved by OPTCL Review and acceptance of test result by OPTCL.	
C)	FINE AGGREGATE					
i) ii) iii) iv) v) vi) vii)	Gradation/Determination of particle size (Sieve Analysis) Specific Gravity and density Moisture content Absorption Value Bulking Silt Content Test Presence of deleterious materials.	One sample per lot of 100 cubic meter or part thereof from each source	IS:383,IS:2386, IS:456 and OPTCL specification	OPTCL approved lab. However , Moisture content test for design mix concrete shall be done on all days of concreting at site.	Each source to be approved by OPTCL Review and acceptance of test result by OPTCL.	
D)	BRICKS					
i) ii) iii) iv)	Dimension tolerance Compressible Strength Water Absorption Efflorescence		OPTCL Specification.	OPTCL approved Lab.	Approved by OPTCL	
E)	WATER					
i)	Cleanliness (Visual Check)	Random	IS:456, IS:3025 and OPTCL specification. The water used for mixing concrete	Contractor.	Each source to be approved by OPTCL	

	<p>Chemical & Physical properties of water for checking its suitability for construction purposes</p> <p>* Applicable to design mix concrete only.</p>	<p>One sample per source</p>	<p>shall be fresh, clean and free from oil, acids and alkalies, organic materials, or other deleterious materials.</p> <p>IS:456, IS:3025 & OPTCL specification.</p>	<p>Contract or/ OPTCL Approved Lab.</p>	<p>Approved by OPTCL</p>	
--	--	------------------------------	--	---	--------------------------	--

**2. ORISSA POWER TRANSMISSION CORPORATION LIMITED
(Quality Assurance & Inspection Deptt.)**

Sl. No.	Component/Operation & Description of Test	Sampling Plan with basis	Ref. Document & acceptance norm	Testing Agency.	Remarks	Check
1.	REINFORCEMENT STEEL					
i)	Identification & size	Random	IS:432, IS:1139, IS:1786 & OPTCL Specification.	Contract or	Approved by OPTCL	
ii)	Chemical Analysis test	One sample per heat.	IS:432, IS:1139, IS:1786 OPTCL Specification.	Manufacturer	Review of manufacturers test certificate by OPTCL	
iii)	Tensile Test	One sample per lot of 40MT or part thereof for each size of steel conforming to IS:1139 and 5 MT	IS:432, IS:1139, IS:1786 OPTCL Specification.	Manufacturers/ OPTCL approved Lab.	Review of manufacturers test certificates as well as lab. Test results by	
iv)	Yield stress/proof stress					
v)	Percentage Elongation					

		or part thereof for HDS wire for each size of steel as per IS:432. For steel as per IS:1786 under 10mm 1 sample for each 25 MT or part thereof. 20 mm-16 mm 1 sample for each 35 MT or part thereof. Over 16mm 1 sample for each 45 MT or part thereof.			OPTCL
vi)	Bent/re-bend Test		IS:432, IS:1139, IS:1786 OPTCL Specification.	Manufacturers/ OPTCL	Review of manufacturers test certificates as well as lab. Test results by OPTCL
vii)	Reverse Bend Test for HDS wire.	One sample per lot of 20MT or part thereof for each size of steel as per IS:432, IS:1139. For steel as per IS:1786 under 10mm-16mm 1 sample for each 25MT or part thereof 10mm-	IS:432, IS:1139, IS:1786 OPTCL Specification.	Manufacturers/ OPTCL approved Lab.	Review of manufacturers test certificates as well as lab. Test results by OPTCL

		16mm 1 sample for each 45 Mt or part thereof. One sample per lot of 5MT or part thereof for each size.				
--	--	--	--	--	--	--

ODISHA POWER TRANSMISSION CORPORATION LIMITED

**OFFICE OF THE SR. GENERAL MANAGER,
CENTRAL PROCUREMENT CELL,
JANAPATH, BHUBANESWAR – 751022.**

**TECHNICAL SPECIFICATION
FOR
SWITCH YARD STRUCTURES**

**STRUCTURES FOR OUTDOOR EQUIPMENT
TABLE OF CONTENTS**

.....	1
ORISSA POWER TRANSMISSION CORPORATION LIMITED.....	1
GENERAL.....	3

0.1 Design of structures	3
0.2 Conductor spacing and clearances	3
0.3 Applied loads.....	3
0.3.1 Wind loads.....	3
0.3.2 Vertical loads.....	3
0.4 Electro mechanical loads	4
0.5 Construction	4
0.6 Material	4
1. 0 SUPPORT STRUCTURES OF SWITCHYARD	5
1.1 General	5
1.2 Design requirements	5
1.3 Design drawings, bill of materials and documents.	6
1.4 Fabrication of steel	7
1.5 Assembly	7
1.5.1 General	7
1.5.2 Bolting	7
1.5.3 Welding.....	7
1.6 Foundation bolts	8
1.7 Stub setting.....	8
1.8 Stability of structure	8
1.9 Grouting	8
1.10 Galvanising.....	8
1.11 Painting	9
2. 0 INSPECTION BEFORE DESPATCH.....	9
2.1 Testing and inspection.....	9
2.2 Despatch, handling and storage.	9
2.3 Test certificate.	9
3. 0 ERECTION.....	9
3.1 Safety precautions.....	10
3.2 Fire protection to steelwork.....	10
4. 0 WIDTH AND HEIGHT OF THE BUS AT SUB-STATION	10

GENERAL

1.1 Design of structures

Substation structures shall be designed in accordance with the requirements of IS 802. The wind pressures for the substation sites shall be as per data in schedules and wind pressure map of the State of Orissa.

Structures shall be designed to carry the equipment and associated connections, insulator sets, earth conductors and all fittings under all specified conditions of service of operation and loading.

The substation gantry structures shall be designed to carry the down lead spans and the Contractor shall be provided with the details and location of the terminal tower and the type of conductor used on the overhead line in order to do so. All structures intended to carry equipment or materials on more than one side of the structure shall be designed to cater for all possible stages of equipment erection, installation and maintenance. The substation gantry structures shall be designed to terminate the overhead line down lead spans which may enter ± 30 degrees horizontally and ± 15 degrees vertically.

1.2 Conductor spacing and clearances

Structures shall be dimensioned to maintain the specified minimum phase to earth, phase to phase and insulation height clearances under conditions of maximum conductor swing and sag. The spacing between individual phase conductors, and the clearance between clamps, arcing horns, jumper loops or other live metal and the structure steelwork and other obstacles, under all specified conditions of temperature and loading shall not be less than the specified values.

1.3 Applied loads

The assumed maximum simultaneous loadings on the substation structures shall be as follows:

1.3.1 Wind loads

The normal wind load shall be given by the wind pressure, as stated in the Schedules, acting on the whole projected area of the phase and earth conductors and, where applicable, the horizontal resultant of the maximum line and earth conductor tensions, together with the wind pressure, as stated in the Schedules, on 1.5 times the projected area of the members of one face of the structure plus the projected area of the plant being supported.

1.3.2 Vertical loads

The normal vertical load shall be the mass of the line and earth conductors, insulators, the plant item, insulator fittings, earth conductor fittings, spacers, line traps and ancillary apparatus where applicable. For the overhead line terminating span it shall be assumed that the mass of the conductors and earth wires shall include the actual total mass of the down lead span.

1.4 Electro mechanical loads

Electro dynamic forces due to short circuit conditions, snatch forces, aeolin vibration and other similar loads shall be computed and applied for design of structures. The different mechanical effects due to short circuit current etc. shall be estimated as per IEC 865 and CIGRE guide line No. 7

1.5 Construction

The structures shall be of an approved design and construction. All stressed members (tension and compression) of steel structures shall consist of rolled steel sections unless otherwise approved.

The material used for the members shall not be less than 6 mm thick except for unstressed members where the thickness may be reduced to 4 mm.

No bolt hole shall be more than 1.5 mm larger than the corresponding bolt diameter. As far as possible, bolt heads, rather than nuts, shall be on the outer or upper faces of structure connections.

To facilitate inspection and maintenance, all tall structures shall be provided with step bolts and ladders complete with hoops. Handrails, screens, guards and other appropriate facilities shall also be provided.

Where the structure is to terminate overhead transmission lines supplied under another contract, suitable provisions shall be made to accept the transmission line insulator fittings and earth conductor clamps.

Means shall be provided for fixing and bonding GI flat strip to the steelwork at a minimum of two points. Earth connections shall be made to a vertical face, clear of the ground. Foundation bolts shall not be used for their attachment. GI flats for earth connections, bolts, nuts washers etc.. shall be included in the structures.

Gantry type structures which support more than one three phase circuit shall have suitable interbay screens installed to prevent access along the beam from a dead to an energised circuit. The location of the screens shall be agreed with the Engg Incharge (Divisional Engr.).

1.6 Material

All rolled steel sections, flats, plates and bolt and nut bars used shall consist of steel manufactured by an approved process and shall be to the requirements of ISO 630 (minimum yield strength 255 N/mm²). The steel shall be free from blisters, scales, laminations and other defects. Steel sections shall preferably be British Standard or metric standard sections chosen with a view to avoiding delays in obtaining material.

All members shall be cut to jig and all holes shall be drilled or punched to jig. All parts shall be carefully cut and holes accurately located so that when the members are in position the holes will be truly opposite to each other before being bolted up. Drifting or reaming of holes will not be allowed.

Built members shall, when finished, be true and free from all kinks, twists and open joints, and the material shall not be defective or strained in any way.

If the structures are fabricated or galvanised by subcontractors, the Contractor shall, if required by the Engg Incharge (Divisional Engr.), provide a resident inspector at the works of each subcontractor during the time that the steelwork is being fabricated or galvanised.

All bolts and screwed rods shall be galvanised, including the threaded portions; all nuts shall be galvanised with the exception of the threads, which shall be oiled.

Except where specified to the contrary, all iron and steel used in the construction of the Contract works shall be galvanised after all sawing, shearing, drilling, punching, filing, bending and machining are completed.

Galvanising of all material shall be in accordance with the requirements of this Specification. The preparation for galvanising and the galvanising itself shall not adversely affect the mechanical properties of the coated material.

Sheradizing or other similar process shall not be used.

2. 0 SUPPORT STRUCTURES OF SWITCHYARD

2.1 General

The scope of works covers design, fabrication, proto -assembly, supply and erection of galvanised steel structure for portals (columns, girders), lightning masts and equipment support structures.

Portals (columns, girders), lightning masts, and equipment support structures shall be lattice type structures fabricated from structural steel conforming to IS 226/2062. The design of all support structures for 220kV, 132kV and 33kV equipment. The column and beam and lightning cum lighting mast of 400 KV side shall be of lattice type. The equipment support structure for 400 KV shall be GI Tubular pipe of adequate height and strength conforming to the latest IS. All the structural materials are within the scope of the Contractor. The use of GI pipes conforming to IS 806 to support certain equipment will also be considered. However approval of the Engg Incharge (Divisional Engr.) should be obtained for the same before commencement of detailed design.

It is the intent of the Employer to provide structures which allow interchangeability of equipment at a later stage. Keeping this in view, the height of all the structures must be maintained as per approved drawings. It is stressed that the Contractor has to provide minimum steel sections as per the standard drawings. However, if a higher section is required from design point of view the same shall be acceptable. Additional structures called stools shall be connected to the equipment and the bottom of the stool shall be connected to the support structure where required.

The scope shall include the supply of all types of bolts, nuts, hangers, shackles, clamps, anticlimbing devices, bird guards, climbing systems, inserts in concrete, gusset plates, equipment mounting bolts, structure earthing bolts, foundation bolts, spring washers, fixing plates, angles and bolts for structure mounted or ground mounted marshalling boxes (ACDC marshalling box and equipment control cabinets), and any other items as required to complete the works.

The connection of all structures to their foundations shall be by base plates and embedded anchor and foundation bolts. All steel structures and anchor or foundation bolts shall be fully galvanised. The weight of the zinc coating shall in accordance with this Specification. One additional nut shall be provided below the base plate which may be used for the purpose of levelling.

2.2 Design requirements

The minimum bolt diameter shall be 16 mm.

In order to facilitate inspection and maintenance, the structures shall be provided with climbing devices. Each substation gantry structure shall be provided with step bolts not less than 16mm diameter and 175mm long spaced not more than 450mm apart, staggered on faces of one leg extending from about 2.5 metres above ground level to the top of the tower. The step bolts shall conform to IS 10238. Ladders on lighting masts and other tall structures shall be provided with safety guards.

All structures shall be designed for the worst combination of dead loads, live loads, wind loads as per code IS 802, seismic forces as per code IS 1893, loads due to deviation of conductor, load due to unbalanced tension in conductor, torsional load due to unbalanced vertical and horizontal forces, erection loads, short circuit forces including 'snatch' in the case of bundled conductors etc. Short circuit forces shall be calculated considering a fault level of 40kA. IEC 865 and CIGRE Guide No. 7 may be followed to estimate the various forces of conductor for structural design.

Substation gantry structures shall be designed in accordance with IS 802 for the three conditions i.e. normal conditions, three conductors on one side broken, and broken wire condition and short circuit force. The design of all structures shall be based on the condition where stringing is done only on one side i.e. all the three (phase) conductors broken on the other side.

A factor of safety of 2.0 under normal and broken wire conditions and 1.5 under combined short circuit and broken wire conditions shall be considered for the design of switch yard structures. For purpose of design 110% of static tension pull and transverse reaction on the gantries as calculated for each span shall be considered.

Vertical load of half the span of conductors/string and the earth wires on either side of the beam shall be taken into account for the purpose of design. The weight of a man with tools shall be considered as 150 kg for the design of structures.

Torsional effect on towers and beams due to unbalanced forces may be taken care of as per American Code DS-10.

Terminal line take off gantries shall be designed for a minimum conductor tension of four metric tonnes per phase for 400kV and two metric tonnes per phase for 220kV & 132 kV. The distance between terminal gantry and dead end tower shall be taken as 200 metres. The design of these terminal gantries shall also be checked considering ± 30 degree horizontal and ± 15 degree vertical deviation of conductor. The transmission line conductors would be either single ACSR conductor per phase on AC side for all lines except for 400kV. For 400kV the line side conductor shall be twin ACSR.

The girders shall be connected with lattice columns by bolted joints.

All pipe supports used for supporting equipment shall be designed for the worst combination of dead loads, erection load, wind load, seismic forces, short circuit forces and operating forces acting on the equipment and associated busbars as per IS 806 and IS 1161. Minimum sections for 400kV, 220kV and 132kV & 33kV structures shall be as per standard drawings approved by the Engg Incharge (Divisional Engr.). However, the Contractor can increase the sections if required. The height of the structures shall be as per standard drawings.

If lighting fittings are proposed to be fixed on gantries or towers, the proper loading for these shall be considered in the design. Holes for fixing the brackets for lighting fittings should be provided wherever required.

Foundation bolts and stubs shall be designed for the loads for which the structures are designed.

Lightning masts shall be designed as per IS 802 for diagonal wind condition for a height of 47.5 m for lattice structures and 2.5m for MS pipe with conical head at top.

Lightning masts shall be provided with a structural steel ladder within its base up to a height of 25 metres. The ladder shall be provided with protection rings. Two platforms shall be provided one each at 12.5m and 25m height for mounting of lighting fittings. The platforms shall also have protection railing.

2.3 Design drawings, bill of materials and documents.

The fabrication drawings to be prepared and furnished by the Contractor shall be based on the design approved by the Engg Incharge (Divisional Engr.). These fabrications drawings shall indicate complete details of fabrication and erection including all erection splicing details and typical fabrication splicing details, lacing details, weld sizes and lengths, bill of materials in the proforma approved by the Engg Incharge (Divisional Engr.), bolt details and all customary details in accordance with standard structural engineering practice whether or not given by the Contractor.

Fabrication work shall start only after the final approval of the design and fabrication drawings is accorded by the Engg Incharge (Divisional Engr.).

Such approval shall, however, not relieve the Contractor of his responsibility for the safety of the structure and good connections. Any loss or damage occurring due to defective fabrication, design, or workmanship shall be borne by the Contractor.

2.4 Fabrication of steel

The Contractor shall bear all the expenditure at all stages on account of loading and unloading, transportation and other miscellaneous expenses and losses and damages for all materials up to the fabrication yard/shop and thereafter to the erection site including all other expenses till the erection of work has been completed and accepted. His unit rates shall be deemed to be inclusive of all such incidental expenses and no extra shall be payable on any account in this regard.

The fabrication and erection works shall be carried out generally in accordance with IS 802. A reference however may be made to IS 800, in case of non stipulation of some particular provision in IS 802. All materials shall be completely shop fabricated and finished with proper connection material and erection marks for ready assembly in the field.

2.5 Assembly

2.5.1 General

The component parts shall be assembled in such a manner that they are neither twisted nor otherwise damaged and shall be so prepared that the specified camber, if any, is provided. In order to minimise distortion in members the component parts shall be positioned by using clamps, clips, dogs, jigs and other suitable means. Fasteners (bolts and welds) shall be placed in a balanced pattern if the individual components are to be bolted, paralleled and tapered.

Sample towers, beams and lightning mast shall be trial assembled keeping in view the actual site conditions, before erection in the fabrication shop and shall be inspected and approved by Engg Incharge (Divisional Engr.) before mass fabrication. Necessary erection marks shall be made on these components in the shop before disassembly and despatching.

2.5.2 Bolting

Every bolt shall be provided with a washer under the nut so that no part of the threaded portion of the bolt is within the thickness of the parts bolted together.

- All steel items, bolts, nuts and washers shall be hot dip galvanised.
- 2.0% extra nuts and bolts shall be supplied for erection.

2.5.3 Welding

The works shall be done in accordance with the General Technical Clauses (TS-GTC) and as per approved fabrication drawing which shall clearly indicate various details such as joints to be welded, type of weld, length and size of weld, and whether shop or site welded. Symbols for welding on erection and shop drawings shall be according to IS 813. Efforts shall be made to reduce site welding so as to avoid improper welding due to constructional difficulties.

Those welds which are considered to be critical to the design and the integrity of the construction of the structure shall be subject to radiographic inspection.

The Contractor shall carry out non-destructive testing of all butt welds subject to tensile stresses. Testing shall be carried out in the fabrication shop or on site as the case may be.

Unless otherwise approved, non-destructive testing shall be by radiographic examination.

2.6 Foundation bolts

Foundation bolts for the towers and equipment supporting structures and elsewhere shall be embedded in first stage concrete while the foundation is cast. The Contractor shall ensure the proper alignment of these bolts to match the holes in the base plate.

The Contractor shall be responsible for the correct alignment and levelling of all steel work on site to ensure that the towers and structures are plumb.

All foundation bolts for all structures and supports are to be supplied by the Contractor.

All foundation bolts shall be fully galvanised in accordance with the General Technical Clauses of this specification.

The contractor shall provide templates for all stanchion bolt spacing. Holding down bolts, assemblies, templates, tubes and washers shall be delivered to the site in sufficient time to position and build them into the foundations. Boxing out for bolts shall not be permitted. The projection of threaded portions of bolts above the foundation level shall be adequate to properly secure the nuts.

2.7 Stub setting

Stub for towers and lightning mast shall be set in such a manner that the distance between the stubs and their alignment and slope shall be exactly as shown in the fabrication drawings.

2.8 Stability of structure

The Contractor shall be responsible for the stability of the structure at all stages of its erection at site and shall take all necessary measures by the additions of temporary bracing and guying to ensure adequate resistance to wind and also to loads due to erection equipment and their operations.

2.9 Grouting

The method of grouting the column bases shall be subject to approval of Engg Incharge (Divisional Engr.) and shall be such as to ensure a complete uniformity of contact over the whole area of the steel base. The Contractor will be fully responsible for the grouting operations. The mix for the grouting shall contain one part of cement and two parts of coarse sand. Non shrinkage admixtures of approved quality and of standard make shall also be added in adequate proportion as specified by the manufacturers of the admixtures.

2.10 Galvanising

All structural steel works and single pipe supports shall be galvanised after fabrication in accordance with this Specification. The galvanising of structures having length not exceeding 6m for lattice type, and 5m along with base plate size of 750x 750mm for other type, shall be made in one dip only.

The Contractor shall be required to make arrangements for frequent inspection by the Engg Incharge (Divisional Engr.) as well as continuous inspection by a resident representative of the Engg Incharge (Divisional Engr.), if so desired for this fabrication work.

2.11 Painting

Where members of steel structures are required to be painted it shall meet the requirements as specified in relevant sections of this Specification.

The preparation, protection and painting systems selected for ferrous surfaces provided inside the switchyard shall provide a life to first maintenance of 20 years and for doors, windows, louvres etc., it shall provide life to first maintenance of 10 years. Finish colour will be selected as per relevant sections of this Specification.

3. 0 INSPECTION BEFORE DESPATCH

Each part of the fabricated steel work shall be inspected for correctness of physical parameters, welding, joints, erection marks etc.. before it is despatched to the erection site. In any case the Contractor shall be fully responsible for correctness, quality, adequacy and completeness of structures being erected under the scope of this contract.

3.1 Testing and inspection

The Contractor shall give full access to the Engg Incharge (Divisional Engr.) at all times to the place of fabrication and storage for the purpose of inspection and testing. Mill test certificates relating to the material procured by the Contractor for works shall be forwarded to the Engg Incharge (Divisional Engr.).

When so instructed by the Engg Incharge (Divisional Engr.), the Contractor shall provide samples of the steel to be used in the works for tests to be carried out at an independent laboratory approved by the Engg Incharge (Divisional Engr.). The cost of these independent tests shall be paid for by the Contractor.

Should the works or any part thereof fail to pass any test or in the opinion of the Engg Incharge (Divisional Engr.) fail to comply with the specification, the Contractor shall immediately take such action as is necessary to ensure that the works comply with the specification at no extra cost to the Employer.

All defective material and workmanship will be rejected and shall be replaced and reconstructed at the Contractor's expense.

No splice welding of members between connections shall be permitted without the prior approval of the Engg Incharge (Divisional Engr.).

3.2 Despatch, handling and storage.

All bolts, nuts, washers, plates etc. shall be transported to site in properly marked and sealed containers, suitably protected to prevent damage during transportation.

3.3 Test certificate.

Copies of all test certificate relating to material procured by the Contractor for the works shall be forwarded to the Engg Incharge (Divisional Engr.).

4. 0 ERECTION.

The Contractor should arrange his own erection plant and equipment, welding sets, tools and tackles, scaffolding, trestles equipment etc. and any other accessories and ancillaries required for the work.

Finished structures shall be plumb, level and true to dimensions, within the tolerances specified.

4.1 Safety precautions.

The Contractor shall strictly follow at all stages of fabrication, transportation and erection of steel structures, raw materials and other tools and tackles, the stipulations contained in Indian Standard Code for erection for structural steel work, IS 7205.

4.2 Fire protection to steelwork.

The fire protection to steelwork shall be an approved luminescent paint, spray or board system to give two hours fire protection when tested. Fire protection shall only be required in the immediate vicinity of potential fire sources.

If applicable, fire protection coatings shall be sprayed or painted onto previously primed steelwork. Application to be made in strict accordance with product loading rates for base coat and top sealer specified for two hours fire resistance in manufacturers product application notes. Suitable mesh reinforcement shall be incorporated to prevent loss of insulation when subject to mechanical damage.

The coatings shall be applied by a specialist applicator strictly in accordance with the product manufacturers recommendations. The whole of the fire protection proposals and application shall be in accordance with the current Building Regulations and to the satisfaction of the Local Authority and the Fire Authority.

Surfaces which are to receive a fire protective coating shall be delivered to site with travel coatings applied and shall be suitably protected until immediately prior to the fire protective coatings or casings being applied. The latter shall be applied as late as possible in the construction programme subject to other trades and operations. Primer and travel coat shall be compatible with the fire protection coating.

5. 0 WIDTH AND HEIGHT OF THE BUS AT SUB-STATION

<u>VOLTAGE LEVEL</u>	<u>BAY EIDTH</u>	<u>BOTTOM BUS HEIGHT</u>	<u>TOP BUS HEIGHT</u>
132 KV	11MTRS / 13.1 MTRS	8.5 MTRS	13.5 MTRS
220KV	18MTRS	10.5 MTRS	16.0 MTRS
33KV	5.5MTRS	5.5 MTRS	9.5 MTRS
400KV	27 MTRS	>15	>23 MTRS

Remarks: The structure height shall be maintained as per data provided for getting mnimum clearance and sectional clearance and as OPTCL standard. Contractors to furnish the drawings of all the structural items to the owner for according approval.

ODISHA POWER TRANSMISSION CORPORATION LIMITED
OFFICE OF THE SR. GENERAL MANAGER,
CENTRAL PROCUREMENT CELL,
JANAPATH, BHUBANESWAR – 751022.

TECHNICAL SPECIFICATION

FOR
MANUFACTURERS DRAWING, TEST CERTIFICATES
AND
(O &M) MANUALS

Sl.No.	DESCRIPTION	PAGE No.
1.0	DRAWINGS, TEST CERTIFICATES OPERATING AND MAINTENANCE MANUAL.	3
2.0	DRAWING	3
3.0	GENERAL	3
4.0	DETAILED DRAWINGS	4
5.0.	RECORD DRAWING	7

6.0.	SPECIFIC REQUIREMENT	7
7.0.	SUBMISSION OF DRAWING	12
8.0	TEST CERTIFICATE	12
9.0	ROUTIN TEST CERTIFICATES	13
10.0	OTHER DOCUMENTS	13
11.0	OPERATING AND MAINTENANCE MANUALS	14

TECHNICAL SPECIFICATION FOR DRAWINGS, TEST CERTIFICATE & O&M MANUALS

1. 0 DRAWINGS, TEST CERTIFICATES, OPERATING AND MAINTENANCE MANUAL.

2. 0 DRAWING

2.1 GENERAL

Separate drawings shall be prepared and submitted for equipment/installation pertaining to each substation/site.

All drawings to be furnished by the Bidder shall be in standard size of sheets with maximum size being A0. Drawings shall contain the following particulars in the title block at lower right hand corner in addition to the Bidder's name, date, scale, drawing number title, etc.

- a) Client : OPTCL
- b) Project Title:- PROJECT for System improvement for (*AS PER PACKAGE DESCRIPTION)

A blank space of size 100 mm x 100 mm shall preferably be provided for the Employer's approval stamp and provision shall also be made by way of a block for details of revisions to be recorded. The drawing number shall be marked with a subsequent revision number every time the drawing is revised. The drawing title shall also identify name of the substation/site.

The equipment/systems which are to be bought out from the sub vendors are also required to be approved by the Employer prior to placement of order. The relevant technical literature/drawings pertaining to such equipment/systems shall be submitted for approval.

Six copies of each of the drawings are to be submitted for approval of Employer. Bidder shall ensure that the contents of copies of drawings are legible and are complete with all details. Drawings that are not legible or are incomplete will not be reviewed.

Two copies of approved drawings will be furnished to the Bidder. Drawings returned "not approved" / "approved with comments" shall be resubmitted with Revision No. for approved till the final approval is obtained.

Delays caused by submission of incomplete/ incorrect drawings shall be to Bidder account.

Drawings submitted by sub-vendor/sub-contractor shall carry Bidder's approval stamp and the Bidder shall be responsible for their contents, accuracy and completeness. These drawings shall also carry details indicated in this Clause in addition to the Bidder's name.

3. 0 DETAILED DRAWINGS

The bidder shall submit to the Employer all working drawings, equipment data and detailed drawings. These shall include general arrangement, details of equipment, foundations, cable routing, openings in walls and floors, wiring diagrams, cable schedules, interconnection diagrams etc. necessary for the erection of plant. These drawings/data having been corrected or amended as necessary based on the Employer's comments shall become the approved drawings/data to be used for manufacture and erection of plant.

Minimum details required on drawings of different categories are given below:

Type of Drawing.	Minimum details required.
-------------------------	----------------------------------

List of Drawing	:	A detailed list of drawings which The bidder proposes to prepare for The substation in indicating therein Drawing nos. and titles.
-----------------	---	--

Programme:	1)All activities from the start Date up to commissioning shall Be included. Separate Programme shall be furnished for each of the activities.
------------	---

2) Earliest and latest occurrence of each activity.

3) Constraints, if any.

The activities for each of the items shall essentially cover time-table for activities such as placement of order with sub-vendors, Empowering, submission of drawing, review and approval by the Employer, manufacture, inspection, delivery, erection and commissioning. All events shall be represented in a proper in proper sequence of occurrence with due consideration for inter-dependent activities and all period shall be counted from the start date.

Type of Drawing	Minimum details required
------------------------	---------------------------------

Single line diagrams.	<ol style="list-style-type: none"> 1. All equipment connection with ratings, polarities, protection and metering details, etc. 2. Cable details for all circuits. 3. Details of relays, meters and
------------------------------	---

**General Arrangement
(All equipment,
cabling earthing,
lightning protection,
lighting etc.)**

- Major components associated with each circuit.
4. Busbar details, makes of equipment/ Components etc.
 5. Reference Drawings.
 - 1) Dimensional layout drawings covering complete layout of these items/systems.
 - 2) Plans and sections as required to show details, access space/ Clearances etc.
 - 3) Details of foundations, cutouts. Openings, supporting/mounting Details etc. indicating weight on foundation.
 - 4). Bill of material and identification of components/rooms/ areas etc.
 - 5). Reference drawings.

Installation Drawings

Details of installation for equipment, accessories, cabling, lighting, earthing and lightning protection systems. These shall cover cross sectional details, cable trays/cable layouts for cables directly buried/along cable trays/ in conduits/along structures etc. details of marshalling boxes, embedment of conduits at building entry points/between cable trenches and structures, mounting arrangements and wiring for lighting fixtures, installation of earthing conductors directly buried/along structures, jointing/terminations (between conductors and at equipment ends), earth electrodes and pits, lightning shield wire, earth pads to be provided at specific places etc.

4. 0 RECORD DRAWING

Within 6 (six) weeks of successful commissioning tests, the Bidder shall furnish the Record (As Built) drawings. Submission to and approval by the Employer of the Record drawing shall be pre-requisite for the Taking Over Certificate. The drawing shall show the whole sub-station as installed and shall include electrical/mechanical and civil components with schematic and wiring diagrams for all items of electrical equipment included in the works. Six sets of recur drawings shall be furnished in neatly bound volumes. Reduced copies of the relevant drawings shall be included in the operating and maintenance manual.

5. 0 SPECIFIC REQUIREMENT

Following drawings shall be enclosed with the bid :

- a) The programme shall be in the form of a network based on the principles of PERT/CPM. Detailed to cover entire scope of the project showing all activities (separately for each sub-station/site). Their durations start and finish dates and their inter-relationships.

b) Dimensioned general arrangement drawings showing plan, elevation and sections together with identification of parts/accessories, etc. for the major plant items, viz. 132 KV/33 KV. Outdoor transformer and equipment, 415 V A.C. and 220 V A.C. system equipment, control, relay and metering panels, communication equipment, lighting equipment along with manufacturer's catalogues/literature, etc.

Following information/drawings shall be submitted after the award of contract for approval of the Employer.

- (a) Updated programme along with the list of drawings.
- (b) Detailed design calculations for electrical, mechanical and civil equipment and systems etc. including design calculation of earthing grid and illumination system.
- (c) 33 KV/433 V transformer.
- (d) General arrangement drawing, showing plan, front and side elevations and all accessories and fittings. Detailed dimensions, net and shipping weights, crane lift for un tanking, size of lifting lugs and eyes, clearances between HV terminals, LV terminals and to ground and between adjacent bushing identification for fittings and accessories, enter lines in both the directions, details of anti-earthquake clamping device, details of HV/LV bushings. LV box foundation details, detailed manufacturer's catalogues/literature of accessories actually being supplied.
- (e) Rating and terminal marking plate, showing polarity vector group and other details.
- (f) GA drawing of OLTC and Marshaling Box.
- (g) Control and wiring diagram for OLTC marshalling box and cooler system.

(1) 400KV,220KV,132KV AND 33KV outdoor type sub-station equipment:

- (i) Detailed dimensional plan and sections for each equipment and for the sub-station indicating therein salient features of equipment, detailed bill of material for equipment, identification of clamps and connectors, etc. including weight of different equipment.
- (ii) Cable trench, lighting, earthing and lightning protection drawings for outdoor areas, control room drawings for equipment layout, cabling, lighting and earthing systems.
- (iii) Detailed drawings for the sub-station structures, equipment and clamps/ connectors.
- (iv) Foundation layout drawings.
- (v) Control and protection schematic diagrams.
- (vi) Detailed one-line diagrams.
- (vii) Block logic diagrams.
- (viii) Cable schedules and inter-connection wiring diagrams in detail including all interlocking schematics.
- (ix) Typical installation detailed drawings.
- (x) Architectural and other civil drawings including that of state quantum.
- (xi) Manufacturer's catalogues/literature etc. of equipment being supplied.

(2) 400KV/220KV/132 KV/33 KV SF6 Circuit Breaker.

- (I) Complete assembly drawing of the Circuit Breaker showing plan, elevation and control cable terminal blocks.
- (ii) Foundation plan showing the location of channel sills, foundation bolts.
- (iii) Schematic diagram (AC and DC) for control protection, indication, alarm and trip circuits, relays, instruments space heaters, etc.

(iv) Complete wiring diagrams of Marshalling Kiosk including terminal wiring designation.

(v) Cable terminal details with dimensions.

(vi) Manufacturer's catalogues/literature etc.

(3) Control, relay and metering panels, 415/V AC and 220 V DC distribution boards, lighting panels, etc.

(4) Fully dimensioned general arrangement drawings for each of the above complete with plan, elevation and sectional views and complete bill of material, foundation drawing and cable entry details.

(I) Schematic diagrams for all power, control, protection and indication circuits.

(ii) Alarm annunciation scheme drawings.

(iii) Wiring diagrams.

(iv) Manufacturer's catalogues/literature etc. for all items.

(5) 220 V DC Battery and Battery Chargers.

(i) Dimensioned general arrangement drawings of battery and battery charges comprising plan, elevation and sectional views, foundation details, etc.

(ii) Complete schematic and wiring diagrams for battery chargers.

(iii) Detailed bill of material together with rating makes etc.

(iv) Manufacturer's catalogues/literature.

a) LIGHTING SYSTEM

Lighting layout drawings for indoor and outdoor areas showing layout of lighting fixtures, conduit/cables, lighting circuit distribution scheme, complete bill of materials, locations of control switches, receptacles etc. and mounting details for fixtures, switches and receptacles as well as manufacturer's catalogues/literature.

b) EARTHING AND LIGHTNING PROTECTION SYSTEM

Layout drawings for earthing and lightning protection system showing earthing grid, locations of earth electrodes, routes of conductor, interconnections, earth leads to various equipments, bill of materials, etc.

c) MISCELLANEOUS SYSTEM

Detailed general arrangement, schematic and other drawings, bill of material and manufacturer's catalogues/literatures.

d) TYPICAL INSTALLATION DRAWING

Cabling, lighting, earthing and lightning protection as well as miscellaneous system drawings showing all, necessary details.

6. 0 SUBMISSION OF DRAWING

The list of drawings and the programme shall be submitted within 30 days from the start date.

All other drawings shall be submitted progressively thereafter within a maximum period of 180 days as per approved sequence of drawings to be submitted with the above period. But in no case the work progress should be hampered due to wrong/unscheduled sequence of drawings submission.

7. 0 TEST CERTIFICATE

Type test certificates for the following items shall be furnished.

- a) 400KV, 220 KV, 132 KV and 33KV equipment like circuit Breaker, isolators, CTs, VTs and CVTs. Line traps, insulators, bushings, LAs, etc.
- b) Cables
- c) Clamps, connectors and hardwires.
- d) Transformers, OLTC etc.

Type test certificates shall be furnished for tests carried out on similar type/design of equipment. Type test to be carried out in presence of employer's representative for transformer.

7.1.1 ROUTIN TEST CERTIFICATES

Routine test certificates for all the plant items and accessories shall be furnished.

Routine test certificates shall be furnished in addition to test reports which will be collected at the time of inspection.

Routine test certificates shall be furnished for review by the Employer within seven (7) days after completion of inspection of relevant item or as instructed by the Employer in case of items for which witnessing of tests is waived.

Test certificates should be approved by the Employer for obtaining dispatch clearance of any material.

Six (6) copies of approved test certificates should be submitted for record.

7.1.2 OTHER DOCUMENTS

Technical catalogues, descriptive literature, characteristic curves, write-up on schemes where required in support of relevant control/annunciation drawings etc. shall be furnished for all the items of plant and accessories/components.

Documents pertaining to cables shall, in addition, include current ratings, de rating factors, physical and electrical data, recommended bending radii etc.

Documents in respect of lighting systems equipment shall include data in respect of each type of lighting fixture/switch, receptacles/miniature circuit breaker and wires to be used in circuit wiring. Data on lighting fixtures shall include dimensional drawings, cable facility, mounting details and weight, light distribution diagrams, light absorption and utilization factors, lamp data etc.

Bidder shall note that the documents mentioned above shall be made available along with relevant drawings (listed in Clause 11.4 above items/ accessories components etc. as supporting documents to facilitate expeditious review of such drawings.

7.1.3 OPERATING AND MAINTENANCE MANUALS

The Contractor shall provide five bound sets of approved manuals written in English language. All descriptive leaflets, instruction sheets, charts, lists, pamphlets and other documents that are used in compiling each manual shall be contained in one or more bundle designed to prevent loss of contents. Each binding shall be titled with a name of the Employer, the name of the project the Contract Number, the name of the Bidder and with information to identify the subject matter and shall include a detailed index to all the literature contained therein.

The manuals shall be initially approved in draft form by the Employer and shall cover all items of the works. For this purpose, three (3) draft copies shall be submitted to the Employer. Final submission of manuals shall be done after satisfactory completion of commissioning tests. A mere collection of manufacturer's descriptive leaflets, will not be acceptable in satisfaction of this clause. The manuals shall comprise both operating instructions and maintenance instructions. The operating manual should also highlight operation of the Plant in conjunction with the system. Thus, a general tie-up between system and equipment shall be available in the manuals.

A separate section of a manual shall be devoted to each size and type of equipment. It shall contain a detailed description of its construction and operation and shall include all relevant pamphlets and a list of parts with procedure for ordering spares. Operation of electrical equipment shall be described step by step giving the complete sequence of operation. The detailed sections of the manual if necessary, shall contain further maintenance instructions and fault location charts.

The manuals shall be printed on A4 size sheets and shall be bound. Reduced copies of record drawings shall also be included in the manuals.

Step to step of the plant to work, listing all adjustment necessary for the correct functioning of the plant alarms giving possible causes for alarm initiation and sequence of remedial actions to be taken.

Instructions on monitoring of plant performance and sample log sheet for each plant item, to be filled by operators on a routine basis.

Do's and Don'ts in plant operations. Operations attention shall be drawn to all operations considered to be dangerous to operators or likely to cause damage to the plant.

The maintenance instructions shall include the following.

Checking, testing and replacement procedures to be carried out on all plant items on a daily, weekly and monthly basis or at longer intervals to ensure trouble free operation.

Fault locations and remedy charts to facilitate tracing the cause of malfunctions or breakdown and correcting faults.

A spares schedule which shall consist of a complete list of itemized spares for all plant items with ordering references and part numbers.

Full instructions to cover the complete dismantling and reassembly of all items of plant.

Part list and drawings or exploded diagrams for such items of plant showing manufacturing tolerances, matching clearances between machined components at the time of supply, maximum wear and clearances permitted to facilitate replacement.

Complete list of recommended lubricants and lubricating charts insulating oil and insulation checking/replacement chart.

ODISHA POWER TRANSMISSION CORPORATION LIMITED

**OFFICE OF THE SR. GENERAL MANAGER,
CENTRAL PROCUREMENT CELL,
JANAPATH, BHUBANESWAR – 751022.**

TECHNICAL SPECIFICATION

FOR

ELECTRICAL EQUIPMENT

INSTALLATION AND

COMMISSIONING

SI.No.	DESCRIPTION	PAGE No.
1.	ELECTRICAL EQUIPMENT INSTALLATION AND COMMISSIONING	3
1.1	SCOPE	3
1.2	CODES AND STANDARDS	3
1.3	GENERAL	4
2.	INSTALLATION WORK SCOPE	4
2.1	POWER AND INSTRUMENT TRANSFORMERS	5

2.2	SWITCHGEAR, CONTROL/RELAY PANELS	5
2.3	BATTERY AND CHARGERS	6
3.0	SWITCHYARD	6
3.1.	GENERAL REQUIREMENTS OF INSTALLATION FOR CONDUITS, PIPES AND DUCTS.	7
3.2	GENERAL REQUIREMENTS OF INSTALLATION FOR EARTHING AND LIGHTNING PROTECTION SYSTEMS	8
4.0	SCOPE AND INSTALLATION	8
4.1`	EARTHING CONNECTIONS	9
4.2	EARTH ELECTRODES	9
5.0	TESTING OF EARTHING SYSTEM	
	9	
5.1	GENERAL REQUIREMENTS OF INSTALLATION FOR LIGHTING SYSTEM AND POWER RECEPTACLES	10
5.2	TESTING AND COMMISSION	10
6.0	COMPLETION CHECKS	11
6.1	COMMISSIONING TEST	11

1 .0 ELECTRICAL EQUIPMENT INSTALLATION AND COMMISSIONING

1.1 SCOPE

This chapter describes board guidelines for installations, testing and commissioning of electrical equipment. The work shall, however, be carried out strictly as per the instruction of the MANUFACTURER / EMPLOYER.

1.2 CODES AND STANDARDS

The electrical installation work shall comply with the latest applicable standards, regulations, electricity rules and safety codes of the locality where the installation is carried out. Nothing in this specification shall be construed to relieve the CONTRACTOR OF HIS RESPONSIBILITY

1.3 GENERAL

The CONTRACTOR shall transport the equipments where required in actual position. Erect, assemble all parts of the equipments and test and commission the same.

The CONTRACTOR shall furnish all tools, welding equipment, rigging materials, testing equipment, test connections and kits, etc. required for complete installation, testing and commissioning of the items included in the contract work.

The EMPLOYER may engage specialist Employer to supervise the installation, testing and commissioning of their equipment. The CONTRACTOR shall extend full co-operation to these Employers and carry out the works as per their instructions. The CONTRACTOR'S work shall include minor rewiring modifications as may be necessitated during commissioning. Providing such assistance shall be deemed to be included in the CONTRACTOR'S basic scope.

The CONTRACTOR shall co-operate through the EMPLOYER with other contractors at site, in all matters of common interest, so as not to abstract operation of others and to ensure the safety of all personnel and works covered under this specification.

It will be the CONTRACTORS responsibility to assist the OWNER to obtain approval/ clearance from local statutory authorities including electrical inspector, wherever applicable, for conducting any work or for installation carried out which comes under the purview of such authorities.

The work shall be carried out strictly as per the instructions and layout drawings of the EMPLOYER/ manufacturer. In case of any doubt/ misunderstanding as to correct interpretation of the drawings or instructions, necessary clarifications shall be obtained from the EMPLOYER. The CONTRACTOR shall be held responsible for any damage to the equipment consequent to not following the MANUFACTURER'S instructions correctly. All necessary drawings. MANUFACTURER'S instructions correctly. All necessary drawings. MANUFACTURER'S equipment manuals will have to be arranged by the contractor as this is a Turn-key contract.

All thefts of equipment/component parts till the including executed portion handed over to the EMPLOYER shall be made good by the CONTRACTOR.

The CONTRACTOR shall have a separate cleaning gang to clean all equipment during erection and as well as the work area and the project site at regular intervals to the satisfaction of the EMPLOYER. In case the cleaning is not to the Employer's satisfaction, he will have the right to carry out the cleaning operations and any expenditure incurred by the OWNER in this regard will be the CONTRACTOR'S account.

In order to avoid hazards to personnel moving around the equipment such as switcher etc. which is kept charged after installation before commissioning, such equipment shall be suitably cordoned off to prevent any one accidentally going near it.

Safety of the Contractor's personnel engaged in erection and commissioning job will be Contractor's responsibility.

The CONTRACTOR shall carry out touch-up painting on any equipment indicated by the EMPLOYER if the finish paint on the equipment is soiled for marred during installation handling.

The CONTRACTOR shall ensure workmanship of good quality and shall assign qualified supervisors/Employers and competent labour who are skilled, careful and experienced in their several trades in similar works. The EMPLOYER shall reserve the right to reject non-competent persons employed by the CONTRACTOR, if the workmanship is not of good order.

It shall be the responsibility of the CONTRACTOR to obtain necessary Licence/ Authorisation, Permit for work from the Licensing Board of the Locality/ state where the work is to be carried out. The persons deputed by the CONTRACTOR's firm should also hold valid permits issued or recognized by the Licensing Board of the locality/State where the work is to be carried out. A list of the personnel engaged in erection and commissioning work should be submitted to the Employer before commencement of the work.

2. 0 INSTALLATION WORK SCOPE

Equipment shall be installed in neat, workmanlike manners so that it is level, plumb, square and properly aligned and oriented. Tolerances shall be established in the Manufacturer's drawings or as stipulated by the EMPLOYER. No equipment shall be permanently bolted down to foundation or structure until the alignment has been checked and found acceptable by the EMPLOYER.

Care shall be exercised in handling to avoid distortion to stationary structures, the marring of finish, or damaging of delicate instruments or other electrical parts. Adjustment shall be made as necessary to the stationary structures for plumb and level, for the sake of appearance or to avoid twisting of frames, binding of hanged members, etc.

The CONTRACTOR shall move all equipment into the respective building through the regular doors or floor opening provided specially for lifting the equipment.

All external cabling including end connections and earthing shall also be carried out.

2.1 POWER AND INSTRUMENT TRANSFORMERS

Physical inspection on receipt, storage, installation, testing and commissioning of transformers shall be in accordance with the specified code of practice and Manufacturer's instructions.

Transformer may be delivered without oil filled with inert gas and without bushings and external mounted accessories. As applicable, the CONTRACTOR shall.

- a) Assemble the transformers with all fittings such as bushings, cooler banks, radiator, conservators, valves, piping, cables boxes, marshalling boxes OLTC, cooling fans/pumps, etc.
- b) Arrange for vacuum and oil filtration of the transformers. Oil filtration shall be done as per the standard practice. Oil tanker in this effect are to be used and filtration to be done while the oil is inside the tanker. On getting the standard value of the oils the same shall be pushed into the main tank and other portion of the transformer. Final filtration to be done after entire oil is filled in the transformer. Prior to that vacuum treatment of the tank of the transformer with the windings are to be taken up.
- c) Provide wedges/clamps to rigidly station all transformers on rails.
- d) Connect up the transformer's terminals.
- e) Lay and terminate cables/ conduits between all the accessories mounted on the transformer tank/cooler and the transformer-marshalling kiosk and RTCC panels etc.

- f) Pre commissioning checks shall be carried out as per relevant standards and Employer's instructions.

The CONTRACTOR shall arrange the oil filtration equipment.

Care shall be taken during handling of insulating oil to prevent ingress of moisture or foreign matter. In the testing, circulating, filtering or otherwise handling of oil, rubber hoses shall not be used, circulation and filtering of oil, the heating of oil by regulated short-circuit current during drying runs and sampling and testing of oil shall be in accordance with the MANUFACTURER'S instructions and specified Code of Practice.

2.2 SWITCHGEAR, CONTROL/ RELAY PANELS

Switchgears and control relay panels/desks shall be installed in accordance with specified Code of Practice and the Manufacturer's instructions. The switchgear panels shall be installed on finished surfaces or concrete or steel sills. The CONTRACTOR shall be required to install and align and channel sills which form part of the foundations. In joining shipping sections of the switchgear/panels /control centers together with adjacent housing or panel sections provided shall be bolted together after alignment has been completed. Power bus, enclosures, ground and control splices of conventional nature shall be cleaned and bolted together, being drawn up with torque wrench of proper size or by other approved means. Tape or compound shall be applied where called for by the MANUFACTURER'S drawings.

The CONTRACTOR shall take utmost care in handling instruments. Relays and other delicate mechanisms. Wherever the instruments and relays are supplied separately, they shall be mounted only after the associated control panel/desks have been erected and aligned. The blocking materials/mechanism employed for the safe transit of the instruments and relays shall be removed after ensuring that the panels/desks have been completely installed and no further movement of the same would be necessary. Any damage to relays and instruments shall be immediately reported to the EMPLOYER.

Pre-commissioning checks on relays have to be carried out on all relays in accordance with manufacturer's instruction and in presence of Employer.

2.3 BATTERY AND CHARGERS

Installation and testing of battery and battery chargers shall be done in strict compliance with the manufacturer's instructions. Each cell shall be inspected for break at and condition of cover seals as soon as received at site. Each cell shall be filled with electrolyte in accordance with the MANUFACTURER'S instructions. Battery shall be set up on racks as soon as possible after receipt, utilizing lifting devices supplied by the MANUFACTURER. The cells shall not be lifted by the terminals. Contact surfaces of battery terminals and inter-cell connectors shall be cleaned, coated with protective grease and assembled. Each connection shall be properly tightened. Each cell shall be tested with hydrometer and results logged. Freshening charge, if required, shall be added. When turned over to the EMPLOYER, the battery shall be fully charged and electrolyte shall be at full level and of specified specific gravity.

Battery shall be put in commercial use only after carrying out charge/discharge cycle as per Manufacturer's instruction.

3.0 SWITCHYARD

The CONTRACTOR shall carry out switchyard installation as required as per approved plan and elevation drawings of switchyard showing bus bar configurations, sizes, tensions, insulator details, etc. All equipment including connectors (unless otherwise specified) will be supplied by the VENDOR. The bus bar arrangement shall be two Bus system, main Bus-1 and main Bus-2 for 220 KV side and Main bus and transfer bus arrangement for 132 KV side.

The CONTRACTOR shall install complete set of bus bars and all baysø conductors, complete with tension with tension suspension insulator strings, bus-post insulators, equipment connections, bus bar connections to equipment, lightning shield wires including down comers up to a height of 1000 mm. From ground level where they shall be connected to the Employerø test links.

Installation work of breakers and isolators shall include adjustment/ alignments necessary for proper operation of circuit breakers, isolators and their operating mechanisms. All insulators and bushings shall be protected against damage during installation. Insulators and bushings damaged due to negligence or carelessness of the CONTRACTOR shall not be in any way accepted and shall be replaced by him at his expense.

General requirements of Installation of Cabling:

- i) The supplier shall install, test and commission the cables. Cables shall be laid on cable trays and supports, in conduits and doctor or bare on walls, ceiling, etc. as required. The supplierø scope of work includes laying, fixing, jointing, bending and terminating cables. The supplier shall also supply necessary materials and equipment required for jointing and terminating of cables. The supplier shall prepare detailed layout drawing for cable trenches, cable tray layouts for approval by Employer and construct cable routes strictly according to these drawings.
- ii) Sharp bending, twisting and kinking of cables shall be avoided. The bending radius for various types of cables shall not be less than those specified by cable manufacturer.
- iii) In each cable run, some extra length shall be kept at a suitable point to enable one or two straight through joints to be made. Should the cable develop fault at a later date.
- iv) Cable joints in the middle of the run for control cables will not be a accepted.
- v) All cable terminations shall be made in a neat. Workmanlike manner. Terminations shall be made for each type of wire or cable in accordance with instructions issued by cable manufacturers and the Employer.
- vi) Metal sheath and Armour of the cable shall be bounded to the earthing system of the sub-station.

3.1. GENERAL REQUIREMENTS OF INSTALLATION FOR CONDUITS, PIPES AND DUCTS.

- i) The supplier shall supply and install conduits pipes(PVC thick but flexible suitable for taking inside the roof and walls) and ducts as necessary for the lighting system. All accessories/fittings required for making installation complete. Including but not limited to ordinary and inspection tees and elbows, check nuts, male and female reducers and

enlargers, wooden plugs, caps, squat headed male plugs, nipples, gland sealing fittings, motion boxes, pull boxes, conduit outlets, outlet boxes, splice boxes, terminal boxes, glands, gaskets and box covers, saddles and all steel supporting work shall be supplied. Conduit fittings shall be of the galvanized one. Flexible metallic conduits shall be used for termination of connections to equipment such as motors or other apparatus to be disconnected at periodic intervals.

- ii) Conduits(thick and flexible PVC) and accessories shall be adequately protected against mechanical damage as well as corrosion.

3.2. GENERAL REQUIREMENTS OF INSTALLATION FOR EARTHING AND LIGHTNING PROTECTION SYSTEMS

4. 0 SCOPE OF INSTALLATION

- i) The supplier shall install steel conductors(GI flats) and braids, as required for system and individual equipment earthing. All work such as cutting, bending, supporting, painting coating drilling, brazing/soldering/welding, clamping, bolting and connection on to structures, equipment frames, terminals, rails or other devices shall be in the scope of work. All incidental hardware and consumables such as fixing cleats/clamps. Anchor fasteners, lugs, bolts, nuts, washers, bituminous compound, anticorrosive paints as required for the complete work shall be deemed to to be included as part of the installation work.
- ii) The quantities, sizes and material of earthing conductors and electrodes to be installed and routes of the conductors and location of the electrodes shall be as per specification mentioned elsewhere and approved drawings for the optimal capacity of the Sub-station taking the future requirement in to account..
- iii) The scope of installation of earth conductors in outdoor areas, buried in ground shall include excavation in earth at least upto 700 mm. Deep and 450 mm, wide (unless otherwise stated), brazing/welding as required of main grid conductor joints as well as risers of 500 mm. Length above ground at required locations and back filling. Back filling material to be placed over buried conductor shall be free from stones and other harmful mixtures. Backfill shall be placed in layers of 150 mm, uniformly spread along the ditch and tempered utilizing pneumatic tempers or other approved means.
- vii) The scope of installation of earth connection leads to equipment and risers on steel structures/walls shall include laying the conductors, welding/ cleating, at specified intervals, welding/brazing to the main earth grids risers, bolting at equipment terminals and coating welded/brazed joints by bituminous paint. Galvanized conductors shall be touched up with zinc rich paint, where holes are drilled at site for holding to equipment/structure.
- viii) The electrodes shall be installed either directly in earth or in constructed earth pits as shown in approved drawings.
- ix) The scope of installation of lightning conductors on the roof of buildings shall include laying, anchoring, fastening and cleating of horizontal conductors, grouting of vertical rods where necessary, laying, fastening/cleating/welding of the down comers on the walls/columns of the building and connection to the test links above the ground level.

- x) The scope of installation of the test links shall include mounting of the same at specified height on wall/column by suitable brackets and connections of the test link to the earth electrodes.

4.1 Earthing connections:

- i) All connections in the main earth conductors buried in earth/concrete shall be welded/brazed type,. Connection between main earthing conductor and earth leads shall also be of welded/brazed type.
- ii) Welding and brazing operations and fluzes/alloys shall be of approved standards.
- iii) All connections shall be of low resistance. Contact resistances shall also be minimum.
- iv) All bi-metallic connections shall be treated with suitable compound to prevent moisture ingress.

4.2 Earth Electrodes:

- i) Electrodes shall as far as practicable, be embedded below permanent moisture level.
- ii) Some electrodes shall be housed in test pits with concrete covers for periodic testing of earthing resistively. Installation of rod/pipe plate electrodes in test pits shall be convenient for inspection, testing and watering.
- iii) Earth pits shall be treated with salt and charcoal.
- iv) Soil, salt and charcoal placed around the electrode shall be finely graded free from stones and other harmful mixtures. Backfill shall be placed in the layers of 250 mm. Thick uniformly spread and compacted. If excavated soils are found unsuitable for backfilling, the contractor shall arrange for a suitable soil from outside.

5. 0 TESTING OF EARTHING SYSTEM

The Supplier shall ensure the continuity of all conductors and joints. The Purchaser may ask for earth continuity tests, earth resistance measurements and other tests, which in his opinion are necessary to prove that the system is in accordance with the design, specifications and code of practices. The supplier shall have to bear the cost of all such tests.

5.1. GENERAL REQUIREMENTS OF INSTALLATION FOR LIGHTNING SYSTEM AND POWER RECEPTACLES

- i) The supplier shall supply, install, test and commission complete lighting system and power receptacles in accordance with relevant Standards. Concealed conduit wiring (thick flexible PVC pipes suitable for taking inside the roof and walls) shall be adopted for the control building.
- ii) Wiring shall be colour-coded so as to enable easy identification of phase and neutral conductors, and DC wire (colour-coded as follows ó white ó phase wire, black ó neutral wire, grey / DC wires.)
- iii) There shall be switch on each live conductor of supply mains at the point of entry. The wiring throughout the installation shall be such that there is no break in neutral wire in the form of switch or fuse unit.
- iv) Fixtures shall be ground by 1.5sq mm .flexible PVC copper wires(green colour) and taken to earth strips.

- v) All fixtures, associated accessories, conduits, wires, junction boxes, cables, switches, switch boxes, etc. required for complete wiring of the lighting system as per approved drawings shall be supplied.

5.2. TESTING AND COMMISSION

All checks and tests as per the Manufacturer's drawings/manuals, relevant code of installation/erection practices and commissioning checks for various types of equipment e.g. transformers, breakers, isolators, CTs, PTs, motors, relays, meters, etc. shall be carried out by the CONTRACTOR as part of the installation work.

The owner may ask for such additional tests on site as in his opinion are necessary to determine that the works comply with the specification, Manufacturer's guarantee/instructions or the applicable code of installation. The CONTRACTOR shall carry out such additional tests also.

The CONTRACTOR shall perform operating tests on all switchgear and panels to verify operation of switchgear/panels and correctness of the inter-connections between various items of the equipment. This shall be done by applying normal AC or DC voltage to the circuits and operating the equipment for functional checking of all control circuits e.g. closing, tripping, control interlock supervision and alarm circuits. All connections in the switchgear shall be tested from point for possible ground or short circuit.

Insulation resistance tests shall be carried out by following rating megger :

- a) Control circuits up to 220 V : By 500 V Megger
- b) Power circuits, busbars : By 5000 Motor
connections for 132 KV. Operated Megger.
- c) Power circuits, busbars : By 5000 V Motor
connections above 220 KV. Operated Megger.

The Employer's authorized representative shall be present during every test as called for by the EMPLOYER. The CONTRACTOR shall record all test values and furnish the required copies of the test data to the EMPLOYER. Electrical circuits and equipments shall be energized or used at nominal operating voltage only after such reports have been accepted as satisfactory by the EMPLOYER.

6. 0 COMPLETION CHECKS

- a) Name plate details according to approved drawings/ specifications.
- b) Any physical damage or defect and cleanliness.
- c) Tightness of all bolts, clamps and connections
- d) Oil leakages and oil level.
- e) Condition of accessories and their completeness.
- f) Clearances.
- g) Earthing connections.
- h) Correctness of installation with respect to approved drawings/ specifications.
- i) Lubrication Moving parts.
- j) Alignment.
- k) Correctness and condition of connections.

6.1 COMMISSIONING TESTS

- a) Insulation resistance measurement of equipment, accessories, cabling/ wiring. etc.

- b) Dielectric tests on equipment, accessories, cabling/wires. etc.
- c) Phase sequence and polarity.
- d) Voltage and current ratios.
- e) Vector group.
- f) Resistance measurement of winding. Contacts, etc.
- g) Continuity tests.
- h) Calibration of indicators, meters, relays. etc.
- i) Control and interlock checks.
- j) Settings of equipment accessories.
- k) Checking of accuracy/error.
- l) Checking of operating characteristics, pick/up voltages and currents. Etc.
- m) Operational and functional tests on equipment, accessories, control schemes, alarm/trip/indication circuits, etc.
- n) Measurement of guaranteed/approved design values including lighting levels, earth resistance measurements, etc.
- o) Complete system commissioning checks.

ODISHA POWER TRANSMISSION CORPORATION LIMITED

TECHNICAL SPECIFICATION

FOR

GENERAL EQUIPMENT AND SUBSTATION ACCESSORIES

GENERAL EQUIPMENT AND SUBSTATION ACCESSORIES

TABLE OF CONTENTS

ORISSA POWER TRANSMISSION CORPORATION LIMITED.....	1
1. MOTORS	4
1.1 General.....	4
1.2 Motor control gear.....	5
2.0 CABLE BOXES	5
3.0 TERMINAL BOARDS AND TERMINAL BLOCKS.....	6
4.0 FUSES AND LINKS.....	7
5.0 COMMUNICATIONS CABLES.....	8
6.0 MARSHALLING KIOSKS AND CONTROL CABINETS	8
7.0 AUXILIARY SWITCHES	9
8.0 MINIATURE OR MOULDED CASE CIRCUIT BREAKERS.....	10
9.0 SPACE HEATERS.....	10
10.0 LVAC CABLES.....	10
10.1 General.....	10
10.2 1.1kV grade power and control cables.....	11
10.2.1 Codes and Standards	11
10.2.2 Technical requirements	11
10.3 LV XLPE power cables	11
10.4 LV XLPE power cables	11
10.5 LV PVC control cables	12
10.6 Cable drums.....	12
10.7 Tests.....	12
10.8 Cable sizes.....	12
11.0 BUSHINGS	13
12.0 BUSHINGS, HOLLOW COLUMN INSULATORS, SUPPORT INSULATORS ..	13
12.1 Tests.....	14
12.2 Technical parameters of bushings, hollow column insulators and support insulators:	14

13.0 CIRCUIT BREAKERS.....	14
13.1 General.....	14
13.2 Power operated mechanism.....	15
14.0 RELAYS.....	15
15.0 CONTACTORS.....	16
16.0 INSTRUMENT TRANSFORMERS.....	16
17.0 INDICATING INSTRUMENTS.....	17
18.0 CONTROL AND SELECTOR SWITCHES.....	17
19.0 AIR BREAK SWITCHES.....	19
20.0 PUSH BUTTONS.....	19
21.0 INDICATING LAMPS.....	19
22.0 FUSES.....	20
23.0 NAME PLATES AND LABELS.....	20
24.0 ELECTRIC MOTORS (LV).....	21
24.1 Codes and Standards.....	21
24.2 Service conditions and temperature rise.....	21
24.3 AC Motors.....	21
24.3.1 General.....	21
24.3.2 Transient recovery.....	22
24.4 DC Motors.....	22
24.5 Enclosure and method of cooling.....	22
24.6 Constructional features.....	23
24.7 Variable speed motors.....	23
24.9 Internal electric heaters.....	24
24.10 Lifting facilities.....	24
24.11 Winding and insulation.....	24
24.12 Bearings.....	24
24.13 Heat exchangers.....	25
24.14 Noise level.....	25

24.15 Vibration level	25
24.16 Earthing terminals.....	25
24.17 Terminal boxes and associated fittings	25
24.18 Rating plate.....	26
24.19 Paint and finish	26
24.20 Tests	26
24.20.1 Routine Tests	26
24.20.2 Type Tests	27
24.20.3 DC motors	27
24.21 Junction boxes and cables	27

25.0 JUNCTION BOXES 28

25.1 Construction	28
25.2 Interconnecting cables.....	28

26.0 CONDUIT AND CONDUIT ACCESSORIES 28

1..... MOTORS

1.1 General

All motors shall comply with IEC 34 / IS 335 and dimensions with IEC 72, however they shall be capable of operating continuously under actual service conditions without exceeding the specified temperature rises, determined by resistance, at any frequency between 48 and 51.5Hertz together with any voltage between ± 10 per cent of the nominal value.

All motors shall be totally enclosed, and if situated in the open they shall be weatherproof and suitable for outdoor working. They shall be provided with a suitable means of drainage to prevent accumulation of water due to condensation and with suitable means of breathing.

Motors operating in an ambient temperature not exceeding 40°C shall have insulation to at least ClassB and preferably ClassF standards. The temperature rise shall be restricted to that associated with ClassB insulation. Where the motor may be appreciably affected by conducted heat the class of insulation shall be to approval.

All motors shall be suitable for direct starting at full voltage.

Motors shall have sealed ball or roller bearings.

The three line connections of AC motors shall be brought out to a terminal box. The terminal arrangement shall be suitable for the reception of aluminium cable. Terminal markings shall be made in a clear and permanent manner and shall comply with IEC 34. A permanently attached diagram or instruction sheet shall be provided giving the connections for the required direction of rotation. All terminal boxes shall be of the totally enclosed type designed to exclude the entry of dust and moisture and sealed from the internal air circuit of the motor. All joints shall be flanged with gaskets of neoprene or other approved material. Natural rubber insulation shall not be used.

Motors rated above 1 kW shall be three phase motors. Where single phase motors are employed the motors shall be grouped so as to form an approximately balanced three phase load.

1.2 Motor control gear

Control gear shall comply with the requirements of IEC292, the control gear being rated according to the duty imposed by the particular application.

Motor contactors shall comply with IEC158 class of intermittent duty 0-3 with type 52 enclosure protection. Apparatus shall be capable of switching the stalled current, and shall have a continuous current rating of at least 50per cent greater than the full load current of the motors they control.

The operating currents of overload trips fitted to motor contactors shall be substantially independent of ambient temperature conditions, including the effect of direct sunlight on the enclosure in which the contactors are installed.

Where small motors are connected in groups, the group protection shall be arranged so that it will operate satisfactorily in the event of a fault occurring on a single motor. The control and protection equipment shall be accommodated in the control cabinet or marshalling kiosk.

Each motor or group of motors shall be provided with control gear for starting and stopping by hand and automatically. Overload and single-phasing protection shall be provided.

2.0 CABLE BOXES

Cable boxes shall be suitable for cables entering from above or below as may be required. They shall be weatherproof, rodent and insect-proof and be complete with all gaskets, compression glands, wiping glands and all associated fittings as may be required to make-off the cables.

Gland plates shall be insulated from the cable boxes and, in the case of single core cables, shall be of non-magnetic or insulating material. If metallic gland plates are used, single core cable glands shall be insulated from the gland plate. Gland plate insulation shall be capable of withstanding a dry high voltage test of 2000volts ac for one minute.

Where cable boxes are provided for three core cables, the sockets on the outer phases shall be inclined towards the centre to minimise opening of the cable cores. Cable sockets shall be supplied under this Contract.

Cable boxes for voltages up to and including 11kV shall be suitable for PVC or XLPE insulated steel wire-armoured PVC served cables. The boxes shall be air insulated and designed to accommodate all the fittings required by the cable manufacturer. Front covers and gland plates shall be removable and a 12mm diameter breathing hole covered with a wire gauze shall be provided.

Cable boxes shall be capable of withstanding on site the cable high voltage test level in accordance with IEC 502.

The drilling of gland plates, supply and fitting of compression glands and connecting up of power cables not included in the Contract scope of work shall be carried out under a separate contract.

Connection of the power cables included in the Contract scope of works shall be carried out under this Contract.

3.0 TERMINAL BOARDS AND TERMINAL BLOCKS

Terminal boards shall be of good quality non-flammable insulating material with a comparative tracking index (CTI) of not less than 500 to IEC112.

Terminal boards shall be spaced not less than 150 mm apart. For relay panels, they shall be mounted at the sides of the cubicle, and set obliquely towards the rear doors to give easy access to termination and to enable ferrule numbers to be read without difficulty.

Studs of stud type terminal boards shall be locked in the base to prevent turning and all connections shall be made on the front of the terminal board using lock nuts or lock washers. Where crimped type termination are provided at least two sets of crimping tools for each size of crimp must be supplied for each installation.

Terminals shall be of the insertion clamp type incorporating captive pressure screws which do not bear directly on the wire but on a serrated clamping plate. The pressure screws shall have an inherent locking feature.

Where connections are to be made between multi-core cables and telephone type multi-pair cables, the terminal blocks shall be of the insulation displacement type and shall have a withdrawable insulated link in order to facilitate isolation (or busy out in the case of the apparatus associated with the telephone system) of the individual circuits. These terminals shall also be provided with facilities for the insertion of test probes on both sides of the link.

All terminations shall be numbered for identification and grouped according to function. Engraved white on black labels shall be provided on the terminal blocks.

Terminals for connections which exceed 110 Volts shall be separated from those of other circuits and shall be fitted with insulating screens and "DANGER" notices.

The use of terminal blocks as junction points for wires which are not required in the associated cubicle shall be avoided wherever practicable.

All termination racks shall have a minimum of 20 per cent spare terminals blocks. At least 20% spare terminals shall be provided on each panel and these spare terminals shall be uniformly distributed on all terminal blocks.

All internal wiring to be connected to external equipments shall terminate on terminal blocks, preferably vertically mounted on the side of each panel. Terminal blocks shall be 650 V grade and have 10A continuous rating. Terminal blocks shall be moulded in one piece, complete with insulated barriers, stud type terminals, washers, nuts and lock nuts. Terminal blocks shall include a white fibre marking strip with clear plastic, slip-on/clip-on terminal covers. Markings on the terminal strips shall correspond to terminal numbers on the wiring diagrams.

Terminal blocks for current transformer and voltage transformer secondary leads shall be provided with test links and isolating facilities. Current transformer secondary leads shall be provided with short circuiting and earthing facilities.

All terminal blocks shall be suitable for terminating on each side, two by 2.5 mm² standard copper conductors.

Wherever duplication of a terminal block is necessary it shall be achieved by solid bonding links.

Unless otherwise specified, terminal blocks shall be suitable for connecting the following conductors on each side :

- All CT and VT circuits : Minimum of two 2.5 mm² copper stranded.
- AC/DC power supply circuits : One 16 mm² aluminium.
- All other circuits : Minimum of one of 2.5 mm² copper stranded

There shall be a minimum clearance of 250 mm between the first row of terminal blocks and the associated cable gland plate or panel side wall, as per the terminal block mounting arrangement adopted. Also the clearance between the edges of two rows of terminal blocks shall be minimum of 150 mm.

Arrangement of the terminal block assemblies and the wiring channel within the enclosure shall be such that a row of terminal blocks is run in parallel and close proximity along each side of the wiring duct to provide for convenient attachment of internal panel wiring. The side of the terminal blocks opposite the wiring duct shall be reserved for external cable connections. All adjacent terminal blocks shall also share this field wiring corridor. All wiring shall be provided with adequate support inside the panels to hold it firmly and to enable free and flexible termination without causing strain on terminals.

All necessary cable terminating accessories such as gland plates, supporting clamps and brackets, wiring troughs and gutters etc. including glands and lugs for cable shall be in Contractors scope of supply.

4.0 FUSES AND LINKS

Carriers and bases for fuses and links shall be in accordance with IEC 269 and colour coded to permit identification of the circuit rating.

The fuses and links mounted in cubicles for tripping circuits and protective gear test links shall be mounted on the front of the panel. Other links and fuses shall be accommodated within the cubicle or above the cubicle doors. Fuses and links shall be grouped and spaced according to their function in order to facilitate identification.

All incoming circuits in which the voltage exceeds 125V shall be fed through insulated fuses and/or links, the supplies being connected to the bottom terminal. The contacts of the fixed portion of the fuse or link shall be shrouded so that accidental contact with live metal cannot be made when the moving portion is withdrawn.

Main supply fuse links shall be of the high rupturing capacity cartridge type.

Where fuse carriers are mounted vertically the incoming (supply) side shall be the bottom terminal.

Where either fuses or circuit breakers are used it should be ensured that proper discrimination between main and sub-circuits is maintained.

5.0 COMMUNICATIONS CABLES

All cables and wiring shall have copper conductors and PVC insulation and shall comply with IEC 227. Telephone type cables shall comply with IEC 96 and IEC 189.

Cabling and wiring installations shall be arranged to minimise the risk of fire and damage which may be caused in the event of fire.

For telephone type cables conductor wires with a cross sectional area of less than 0.2 mm² shall not be used. Where twin or quad make up is required in any cable the cores shall be uniformly twisted and the lays arranged such that crosstalk is reduced to a minimum.

No conductor smaller than 32/0.2mm (1mm²), or having less than three strands shall be used for interconnecting cabling except in the case of telephone cables. All cables shall have insulation which will withstand the highest temperature to be experienced in service.

Each conductor of a multi-core cable shall be readily identified by a numbered marker tape or, in the case of telephone type cables, colour coded insulation.

The Contractor shall submit full details of all loading on cables and in the case of interposing current transformer connections, the loop resistance of each circuit.

Apparatus cubicles, cabinets, racks and panels shall be provided with gland plates and all necessary equipment for the termination of cables. The Contract Works shall include for the checking, termination and ferruling of the cable cores and their lacing into cable forms and connection to the equipment terminal boards or tag blocks using claw washers. Crimping ferrules shall be used for each conductor.

6.0 MARSHALLING KIOSKS AND CONTROL CABINETS

The Contractor shall provide within every bay of the switch yard a bay marshalling kiosk to which all incoming and outgoing connections to and from the associated bay equipment will be run. The terminal blocks within the kiosks shall be grouped together by function and shall be properly labelled and segregated. Transformer and circuit breaker control/marshalling kiosks will be provided under a separate contract, but it shall be the Contractor's responsibility to cable up to the control/marshalling

kiosks as provided by the transformer and circuit breaker suppliers. The Contractor shall provide a separate stand alone kiosk for busbar protection CT marshalling and the kiosk shall house the CT shorting and switching relays required for the correct function of the busbar protection scheme.

All outdoor cabinets and kiosks shall be protected in accordance with Class IP55 of IEC 947-1 and shall be insect and rodent proof. The minimum sheet steel thickness for all cubicles, kiosks and panels shall be not less than 2 mm cold rolled or 2.5 mm hot rolled sheet steel. The top of the outdoor boxes/kiosks shall be provided with Aluminium alloy sheets having 2 mm thick with proper sloping for easy discharge of water.

Anti-condensation heaters, 240V AC single phase, shall be provided and shall be controlled by a watertight switch mounted externally. Ventilation louvres shall be provided, suitably lined internally with a mesh screen, and divisions between compartments shall be perforated.

Control cabinets shall be illuminated with a switch operated and fused 240V CFL tube. Control cabinets shall be provided with a switch operated single phase 240V 15A power socket.

All cables shall enter cabinets and kiosks at the base.

Each compartment of all kiosks and cabinets shall be provided with access doors at the front and rear. Doors and access covers shall not be secured by nuts and bolts but shall be fastened with integral handles with provision for locking with a padlock.

Doors for kiosks shall be of the lift off and hinged type and shall be provided with glazed windows of adequate size to facilitate reading of indicators from outside the kiosk. Facilities shall be provided to permit removal of the temperature indicators without the need to pass the capillary tubing and bulb through the various compartments.

Doors and covers under 15kg mass may be of the slide on pattern, but above this mass hinged doors shall be used. Door shall be provided with padlocking facilities.

When three phase connections rated at 380V and above are taken through cabinets or kiosks, the terminal blocks shall be adequately screened, insulated and suitably marked with the phase colour; "DANGER" notices shall be affixed to the terminal blocks and a DANGER notice stating the voltage shall be fixed on the inside and outside of the kiosk or cabinet. Exterior DANGER notices shall be stove enamelled and shall be written in English and Oriya and shall be of an approved class/grade.

A durable copy of the circuit wiring diagram shall be affixed to the back of the kiosk door and labels shall be provided inside each kiosk or box to describe the functions of the various items of equipment.

When the marshalling kiosks are positioned in side the switchyard , flood water shall not ingress in to the marshalling kisok. The contractor may achieve the same either positioning the marshalling kiosk appropriately or providing adequate water proof arrangement.

CT, CVT & IVT outdoor kiosks shall be of Aluminium alloy sheets having 3mm thickness. It shall have proper slop canopy for easy drainage of water.

7.0 AUXILIARY SWITCHES

With each disconnecter, contactor and earthing device, there shall be supplied all necessary auxiliary switches and mechanisms for indication, protection, control, interlocking, supervisory and other services as specified. Not less than four spare auxiliary switches of each type shall be provided.

All auxiliary switches shall be wired up to a suitable terminal board on the fixed portion of the switchgear whether they are in use or not in the first instance, and shall be arranged in the same sequence on all similar items of equipment. Switches shall be provided to interrupt the supply of current to the tripping mechanism of the circuit breakers and latched contactors. All such switches and mechanisms shall be mounted in accessible positions clear of the operating mechanism, and shall be adequately protected.

The contacts of all auxiliary switches shall be strong and be capable of adjustment in relation to the movement of the circuit breaker or other item of equipment. Auxiliary switches and auxiliary circuits shall be capable of carrying a continuous current of 10 Amps.

8.0 MINIATURE OR MOULDED CASE CIRCUIT BREAKERS

Miniature or moulded case circuit breakers (MCB ϕ or MCCB ϕ) shall be designed and tested in accordance with IEC 157 and supplementary requirements of this specification. They shall be suitable for use over the full range of expected voltage variation as specified in the Schedules.

MCB ϕ and MCCB ϕ shall be suitably rated for both the continuous and short circuit loading of the circuits they are protecting under all service and atmospheric conditions stated in the specification. The Contractor shall ensure that correct discrimination is maintained between main and sub-circuits.

For three phase circuits, the miniature circuit breakers shall be of the three pole type; for single phase circuits they shall be of the single pole type and for dc circuits they shall be of the double pole type.

Where miniature circuit breakers are used in circuits containing inductive loads, e.g. operating coils, it is essential that they are suitable for satisfactory operation in the circuit in which they are used, i.e. account is taken of the circuit time constant.

All miniature circuit breakers shall be provided with an auxiliary contact for remote indication of circuit breaker operation.

Means shall be provided to prevent the miniature circuit breakers being inadvertently switched to the -OFF ϕ position.

Miniature circuit breakers shall be mounted in such a manner so as to give easily visible indication of breaker position and shall be grouped and spaced according to their function in order to facilitate identification and easy replacement.

9.0 SPACE HEATERS

Heaters shall be suitably designed to prevent any contact between the heater wire and the air. They shall consist of coiled resistance wire centred in a metal sheath and completely encased in a highly compacted powder of magnesium oxide or other material having equal heat conducting and electrical insulation properties, or they shall consist of resistance wire wound on a ceramic and completely covered with a ceramic material to prevent any contact between the wire and the air.

Alternatively, they may consist of a resistance wire mounted into a tubular ceramic body built into an envelop of stainless steel or the resistance wire wound on a tubular ceramic body and embedded in vitreous glaze. The surface temperature of the heaters shall be restricted to a value which will not shorten the life of the heater sheaths or that of insulated wire or other component in the compartments.

10.0 LVAC CABLES

10.1 General

LVAC power cables shall have aluminium conductors with XLPE insulation, galvanised steel wire armour and PVC oversheath and shall comply with the requirements of IEC 227, 228 and 502 as applicable. Cables shall be sized to carry the highest anticipated load under the worst case ambient conditions. Where a three, three and a half or four core power cable is provided, the cores shall be coloured to distinguish the relevant phases.

All sheaths shall be free from defects and impervious to water.

10.2 1.1kV grade power and control cables

10.2.1 Codes and Standards

The design, manufacture, testing and performance of cables covered under this specification shall comply with latest edition of the standards including amendments as indicated in the relevant schedules attached to this specification.

10.2.2 Technical requirements

The cables shall be suitable for laying in racks, ducts, trenches, conduits and underground buried installation with uncontrolled backfill and chances of flooding by water.

They shall be designed to withstand all mechanical, electrical and thermal stresses under steady state and transient operating conditions. The XLPE insulated LV power cables shall withstand without damage a three phase fault current of at least 45 kA for a minimum of 0.12 seconds, with an initial peak of 105 kA in one of the phases. The armour for XLPE insulated power cables shall be capable of carrying 45 kA for at least 0.12 seconds without exceeding the maximum allowable temperature of PVC outer sheath.

Progressive sequential marking of the length of cable in metres at every one metre shall be provided on the outer sheath of all cables.

Strip wire armouring following method (a) of the relevant IS shall not be accepted for any of the cables. For control cables round wire armouring only shall be used.

Cables shall have outer sheath of a material with an oxygen index of not less than 29 and a temperature index of not less than 250°C.

All the cables shall pass fire resistance test as per IS 1554 (Part-I)

The normal current rating of all PVC insulated cables shall be as per IS 3961.

Repaired cables shall not be accepted.

10.3 LV XLPE power cables

XLPE insulated cables shall conform to IS 7098 (Part-I) and its amendments read along with this Specification. The conductor shall be stranded aluminium circular/sector shaped and compacted. In multi-core cables, the core shall be identified by red, yellow, blue and black coloured strips or colouring of insulation. A distinct inner sheath shall be provided in all multi-core cables even if they are unarmoured. For armoured or unarmoured cables, the inner sheath shall be of extruded PVC to type ST-2 of IS 5831. When armouring is specified for single core cables, the same shall consist of aluminium wires/strips.

10.4 LV XLPE power cables

PVC (70C) insulated 1100V grade power cables shall conform to IS 1554 (Part-I) and its amendments, read along with this Specification and shall be suitable for a steady conductor temperature of 70°C. The conductor shall be stranded aluminium. Insulation shall be extruded PVC to type-A of IS 5831. A distinct inner sheath shall be provided in all multi-core cables. For multi-core armoured cables, the inner sheath shall be of extruded PVC. The outer sheath shall be extruded PVC to Type ST-1 of IS 5831 for all cables.

10.5 LV PVC control cables

The 1100V grade control cables shall conform to IS 1554 (Part-1) and its amendments, read along with this specification. The conductor shall be stranded copper. The insulation shall be extruded PVC to type A of IS 5831. A distinct inner sheath shall be provided in all cables whether armoured or not. The oversheath shall be extruded PVC to type ST-1 of IS 5831 and shall be grey in colour except where specifically advised by the Project Manager to be black.

Cores shall be identified as per IS 1554 (Part-1) for cables up to five cores and for cables with more than five cores the identification of cores shall additionally be done by printing legible alphabets on all cores. The alphabets shall be white and shall be printed at approximately 100 mm intervals along the cable length. Cables without such core identifications will not be accepted.

10.6 Cable drums

Cables shall be supplied non-returnable wooden or steel drums of heavy construction. Wooden drums shall be properly seasoned sound and free from defects. Wood preservative shall be applied to the entire drum.

Standard lengths for each size of power and control cables shall be 500/1000 meters. The cable length per drum shall be subject to a tolerance of plus or minus 5% of the standard drum length. The Project Manager shall have the option of rejecting cable drums with shorter lengths. However, the total quantity of cables after taking into consideration of all cable drums for each size shall be within the tolerance of $\pm 2\%$.

A layer of water proof paper shall be applied to the surface of the drums and over the outer most cable layer.

10.7 Tests

All cables shall conform to all type, routine and acceptance tests listed in the relevant IS.

The temperature index tests shall be carried out as per ASTM-D-2863.

All cables shall meet the fire-resistance test as per IS 1554 (Part-I)

10.8 Cable sizes

Following standard sizes of cables shall be considered by Bidder for various power distribution and protection, control and metering purposes in the system:

- XLPE power cables: 1c 630 mm², 1c 300 mm², 3 1/2c 300 mm². (armoured)
- LV XLPE power cables: (armoured) 1c 150 mm², 3 1/2 c 70 mm², 3 1/2c 35 mm², 4c 16 mm², 4c 6 mm², 2c 6 mm².
- PVC control cables: 2c 2.5 mm², 3c 2.5 mm², 5c 2.5 mm², 7c 2.5 mm², 10c 2.5 mm², 14c 2.5 mm², 19c 2.5 mm², 27c 2.5 mm²

11.0 BUSHINGS

All bushings shall comply with the requirements of IEC 137 and the associated barrel porcelains shall comply with IEC 233 together with the requirements of this Specification. Provision shall be made for the fitting of arcing horns.

Transformer bushings rated at 66 kV and above shall be either of the oil impregnated paper or resin impregnated type. When filled with transformer oil there shall be no connection with the oil in the transformer and an oil gauge shall be provided. The visible oil levels in the gauge shall correspond to the range of average oil temperatures, from the minimum ambient stated in the Schedules to plus 70C. The oil level at 15C shall be marked. Connections from the main windings to bushings shall be flexible and shall be such that undue mechanical stresses are not imposed on them during assembly on site.

Terminal clamps shall be supplied with each bushing for flexible or rigid busbars as may be required. The material of the clamps shall be as stated in the Schedules.

12.0 BUSHINGS, HOLLOW COLUMN INSULATORS, SUPPORT INSULATORS

Bushings shall be manufactured and tested in accordance with IS 2099 and IEC 137 while hollow column insulators shall be manufactured and tested in accordance with IEC 233/IS 5621. The support

insulators shall be manufactured and tested as per IS 2544/IEC 168 and IS 2099/IEC 273. The insulators shall also conform to IEC 815 as applicable.

The Contractor may also offer composite silicon insulators conforming to IEC 36.

Support insulators, bushings and hollow column insulators shall be manufactured from high quality porcelain. Porcelain used shall be homogeneous, free from laminations, cavities and other flaws or imperfections that might affect the mechanical or dielectric quality and shall be thoroughly vitrified tough and impervious to moisture.

Glazing of the porcelain shall be uniform brown in colour, free from blisters, burrs and other similar defects.

Support insulators, bushings and hollow column insulators shall be designed to have ample insulation, mechanical strength and rigidity for the conditions under which they will be used.

When operating at normal rated voltage there shall be no electric discharge between the conductors and bushing which would cause corrosion or injury to conductors, insulators or supports by the formation of substances produced by chemical action. No radio interference shall be caused by the insulators or bushings when operating at the normal rated voltage.

Bushing porcelain shall be robust and capable of withstanding the internal pressures likely to occur in service. The design and location of clamps and the shape and the strength of the porcelain flange securing the bushing to the tank shall be such that there is no risk of fracture. All portions of the assembled porcelain enclosures and supports other than gaskets, which may in any way be exposed to the atmosphere shall be composed of completely non hygroscopic material such as metal or glazed porcelain.

All iron parts shall be hot dip galvanised and all joints shall be air tight. Surface of joints shall be trued up, porcelain parts by grinding and metal parts by machining. Insulator and bushing design shall be such as to ensure a uniform compressive pressure on the joints.

12.1 Tests

In accordance with the requirements stipulated above bushing, hollow column insulators and support insulators shall conform to type tests and shall be subjected to routine tests in accordance with IS 2099 and IS 2544.

All routine tests shall be conducted on hollow column insulators as per IEC 233. In addition the following tests shall also be conducted

1. Ultrasonic test as a routine test.
2. Pressure test as a routine test.
3. Bending load test in four directions at 50% specified bending load, as a routine test.
4. Bending load test in four directions at 100% specified bending load, as a sample test on each lot.
5. Burst pressure test as a sample test on each lot.
6. Hollow porcelain insulators should be in one integral piece in green and fired stage. No jointed porcelain will be acceptable.

12.2 Technical parameters of bushings, hollow column insulators and support insulators:

Parameter	420kV	245kV	145kV	36kV
Rated voltage kV	420	245	145	36
Impulse withstand (wet and dry) kVp	±1425	±1050	±650	±170

Switching surge withstand (wet and dry) kVp	±1050			
Power frequency withstand (wet and dry) kVrms	630	460	275	70
Total creepage distance mm	10500	6125	3625	900

Pollution level shall be Class III Heavy as per IEC 71, and as specified in Schedules for all classes of equipment.

Insulators shall also meet the requirements of IEC 815 for 420kV, 245kV and 145kV systems as applicable having alternate long and short sheds.

13.0 CIRCUIT BREAKERS

13.1 General

Circuit breakers shall be of three pole air break design, horizontal draw out type in accordance with IEC 947-2. In particular, evidence shall be provided of the performance when switching currents in the critical current range. They shall be capable of the ratings specified in the Schedules, when mounted in the switchboard.

Circuit breakers shall be fitted with trip-free, spring-operated mechanisms of the independent manually operated type and be provided with making and over current release facilities. A push-button shall be provided to trip the breaker electrically.

The breaker shall be provided with '**OPEN**', '**CLOSE**', '**SERVICE**', '**TEST**' and '**SPRING CHARGED**' position indicators and shall be provided with the necessary number of auxiliary contacts for interlocking, indication and tripping purposes plus two spare.

Each incoming circuit shall be provided with thermal overload relays and short circuit protection relays; they shall also be provided with an undervoltage relay to trip breaker in the event of a supply failure.

There shall be '**SERVICE**', '**TEST**' and fully withdrawn positions for the breakers. It shall be possible to close the door in '**TEST**' position.

Movement of a circuit breaker between '**SERVICE**' and '**TEST**' positions shall not be possible unless it is in '**OPEN**' position. Attempted withdrawal of a closed circuit breaker shall not trip the circuit breaker.

Closing of a circuit breaker shall not be possible unless it is in '**SERVICE**', '**TEST**' or fully withdrawn positions.

A breaker of particular rating shall be prevented from insertion in a cubicle of a different rating.

Circuit breakers shall be provided with electrical anti-pumping and trip free feature.

Means shall be provided to slowly close the circuit breaker in withdrawn position if required for inspection and setting of contacts. In service position slow closing shall not be possible.

Circuit breakers shall be provided with the following mechanism as specified in the Bill of Material.

13.2 Power operated mechanism

Power operated mechanism shall be provided with a universal motor suitable for operation 220V DC control supply with voltage variation from 90% to 110% rated voltage. Motor insulation shall be class 'E' or better.

The motor shall be such that it requires not more than 30 seconds for fully charging the closing spring.

Once the closing springs are discharged, after the one closing operation of circuit breaker, it shall automatically initiate, recharging of the spring.

The mechanism shall be such that as long as power is available to the motor, a continuous sequence of closing and opening operations shall be possible. After failure of power supply at least one open-close-open operation shall be possible.

Provision shall be made for emergency manual charging and as soon as this manual charging handle is coupled, the motor shall automatically be mechanically decoupled.

All circuit breakers shall be provided with closing and tripping coils. The closing coils shall operate correctly at all values of voltage between 85% to 110% at rated control voltage. Tripping coils shall operate satisfactorily under all values of supply voltage between 70% to 110% of rated control voltage.

Provision for mechanical closing of the breaker only in 'TEST' and withdrawn positions shall be made.

14.0 RELAYS

All relays and timers in protective circuits shall be flush mounted on panel front with connections from the inside. They shall have transparent dust tight covers removable from the front. All protective relays shall have a drawout construction for easy replacement from the front. They shall either have built-in test facilities, or shall be provided with necessary test blocks and test switches located immediately below each relay. Auxiliary relays and timers may be furnished in non-drawout cases.

All AC relays shall be suitable for operation at 50 Hz with 110 volts VT secondary and 1A or 5A CT secondary.

All protective relays and timers shall have at least two potential free output contacts. Relays shall have contacts as required for protection schemes. Contacts of relays and timers shall be silver faced and shall have a spring action. Adequate numbers of terminals shall be available on the relay cases for applicable relaying schemes.

All protective relays, auxiliary relays and timers shall be provided with hand reset operation indicators (flags) for analysing the cause of operation.

All relays shall withstand a test voltage of 2kV (rms) for one minute.

Motor starters shall be provided with three element, ambient temperature compensated, time lagged, hand reset type terminal overload relays with adjustable settings. The setting ranges shall be properly selected to suit the motor ratings. These relays shall have a separate black coloured hand reset push button mounted on compartment door and shall have at least one changeover contact.

All fuse protected, contactor controlled motors shall have single phasing protection, either as a distinct feature in the overload relays (by differential movement of bi-metallic strips), or as a separate device. The single phasing protection shall operate with 80% of the set current flowing in two of the phases.

15.0 CONTACTORS

Motor starter contactors shall be of air break, electromagnetic type rated for uninterrupted duty as per IS 2959.

Contactors shall be double break, non-gravity type and their main contacts shall be silver faced.

Direct line starter contactors shall be of utilisation category AC2. These contactors shall be as per IS 1822.

Each contactor shall be provided with two normally open (NO) and two normally close (NC) auxiliary contacts.

Operating coils of contactors shall be of 240V AC unless otherwise specified elsewhere. The Contactors shall operate satisfactorily between 85% to 110% of the rated voltage. Contactors shall drop out at 70% of the rated voltage.

16.0 INSTRUMENT TRANSFORMERS

All current and voltage transformers shall be completely encapsulated cast resin insulated type suitable for continuous operation at the temperature prevailing inside the switchgear enclosure, when the switchboard is operating at its rated condition and the outside ambient temperature is 50°C.

All instrument transformers shall be able to withstand the thermal and mechanical stresses resulting from the maximum short circuit and momentary current ratings of the associated switchgear.

All instrument transformer shall have clear indelible polarity markings. All secondary terminals shall be wired to a separate terminal on an accessible terminal block where star-point formation and earthing shall be done.

Current transformers may be multi or single core type. All voltage transformers shall be single phase type. Busbar VTø shall be housed in a separate compartment.

All VTø shall have readily accessible HRC current limiting fuses on both primary and secondary sides.

17.0 INDICATING INSTRUMENTS

All indicating and integrating meters shall be flush mounted on panel front. The instruments shall be of at least 96 mm square size with 90 degree scales, and shall have an accuracy class of 2.5 or better. The covers and cases of instruments and meters shall provide a dust and vermin proof construction.

All instruments shall be compensated for temperature errors and factory calibrated to directly read the primary quantities. Means shall be provided for zero adjustment without removing or dismantling the instruments.

All instruments shall have white dials with black numerals and lettering. Black knife edge pointer with parallax free dials will be preferred.

Ammeters provided on motor feeders shall have a compressed scale at the upper current region to cover the starting current.

Watt-hour meters shall be of three phase, three element type. Maximum demand indicators need not be provided.

18.0 CONTROL AND SELECTOR SWITCHES

Control and instrument switches shall be rotary operated type with escutcheon plates clearly marked to show the function and positions. Switches shall be suitable for flush mounting with only switch front plate and operating handle projecting from the panel front. Switches shall be of sturdy construction suitable for mounting on panel front. Switches with shrouding of live parts and sealing of contacts against dust ingress shall be preferred. Handles of different shapes along with suitable inscriptions on switches shall be provided as an aid to switch identification. The selection of operating handles for the different types of switches shall be as follows :

Switch Type	Application	Specification
Switchgear control switches	For closing and opening of breakers and isolators.	Pistol grip, black, three position type.
Synchronising switches	For synchronising check bypass facilities	Oval, black, keyed (common removable handle, or with locking facility and common key).
Selector switches	Auto, manual, local, remote and test facilities	Oval or knob, black
Instrument switches	Phase or meter selection	Round, knurled, black
Protection transfer switch	Transfer of protection.	Pistol grip, lockable and black.

TABLE 18.1 Switch operating handles

The control switches of breakers and isolators shall be of spring return to neutral type. The control springs shall be strong and robust enough to prevent inadvertent operation due to light touch. The spring return type switch shall have spring return from close and trip positions to 'after close' and 'after trip' positions respectively. They shall have at least two (2) contacts closing in close positions, and two (2) contacts closing in Trip positions unless specified otherwise.

Circuit breaker selector switches for breaker controlled motors shall have three stay put positions marked 'AUTO', 'MANUAL' and 'TEST' respectively. They shall have two contacts each of three positions and shall have black, pistol grip handles.

Instrument selection switches shall be of maintained contact stayput type. Ammeter selection switches shall have make-before-break type contacts so as to prevent open circuiting of CT secondaries when changing the position of the switch. Voltmeter transfer switches for AC shall be suitable for reading all line-to-line and line-to-neutral voltages for non effectively earthed systems, and for reading all line to line voltages for effectively earthed systems. Ammeter and voltmeter selector switches shall have four stayput positions with an adequate number of contacts for three phase four wire systems. These shall have black oval handles

Synchronising switches shall be of maintained contact stayput type having a common removable handle for a group of switches. The handle shall be removable only in the 'OFF' position and it shall be co-ordinated to fit in to all the synchronising switches. These switches shall be arranged to connect the synchronising equipment when turned to the 'ONØ' position. One contact of each switch shall be connected in the closing circuit of the respective breaker so that the breaker cannot be closed until the switch is turned to the 'ONØ' position.

Lockable type switches which can be locked in particular positions shall be provided when specified. The key locks shall be fitted on the operating handles.

The contacts of all switches shall preferably open and close with snap action to minimise arcing. Contacts of switches shall be spring assisted and contact faces shall be with rivets of pure silver or silver alloy. Springs shall not be used as current carrying parts.

The contact combination and their operation shall be such as to give completeness to the interlocking and function of the scheme. The contact rating of the switches shall be as follows :

Description	Contact rating in Amps		
	220V DC	50V DC	240V AC
Make and carry continuously	10A	10A	10A
Make and carry Make and carry for 0.5 sec.	30A	30A	30A
Break			
Resistive load	3A	20A	7A
Inductive Load with L/R=40ms	0.2A	—	—

TABLE 18.2 Contact ratings of switches

19.0 AIR BREAK SWITCHES

Air breaker switches shall be of the heavy duty, single throw group operated, load break, fault make type complying with IS 4064.

The Bidder shall ensure that all switches are adequately rated so as to be fully protected by the associated fuses during all abnormal operating conditions such as overload, locked motor, short circuit etc.

Switch operating handles shall be provided with padlocking facilities to lock them in 'OFF' position.

Interlocks shall be provided such that it is possible to open the cubicle door only when the switch is in 'OFF' position and to close the switch only when the door is closed. However suitable means shall be provided to intentionally defeat the interlocks explained above.

Switches and fuses for AC/DC control supply and heater supply wherever required shall be mounted inside and cubicles.

20.0 PUSH BUTTONS

Push-buttons shall be of spring return, push to actuate type. Their contacts shall be rated to make, continuously carry and break 10A at 240V and 0.5A (inductive) at 220V DC.

All push-buttons shall have one normally open and one normally closed contact, unless specified otherwise. The contact faces shall be of silver or silver alloy.

All push-buttons shall be provided with integral escutcheon plates marked with the appropriate function.

The colour of the button shall be as follows :

- GREEN** : For motor **START**, breaker **CLOSE**, valve /damper **OPEN**
- RED** : For motor **TRIP**, breaker **OPEN**, valve /damper **CLOSE**
- BLACK** : For overload reset, all annunciator and miscellaneous functions.

All push-buttons on panels shall be located in such a way that red push buttons shall always be to the left of green push buttons.

21.0 INDICATING LAMPS

Indicating lamps shall be of the panel mounting filament type and low watt consumption. Lamps shall be provided with series resistors, preferably built-in the lamps assembly. The lamps shall have escutcheon plates marked with its function, wherever necessary. Lamps shall have translucent lamp covers of colours appropriate to the application as indicated in Table 21.1

Colour	Indication
RED	For motor ON , breaker/isolator CLOSED , valve/damper OPEN
GREEN	For motor OFF , breaker /isolator OPEN , valve/damper CLOSE
WHITE	For motor Auto-Trip
BLUE	For all healthy conditions (e.g. control supply) and also for ' SPRING CHARGED '
AMBER	For all alarm conditions (e.g. overload) Also for ' SERVICE ' and ' TEST ' positions indicators.

TABLE 21.1 Indicating lamp colours

Indication lamps should be located just above the associated push buttons/control switches. Red lamps shall invariable be located to the right of green lamps. In case a white lamp is also provided, it shall be placed between the red and green lamps along with the centre line of control switch/push button pair. Blue and amber lamps should normally be located above the red and green lamps.

When associated with push-buttons, red lamps shall be directly above the green push button, and green lamps shall be directly above the red push-button.

The wattage and resistance of the lamps shall be as follows:

- 220/250V 5 - 10W 4000 - 8000 ohms
- 110V 5 - 10W 1000 - 2000 ohms

Neon indicating lamps or LED's shall be provided when specified. The wattage of the neon lamp shall be 0.25 to 0.5W.

Bulbs and lenses shall be interchangeable and easily replaceable from the front of the panel. Tools, if required for replacing the bulbs and lenses shall also be included in the scope of supply.

All indicating lamps shall be suitable for continuous operation at 90 to 110% of their rated voltage.

22.0 FUSES

All fuses shall be of HRC cartridge fuse link type. Screw type fuses shall not be accepted. Fuses for AC circuits shall be of Class 2 type, 20kA (RMS) breaking current at 415V AC, and for DC circuits Class 1 type 4kA breaking current.

Fuses shall have visible operation indicators.

Fuses shall be mounted on fuse carriers, which are mounted on fuse bases. Wherever it is not possible to mount fuses on carriers, they shall be directly mounted on plug in type bases. In such cases one set of insulated fuse pulling handles shall be supplied with each switchgear.

Fuse ratings shall be chosen by the Contractor depending upon the circuit requirements and these shall be subject to approval of Project Manager.

23.0 NAME PLATES AND LABELS

All switchgears and ACDC distribution boards etc. shall be provided with prominent, engraved identification plates. The module identification plate shall clearly give the feeder number and feeder designation. For single front switchboards, similar panel and board identification labels shall be provided at the rear also. Language shall conform to the requirements stipulated elsewhere in the technical specification..

All name plates shall be of non-rusting metal or 3-ply lamincoid with white engraved lettering on black back ground. Inscriptions and lettering sizes shall be subject to Project Manager's approval.

Suitable plastic sticker labels shall be provided for easy identification of all equipment, located inside the panel or module. These labels shall be positioned so as to be clearly visible and shall give the device number as mentioned in the module wiring drawings.

24.0 ELECTRIC MOTORS (LV)

24.1 Codes and Standards

All motors shall conform to the latest revisions of the relevant IEC, Indian Standards, British Standards given in the schedules, except where modified or supplemented by this Specification.

The design, manufacture, installation and performance of motors shall conform to the provisions of latest Indian Electricity Act and Indian Electricity Rules. Nothing in these specifications shall be construed to relieve the contractor of his responsibility in this regard.

In case of contradiction between this specification and IS or BS or IEC, the stipulations on this specification shall prevail.

National Electrical Code for Hazardous locations and relevant NEMA standard shall also be applicable for motors located in hazardous location.

24.2 Service conditions and temperature rise

Unless otherwise specified, machines shall be designed for a maximum ambient air temperature of 50C. Accordingly the temperature rise of the stator winding by resistance method over the ambient air temperature shall not exceed 70C.

For applications where the motor temperatures may be appreciably affected by conducted or radiated heat, the amount of heat must be specified by the Contractor and the appropriate temperature rises agreed.

24.3 AC Motors

24.3.1 General

All AC motors shall be of squirrel cage type, unless otherwise specified and shall be suitable for direct on line starting.

Each motor shall be assigned a maximum continuous rating (MCR) corresponding to 70C temperature. Maximum continuous motor rating shall be at least ten percent above the maximum load demand of the driven equipment at designed capacity.

Rated voltage for AC motors shall be as given below for various MCRs of the motor, unless specified otherwise:

- From 0.2 kW to 220 kW 415 V, three phase, 50 Hz
- Below 0.2 kW 240 V, single phase, 50 Hz

Voltage and frequency variations shall be as per clause 3.3 of IS 325.

The lowest voltage at the motor terminals throughout the starting period, with which the driven equipment shall satisfactorily start up even under the most arduous conditions specified, shall be 85% for motors rated up to 110 kW, and 80% for motors rated above.

The accelerating torque at any speed with the lowest starting voltage shall be at least ten (10) percent of rated full load torque of the motor.

The motors shall be suitable for two starts in succession under the specified conditions of load, torque and inertia, with the motor initially at its normal running temperature.

The ratio of locked rotor kVA at rated voltage to rated kW (MCR corresponding to 70C temperature rises) shall not exceed the following (without any further tolerance):

Motor MCR kW	Start kVA/Rated kW
Up to 110kW	1.0
Above 110kW	10.0

When tests to determine the breakaway starting current of cage induction motors are taken at reduced voltage, due allowance shall be made for the effect of saturation. The estimated value of breakaway starting current at rated voltage shall be given on all test certificates.

All motors shall be so designed that the maximum inrush currents and locked rotor and pull out torque, developed by them at 110% of the rated voltage, do not endanger the motor or the driven equipment.

The pull out torque at rated voltage shall not be less than 200 percent of the full load torque.

Motors for reciprocating compressors etc. shall be specially designed/rated to withstand the torque pulsation produced by the driven equipment.

24.3.2 Transient recovery

The motors shall be capable of resuming normal operation after a system disturbance causing temporary loss of supply voltage for periods of up to 0.2 second (fault clearance time), followed by

sudden restoration to 70 percent rated voltage. From this voltage the motors shall be capable of acceleration and ultimate recovery under the most arduous load conditions.

24.4 DC Motors

DC motors shall comply with IS 4722 and shall be shunt wound type rated for 220V. Motor MCR kW rating at 50C ambient shall be at least ten percent higher than the power requirement of the driven equipment under the most onerous operating conditions foreseen during the plant's life.

DC motors which are to operate from batteries shall be capable of operating continuously under actual service conditions at any voltage between 190V and 240V.

DC motors supplied from rectifier equipment connected to AC power supplies shall meet the voltage and frequency variations specified for AC motors.

Rectifier equipment shall be capable of meeting the condition of transient recovery given above for AC motors and shall be provided with the necessary current limiting devices.

The pull-out torque of DC motors at the rated voltage shall not be less than 200 percent of the full load torque.

24.5 Enclosure and method of cooling

The following types of enclosure may be supplied:

- Totally enclosed, fan ventilated.
- Totally enclosed, closed air circuit, integral heat exchanger.
- Totally enclosed, closed air circuit, machine mounted heat exchanger.

In all cases protective enclosure and method of cooling of motors shall be IP 54 and IC 0141 in accordance with IS 4691 and IS 6362 respectively.

Cooling fans shall be directly driven from the motor shaft.

Motors situated outdoors or exposed to the weather shall be weather protected (IPW-55).

All totally enclosed type of motors shall have a dust tight construction with suitable means of breathing and of drainage to prevent accumulation of water from condensation. Drain holes shall exclude bodies greater than 6 mm diameter.

24.6 Constructional features

All components shall be of adequate mechanical strength and robustness and shall be constructed of metal unless otherwise approved. Glass fibre or plastic components, where employed, shall be of adequate design and robustness taking into account the conditions of service required and the effects of operating temperatures, ageing and thermal stability of the material. The material shall be resistant to flame propagation.

Rotors shall be so designed as to keep the combined critical speeds with the driven equipment away from the running speed by at least 20%.

Motors and their major components such as stators, rotors, terminal boxes, bearings and heat exchangers shall be designed to be readily interchangeable as integral units.

All motor rotors shall be dynamically balanced.

The enclosures shall be designed to provide an effective sealing between the primary and secondary air circuits.

The radial air gap between stator and rotor shall have an adequate margin to minimise the possibility of rubbing between the stator and rotor due to eccentric positioning, play and wear, shaft deflection due to rotor weight and unbalanced magnetic pull etc. The minimum radial air gap for all motors shall be in accordance with Clause 5.1.5 of IS 6381.

All requirements of clause 5.1.4 of IS 6381 shall also be complied with.

All the induction motors shall be capable of running at 75% of rated voltage for a period of 5 minutes.

Induction motors shall be designed to be capable of withstanding the voltage and torque stresses developed due to the difference between motor residual voltage and incoming supply voltage equal to 150% of the rated motor voltage during fast changeover of buses. The necessary features incorporated in the design to comply with this requirement shall be clearly indicated in this proposal.

24.7 Variable speed motors

Variable speed motors shall be such that the speed can be continuously adjusted over the required range. The speed control gear shall be provided with an interlock to ensure that the motor can only be started when its control sequence is at the correct setting. When the motor is switched off, the speed control sequence shall automatically return to this position.

24.8 Brush gear, commutators and slip-rings

Brush gear, commutators and slip-rings shall be designed to operate without injurious sparking and to run for at least three months without the need for adjustment or replacement of brushes.

Brushes shall be of electro graphite or metal graphite type. Adequate precautions shall be taken to protect the windings, commutators, slip-rings and brush gear against deposits of entrained carbon dust.

Removable covers shall be fitted to provide access to the brush gear, commutators and slip-rings. For totally enclosed type motors, windows shall be provided to permit observation of the brush gear whilst the motor is running.

Brush holders shall be of non-ferrous materials and located securely to accurately position the brushes on the commutator. Means for adjusting brush pressure and brush assembly shall be provided.

24.9 Internal electric heaters

Internal electric heaters shall be provided on motors rated above 30 kW, to maintain the windings in a dry condition during periods of standstill. The heater shall be suitable for use on a 240V, 50 Hz, AC supply.

24.10 Lifting facilities

All heavy parts of the motors shall be provided with adequate arrangements for lifting or handling during erection or overhaul.

All material used for equipment construction including castings and forging etc. shall be of tested quality as per relevant codes and standards. No welding shall be carried out on cast iron components for repair or any other purpose.

24.11 Winding and insulation

Winding insulation shall be of class B or better and of proven high quality and reliability.

All winding insulation shall be non-hygroscopic, oil resistant and of materials resistant to flame propagation. All windings shall be impregnated and suitably processed to effectively seal them to prevent deterioration from adverse environmental conditions at site during the installation period and also during normal operation.

All winding overhangs and leads shall be adequately supported, braced and blocked to provide sufficient rigidity during all normal conditions of service.

Cage windings and all joints shall be designed to give an adequate safety factor on fatigue due to thermal and mechanical stresses, taking into account the specified starting and running conditions. The short-circuiting and rings shall be of joint less construction. All electrical joints and connections shall be of brazed or welded construction.

Motors shall be designed to give a life endurance of at least 18000 starts.

24.12 Bearings

Bearings shall be of rolling type. Vertical motors shall normally have rolling type guide and thrust bearings.

Bearings shall be designed to prevent ingress of dust and water and shall be sealed against leakage of lubricant along the shaft.

When the motor shaft is not located axially by its own bearings, it shall be permanently marked to indicate its normal running position and the extent of float in either direction.

Bearings shall comply with the relevant Indian or International Standards. The bearing housing shall be correctly packed with lithium based grease at the time of assembly. Construction shall be such that the bearings can be dismantled without risk of damage.

For direct drives, bearings shall have an expected life of at least 40,000 running hours. For motors with significant external radial or axial loads, e.g. belt drives, bearing shall have a life of at least 15000 running hours. The bearing assembly shall be provided with a grease relief device to eject any surplus grease in to a separate container.

Lubrication shall be possible without removal of the guarding. All grease nipples, oil cups and dip sticks shall be readily accessible.

24.13 Heat exchangers

An adequate margin shall be included in the design of heat exchangers to allow for fouling of cooling tubes or ducts under service conditions. Provision shall be made for the easy cleaning of the cooling tubes or ducts, preferably on load.

The cooling tubes or ducts shall be adequately braced and supported to prevent vibration and premature fatigue or fracture.

24.14 Noise level

Noise levels shall comply with BS 4999, Part-51.

24.15 Vibration level

The double amplitude of vibrations as measured at motor bearings shall be within the limits specified in IS 4729, and the limits specified for the driven equipment.

24.16 Earthing terminals

Two independent earthing points shall be provided in accordance with IS 3043(1966), on opposite sides of the motor for bolted connection of Employer's earthing conductor.

24.17 Terminal boxes and associated fittings

Terminal boxes for motors rated above 110 kW shall be capable of withstanding a system fault level of 31 MVA for 0.12 seconds.

Unless otherwise approved, the terminal box shall be capable of being turned through 360 degrees in steps of 90 degrees.

415 volt terminals shall be suitable for receiving 1.1 kV grade PVC or XLPE, unarmoured or armoured power cables.

Only three line terminals need be brought out from each three phase primary winding. All inter phase connections whether star or delta shall be made inside the machine.

Marking of all terminals shall be in accordance with IS 4728.

Leads from terminals to the windings shall be adequately sized and braced to withstand heating and forces produced by maximum fault current.

Cable boxes and terminations shall be designed to enable easy disconnection and replacement of cables.

All joints other than those on cable glands shall be gasketed with neoprene, neoprene bonded cork or other approved material.

For single core cables, gland plates shall be effectively non-magnetic.

The following shall be supplied along with each motor :

1. Crimping type tinned copper lugs for power cables, with all necessary hardware.
2. Compression type tinned brass cable glands for power cables (to be supplied loose).
3. Removable type undrilled gland plate.
4. Terminal boxes shall be of weather proof construction with a degree of protection of IP-55. At least one motor of each batch shall be type tested to comply with the following : the terminal boxes shall be subject to an internal air pressure of 0.207 bar g for 12 hours. After this period the pressure shall not be less than 0.104 bar g (after correcting for any change in temperature).

24.18 Rating plate

In addition to the requirements as called for in General Technical Clauses and relevant IS, the rating plate shall indicate the following:

- Maximum continuous rating in kW for 70C temperature rise.
- Bearing identification numbers (in case of ball or roller bearings) and recommended lubricant.

24.19 Paint and finish

All external parts shall be finished and painted to produce a neat and durable surface which would prevent rusting and corrosion. The equipment shall be thoroughly degreased, and sharp edges and scales removed and treated with one coat of primer and two coats of grey enamel paint. Motor colour codes shall comply with the requirements indicated elsewhere in this Specification.

All fasteners used in the construction of the equipment shall be either of corrosion resistant material or electro galvanised to service condition 4. Current carrying fasteners shall be either of stainless steel or high tensile brass or copper.

24.20 Tests

Induction motors shall be subjected to the following routine and type tests.

24.20.1 Routine Tests

Visual Checks of the following:

- Marking on rating plates
- Appearance and painting
- Location and details of terminal boxes and accessories.
- In order to observe compliance to degree of protection, following test will be performed. It shall not be possible to insert a feeler gauge of 1 mm thick in the enclosure or flange faces.

Dimensional checks

Measurement of Insulation Resistance (IR) of windings, and space heaters.

Measurement of winding resistance, and space heater resistance at ambient temperature.

High voltage test on main windings, and space heaters.

IR measurement after HV test in main windings, and space heaters.

No load running test (reading of current, voltage input and speed measurement).

Measurement of bearing temperature during steady state conditions.

Vibration measurement at rated speed and rated voltage, also measurement of vibration during coasting down.

Reduced voltage running test at no load

Locked rotor test.

Phase sequence polarity check and check for terminal markings.

Over speed test

Measurement of air gap

Functional check on auxiliaries

24.20.2 Type Tests

All tests as listed under routine tests

Measurement of noise at no load

Locked rotor test - measurement of VA power input

Momentary overload test

Temperature rise test at rated conditions as well as at maximum input conditions (during heat run test, measurement of bearing temperature, winding temperature, core temperature, coolant flow and coolant temperature). In case the temperature rise test is carried at other load than rated load, specified approval for the test method and procedure shall be obtained from the Project Manager.

Degree of protection test for the enclosure followed by IR, HV and no load run test.

Terminal box - fault level withstand test and pressure test.

Pull out torque measurement

Measurement of no-load starting time.

24.20.3 DC motors

DC motors shall be subjected to all routine and type tests as per IS 4722. In addition, following tests shall be carried out:

- Noise level measurement as type test.
- Vibration measurement as routine test
- Degree of protection test as per IS 4691 as type test.

24.21 Junction boxes and cables

Design and selection of all the components shall be made with a good margin of safety factor.

The equipment shall be installed indoor.

The reference ambient temperature outside the equipment shall be taken as 50C and relative humidity as 100%.

25.0 JUNCTION BOXES

25.1 Construction

Contractor shall supply and install junction boxes complete with terminals as required.

Junction boxes shall be suitable for mounting on walls, columns, structures etc. The brackets, bolts, nuts, cable-glands, screws and all other accessories required for the erection shall be included in the Bidders scope.

Junction boxes shall be of square or rectangular type of 2.0 mm CRCA sheet steel and shall have bolted cover with good quality gasket lining.

Junction box and covers shall be hot dip galvanised.

All the terminals blocks of ESSEN make or equivalent shall be rated for 1100V and shall be of stud type. Each terminal shall be suitable for connecting two 2.5 mm² copper conductor.

All terminals shall be complete with insulated barriers, terminals studs, washers, nuts, locknuts, identification strips etc.

Junction boxes located inside shall have IP-54 protection as per IS 2147. Junction boxes located outside shall have IP-55 protection as per IS 2147.

Junction boxes shall be provided with one earthing terminal suitable for galvanised steel conductor.

The general arrangement, cross sectional details and other technical details are to be submitted in the form of drawing for Project Manager's approval.

25.2 Interconnecting cables

All cables between junction box and field devices shall be stranded copper conductor, PVC insulated, extruded PVC inner sheathed, single galvanised steel wire armoured and overall PVC sheathed 1.1 kV grade and shall conform to IS 1554. The minimum size of cable used shall be 2.5 mm² copper conductor. All cables shall be supplied by the Contractor.

26.0 CONDUIT AND CONDUIT ACCESSORIES

The contractor shall supply and install all rigid steel conduit, flexible conduits, Hume pipes etc. complete with accessories such as tees, bends, adaptors and couplings as required for cabling work between various field devices to junction boxes.

All conduits shall be seamed by welding and shall be heavy gauge hot dip galvanised.

Each piece of conduit shall be straight, free from any defects and conform to IS 1653. The manufacturer's name shall be stamped on each piece.

**ODISHA POWER TRANSMISSION CORPORATION LIMITED
OFFICE OF THE SR. GENERAL MANAGER,
CENTRAL PROCUREMENT CELL,
JANAPATH, BHUBANESWAR – 751022.**

TECHNICAL SPECIFICATION

FOR

**420,245, 145, & 36 KV(VCB)
CIRCUIT BREAKERS**

TECHNICAL SPECIFICATION

FOR

420,245 & 145 KV SF6 CIRCUIT BREAKER & 36 KV VCB

I- 420 KV SF6 CIRCUIT BREAKER

II-245KV SF6 CIRCUIT BREAKER

III-145 KV SF6 CIRCUIT BREAKER

IV – 36 KV VCB

420/245/145 KV CIRCUIT BREAKERS

1.0 SCOPE :

1.1 This specification provides for the design, manufacture, inspection and testing before dispatch, packing and delivery F.O.R. (destination) By Road transport only and supervision of erection, testing and commissioning, of outdoor SF6 circuit breakers along with structures, all the accessories and auxiliary equipment and mandatory spares, described herein, required for their satisfactory operation in various substations of the state.

1.2 The circuit breaker shall conform in all respects to high standards of engineering, design, workmanship and latest revisions of relevant standards at the time of offer and purchaser shall have the power to reject any work or material, which, in his judgement, is not in full accordance therewith.

2.0 STANDARDS

2.1 Except as modified in this specification, the circuit breakers shall conform to the latest revisions with amendments thereof, of following standards.

SL. NO.	STANDARD	TITLE
1.	IEC-62271-100	High Voltage Alternating Current Circuit-Breaker

2.	IS-12729:2004/IEC-60694	Common Specification for High Voltage Control gear & Switchgear standard
3.	IS-14658/IEC-1633	H.V Alternating Current Ckt Breaker-Guide for Short Ckt & Switching Test Procedures for metal enclosed & dead tank Circuit Breaker
4.	IS-14674:1999/IEC-1166:1993	H.V Alternating Current Ckt Breaker-Guide for Seismic qualification of HV A.C Circuit Breaker
5.	IEC-56 / IS-13118	Specification for alternating current circuit breakers
6.	IS-325	Specification for three phase induction motors
7.	IS-375	Marking and arrangement for switchgear bus-bar, main connections and auxiliary wirings.
9.	IS-802 (Part-1)	Code of practice for use of structural steel in overhead trans. Line towers.
10.	IS-2099	High voltage porcelain bushings.
11.	IS-2147	Degree of protection provided for enclosures for low voltage switchgear and control gear.
12.	IS-2629	Recommended practice for hot dip galvanizing of iron and steel.
13.	IS-4379	Identification of the contents of Industrial Gas Cylinders.
14.	IS-7311	Seamless high carbon steel cylinders for permanent and high pressure liquefied gases.

2.2 Equipment meeting with the requirements of any other authoritative standards, which ensures equal or better quality than the standard mentioned above shall also be acceptable. If the equipment offered by the Bidder conforms to other standards, salient points of difference between the standards adopted and the specific standards shall be clearly brought out in relevant schedule. Two copies of such standards with authentic English Translations shall be furnished along with the offer.

2.3 The standards mentioned above are available from:

Reference/Abbreviation	Name and address from which the standards are available
IS	Bureau of Indian Standards, Nanak Bhawan,

	9-Bahadur Shah Zafar Marg, New Delhi-110 001 INDIA
IEC	International Electrotechnical Commission Bureau Central De la Commission Electro Technique International 1,Rue De Verembe Geneva, Switzerland

3.0 AUXILIARY POWER SUPPLY

Auxiliary electrical equipment shall be suitable for operation on the following supply system.

(a)	Power Devices like drive Motors of rating 1 KW and above.	415 V, 3 phase 4 wire 50Hz, neutral grounded AC supply.
(b)	Lighting, space heaters and Fractional KW motors.	240 V, single phase, 50 Hz neutral grounded AC supply.
(c)	Alarm, control and Protective devices.	220 V DC, 2 wire

Each of the foregoing supplies shall be made available by the Purchaser at the terminal point for each circuit breaker for operation of accessories and auxiliary equipment. Supplier's scope include supply of interconnecting cables, terminal boxes etc. The above supply voltage may vary as below and all devices shall be suitable for continuous operation over entire range of voltages.

- i) AC supply : voltage $\pm 10\%$ frequency $\pm 5\%$
 i) DC supply : - 15% to + 10%

4.0 PRINCIPAL PARAMETERS

The breakers shall conform to the specific technical requirements specified hereunder:

Sl. No.	Item	Requirements	
			145 KV
1.	Rated voltage (KV rms) frequency (Hz)	145 50HZ	245/420 KV 50HZ
2.	Continuous current rating (A) rms	3150	3150/3150
3.	Type	Outdoor SF6	
4.	Mounting	Hot dip galvanized lattice steel support structure to be supplied by the Bidder	
5.	Number of Poles	3	
6.	Type of Operation	Gang Operated	Individually Operated Single

			poles.
7.	Phase to phase spacing in the switchyard i.e. interpole spacing for breaker (mm)		2150 4500/7000
8.	Required ground clearance from the lowest live terminal (mm):		
	i.	If both the terminals are not in the same horizontal plane	- 4800/7000
	ii.	If both the terminals are in the same horizontal plane	4600 6500/7000
9.	Height of concrete plinth (to be provided by the Owner) mm.		300 300
10.	Minimum height of the lowest part of the support insulator from ground level (mm)		2550 2550/3500
11.	Operating Mechanism		spring charged (Spring-Spring)
12.	Autoreclosing duty		Single Phase
13.	Rated operating duty cycle		0-0.3 sec-co-3 min-co
14.	First pole to clear factor		1.3(As per IEC-62271-100)
15.	Type of tripping		Trip free
16.	Max. closing time(ms)		60
17.	Max. BREAK TIME (ms)		30 ± 4 50/40
18.	1.2/50 microsecond impulse withstand voltage: (dry)		
	i.	To earth(kvp)	650 1050/1425
	ii.	Across the open contacts with impulse on one terminal and power frequency voltage on opposite terminal (kvp/kv rms)	650 1050/1425(+240)
19.	1 minute power frequency withstand voltage (kv rms) (wet)		275 460/610
20.	Max. radio interference voltage (micro volts) at 1.1 times maximum phase voltage		500 500/<2500 micro mm
21.	Min. corona extinction voltage (kv rms)		105 176/320
22.	Rated breaking current capacity:		
	i.	Line charging at rated voltage at 90 deg. Leading power factor	50 125/600

		(A) rms		
	ii.	Small inductive current (A) rms	-----0.5 to 10----- without switching o/v exceeding 2.3 p.u.	
	iii.	Short circuit current		
	a)	AC component (kA)	40	40/63
	b)	% DC component	25%	40%/as per IEC62271-100
23.	Rated short circuit making current capacity (kA)		79	100/157.5
24.	Permissible limit of temperature rise		As per Clause 5.29	
25.	Max. acceptable difference in the instant of closing/opening of contacts			
	i)	Within a pole (ms)	5	5/2.5
	ii)	Between poles (ms)	10	10/3.3 for opening & 5 for closing
26.	Min. creepage distance of support insulator(mm)		3,625	6,125/10500
27.	Short time current carrying capability for one second (kA)		40	40/63
28.	Rating of auxiliary contacts		----10A at 220 V D.C.----	
29.	Breaking capacity of auxiliary contact		2 A DC with the circuit time constant not less than 20 ms	
30.	Noise level at base and upto 50 metres		-----140 dB (max.)-----	
31.	Seismic acceleration		-----0.3 g -----	

Note:-Purchaser may accept the phase to phase, or phase to earth spacing of the breakers & structure heights basing on the firm's type test reports or he may ask the firm to manufacture the breakers as per the dimensions indicated in this specification. .

5.0 GENERAL TECHNICAL REQUIREMENTS

5.1 Circuit breaker offered shall be sulphur hexafluoride (SF6) type only.

5.2 Any part of the breaker, especially the removable ones, shall be freely interchangeable without the necessity of any modification at site.

5.3 Circuit breaker shall comprise of three identical single pole units. If the circuit breaker not meant for single pole reclosure, these units shall be linked together electrically . Complete circuit breaker with all the necessary items for successful operation shall be supplied, including but not limited to the following:

5.3.1 Breaker assemblies with bases, support structure for circuit breaker as well as for control cabinet, Ladder, central control cabinet and foundation bolts for main structure as well as control cabinet and central control cabinet (except concrete foundations), terminals and operating mechanisms.

- 5.3.2 Compressed SF6 gas, spring operated systems complete including piping, fittings, valves and controls and etc.
- 5.3.3 One central control cabinet for each breaker and one control box for each pole with all the required electrical devices mounted therein and the necessary terminal blocks for termination of interpole wiring. The necessary interpole cabling at site shall be done by the Purchaser based on the schematic, wiring diagram and termination schedule to be supplied by the Supplier.
- 5.3.4 Instruments, pressure gauges and other devices like gas density monitor, temp. monitor & etc. for SF6 gas pressure supervision.
- 5.3.5 All necessary parts to provide a complete and operable circuit breaker installation such as main equipment, terminal, control parts, connectors and other devices, whether specifically called for herein or not.
- 5.4 The circuit breaker shall be designed for high speed single and three pole reclosing with and operating sequence and timing as specified in clause 4.0 "Principal Parameters".
- 5.5 The support structure of circuit breaker as well as that of control cabinet shall be hot dip galvanized. The minimum weight of zinc coating shall be 610 gm/sq.m and minimum thickness of coating shall be 86 microns for all items thicker than 5 mm.
- 5.6 Circuit breaker shall be suitable for hot line washing.
- 5.7 All breakers shall be supplied with terminal connectors. The exact requirement of terminal connectors would be intimated to the supplier during the course of detailed engineering(during drawing approval).
- 5.8 Terminal pads shall have silver plating of atleast 50 microns thickness.

5.9 CONTACTS

- 5.9.1 All making and breaking contacts shall be sealed free from atmospheric effects. Contacts shall be designed to have adequate thermal and current carrying capacity for the duty specified and to have a life expectancy so that frequent replacements due to excessive burning will not be necessary. Provision shall be made for rapid dissipation of heat generated by the arc on opening.
- 5.9.2 Main contacts shall be first to open and the last to close so that there will be little contact burning and wear. If arcing contacts are used they shall be first to close and the last to open. Tips of arcing contacts and main contacts shall be silver plated or made of superior material like graphite.
- 5.9.3 Any device provided for voltage grading to damp oscillations or to prevent restriking prior to the complete interruption of the circuit or to limit over voltages on closing shall have a life expectancy comparable to that of the breaker as a whole.
- 5.9.4 Breakers shall be so designed that when operated within their specified rating, the temperature of each part will be limited to values consistent with a long life or the material used. The temperature shall not exceed that indicated in IEC-56 under specified ambient conditions.

- 5.9.5 Contacts shall be kept permanently under pressure of SF6 gas. The gap between the open contacts shall be such that it can withstand atleast the rated phase to ground voltage continuously at zero gauge pressure of SF6 gas due to its leakage.
- 5.9.6 If multibreak interrupters are used these shall be so designed and augmented that a uniform voltage distribution is developed across them. Calculations/test reports in support of the same shall be furnished along with the bid. The thermal and voltage withstands of the grading elements shall be adequate for the service conditions and duty specified.

5.10 PORCELAIN HOUSING

- 5.10.1 The porcelain housing shall be of single piece construction without any joint or coupling. It shall be made of homogeneous, vitreous porcelain of high mechanical and dielectric strength. Glazing of porcelain shall be uniform brown or dark brown colour with a smooth surface arranged to shed away rain water or condensed water particles (fog). The type and profile of the porcelain insulator sheds shall be in accordance with IEC-815 joints as per IEC-233.

5.11 ADDITIONAL REQUIREMENTS :

- a) The circuit breakers shall be single pressure type, the design and construction of the circuit breaker shall be such that there is minimum possibility of gas leakage and entry of moisture. There should not be any condensation of SF6 gas on the internal insulating surface of the circuit breaker.
- b) All gasketed surfaces shall be smooth, straight and reinforced, if necessary to minimize distortion and to make a tight seal, the operating rod connecting the operating mechanism to the arc chamber (SF6 media) shall have adequate seals, Double O ring seals and test holes for leakage test of the internal seal shall be provided on each static joint.
- c) In the interrupter assembly there shall be an absorbing product box to eliminate SF6 decomposition products and moisture. The material used in the construction of the circuit breakers shall be fully compatible with SF6 gas.
- d) Each pole shall form an enclosure filled with SF6 gas independent of two other poles. The SF6 density of each pole shall be monitored and regulated by individual pressure switches.
- e) The SF6 gas density monitor shall be adequately temp. compensated. The density monitor shall meet the following requirements:
- i) It shall be possible to dismantle the density monitor for checking/replacement without draining the SF6 gas by using suitable interlocked non-return couplings.
- ii) It shall damp the pressure pulsation while filling the gas in service so that the flickering of the pressure switch contacts does not take place.
- iii) A pressure indicator (pressure gauge) shall also be supplied.
- f) Means for pressure relief shall be provided in the gas chamber of circuit breaker to avoid the damages or distortion during occurrence of abnormal pressure increase or shock waves generated by internal electric fault occurs. The position of vents, diaphragms and pressure relief devices shall be so arranged as the minimize danger to the operators in the event of gas or vapour escaping under pressure.
- g) Facility shall also be provided to reduce the gas pressure within the breaker to a value not exceeding 8 millibars within 4 hours or less. Each circuit breaker shall be capable of withstanding this degree of vacuum without distortion or failure of any part.
- h) Sufficient SF6 gas shall be provided to fill all the circuit breakers installed. **In addition to this 20% of the total gas requirement shall be supplied in separate cylinders as spare requirement.**

i) Provisions shall be made for attaching an operation analyzer after installation at site to record contact travel, speed and making measurement of operation timings, pre insertion timing of closing resistor, synchronization of contacts in one pole.

5.12 SULPHUR HEXAFLUORIDE GAS (SF6 GAS) :

- a) The SF6 gas shall comply with IEC-376, 376A and 376B and be suitable in all respects for use in the switchgear under the worst operating conditions.
- b) The high pressure cylinders in which the SF6 gas is shipped and stored at site shall comply with requirements of the following standards and regulations:

IS:4379 Identification of the contents of industrial gas cylinders.

IS: 7311 Seamless high carbon steel cylinders for permanent and high pressure liquifiable gases.

The cylinders shall also meet Indian Boiler regulations.

- c) Test: SF6 gas shall be tested for purity, dew point, break down voltage, water contents as per IEC-376, 376A and 376B and test certificates shall be furnished to owner indicating all the tests as per IEC-376 for each lot of SF6 gas.

5.13 PREINSERTION RESISTOR (PIR) DELETED

5.14 DUTY REQUIREMENTS

5.14.1 The circuit breaker shall be totally restrike free under all duty conditions. Opening resistors shall not be used.

5.14.2 The circuit breaker shall meet the duty requirements for any type of fault or fault location, for line charging and dropping when used on an effectively grounded system and perform make and break operations as per stipulated duty cycles satisfactorily. It shall withstand the maximum expected dynamic loads (including the seismic) to which the circuit breaker may be subjected during its 45 years service life.

5.14.3 The circuit breaker shall be capable of:

- i) Interrupting the steady and transient magnetizing current corresponding to 420 kv/245 KV and 145 KV class transformers of 315 MVA, 100 MVA & 160 MVA ratings respectively.
- ii) Interrupting line charging current as given in clause 4.0, "Principal Parameters" of this specification with a temporary over voltage as high as 1.5 p.u. without restrikes.
- iii) Clearing short line faults (Kilometric faults) with source impedance behind the bus equivalent to symmetrical fault current specified.
- iv) Breaking inductive currents of 0.5 to 10 A without switching overvoltage exceeding 2.3 p.u.
- v) Breaking 25% of the rated fault current at twice rated voltage under phase opposition condition.

5.14.4 The critical current, which gives the longest arc duration at lockout pressure of extinguishing medium and the arc duration shall be indicated.

5.14.5 The breaker shall satisfactorily withstand the high stresses imposed on them during fault clearing, load rejection and re-energisation of lines with trapped charges. The breaker shall ALSO

WITHSTAND THE VOLTAGE SPECIFIED IN CLAUSE 4.0 (Principal Parameters) of this specification.

5.15 TOTAL BREAK TIME

5.15.1 The (Total Break Time) as specified in clause 4.0, (Principal Parameters) of this section shall not be exceeded under any of the following duties:

- i) Test duties 1,2,3,4,5 (with TRV as per IEC-62271-100)/as per related IS.
- ii) Short line fault L90, L75 (with TRV as per IEC-62271-100) /as per related IS.

5.15.2 The Bidder may please note that there is only one specified break time of the breaker which shall not be exceeded under any duty conditions specified such as with the combined variation of the trip coil voltage, (70-110%) spring-spring operation and arc extinguishing medium pressure etc. while furnishing the proof for the total break time of complete circuit breaker, the Bidder may specifically bring out the effect of non-simultaneity between contacts within a pole or between poles and show how it is covered in the guaranteed total break time.

5.15.3 The values guaranteed shall be supported with the type test reports.

5.16 OPERATING MECHANISM AND ASSOCIATED EQUIPMENTS

5.16.1 The circuit breaker shall be designed for electrical local as well as remote control. In addition there shall be provision for local mechanical control (emergency trip).

5.16.2 SPRING OPERATED MECHANISM:

The operating mechanism for 400 KV, 245 KV & 145 KV class breakers shall be of **spring & spring type only** operated by electrical control. The mechanism shall be adequately designed for the specified tripping and re closing duty. The entire operating mechanism control circuitry & etc as required, shall be housed in an outdoor type, with **Aluminium alloy enclosure/ Galvanised M.S (minimum 3mm thickness)**. This enclosure shall conform to the degree of protection IP-55 of IS-2147. The enclosure shall be invariably mounted on a separate concrete plinth. The enclosure shall be painted / powder coated to the Shade no 631 of IS:5 (for aluminium/G.I MS enclosure)

5.16.3 All working parts in the mechanism shall be of corrosion resistant material. All bearings which require greasing, shall be equipped with pressure grease fittings.

5.16.4 The design of the operating mechanism shall be such that it shall be practically maintenance free. The guaranteed years of maintenance free operation, the number of full load and full rated short circuit current breaking/operation without requiring any maintenance or overhauling, shall be clearly stated in the bid. As far as possible the need for lubricating the operating mechanism shall be kept to the minimum and eliminated altogether if possible.

5.16.5 The operating mechanism shall be non-pumping (and trip free) electrically and mechanically under every method of closing. There shall be no rebounds in the mechanism and it shall not require any critical adjustments at site. Operation of the power operated closing device, when the circuit breaker is already closed, shall not cause damage to the circuit breaker or endanger the operator, provision shall be made for attaching an operation analyzer to facilitate testing of breaker at site.

5.16.6 A mechanical indicator shall be provided to show open and close position of the breaker. It shall be located in a position where it will be visible to a man standing on the ground level with the mechanism housing closed. An operation counter shall also be provided in the central control cabinet.

5.16.7 The supplier shall furnish detailed operation and maintenance manual of the mechanism along with the operation manual for the circuit breaker.

5.16.8 The Breaker shall have spare auxiliary switches for Owners use (I.e, for Interlocking,indication,contacts to main and back up relay etc). A minimum of 16 N/O(52a) & 16 N/C (52b) spare auxiliary switch contacts should be provided.

5.17 CONTROL

5.17.1 The close and trip circuits shall be designed to permit use of momentary contact switches and push buttons.

5.17.2 Each breaker pole shall be provided with two (2) independent tripping circuits, valves and coils each connected to a different set of protective relays.

5.17.3 The breaker shall normally be operated by remote electrical control. Electrical tripping shall be performed by shunt trip coils. However, provisions shall be made for local electrical control. For this purpose a local/remote selector switch and close and trip push buttons shall be provided in the breaker central control cabinet. Remote located push buttons and indicating lamps shall be provided by purchaser.

5.17.4 The trip coils shall be suitable for trip circuit supervision. The trip circuit supervision relay would be provided by the purchaser. Necessary terminals shall be provided in the central control cabinet of the circuit breaker by the supplier.

5.17.5 Closing coil shall operate correctly at all values of voltage between 85% and 110% of the rated voltage. Shunt trip shall operate correctly under all operating conditions of the circuit breaker upto the rated breaking capacity of the circuit breaker and at all values of supply voltage between 70% and 110% of rated voltage. However, even at 50% of rated voltage, the breaker shall be able to perform all its duties. If additional elements are introduced in the trip coil circuit their successful operation and reliability for similar applications on outdoor circuit breakers shall be clearly brought out in the additional information schedules. In the absence of adequate details the offer is likely to be rejected.

5.17.6 Suitable relay for monitoring of DC supply voltage to the control cabinet shall be provided. The pressure switches used for interlock purposes shall have adequate contact ratings to be directly used in the closing and tripping circuits. In case the contacts are not adequately rated and multiplying relays are used then the interlock for closing/opening operation of breaker shall be with No logic of the relay i.e. if the DC supply to the interlock circuit fails then operation lockout shall take place.

5.17.7 For all types of operating mechanism a local manual closing device which can be easily operated by one man standing on the ground shall also be provided for maintenance purposes and direction of motion of handle shall be clearly marked.

5.17.8 The auxiliary switch of the breaker shall be preferably positively driven by the breaker operating rod and where due to construction features, same is not possible a plug in device shall be

provided to simulate the opening and closing operations of circuit breaker for the purpose of testing control circuits.

5.18 MOTOR COMPRESSED SPRING CHARGING MECHANISM

Spring operated mechanism shall be complete with motor, **opening spring, closing spring** and all other necessary accessories to make the mechanism a complete unit. Breaker operation shall be independent of motor which shall be used solely for the purpose of charging the closing spring. Motor rating shall be such that it requires only 15 seconds for fully charging the closing spring. Closing operation shall compress the opening spring and keep ready for tripping. The mechanism shall be provided with means for charging the spring by hand. This operation shall be carried out with the doors of the cubicle open. During the process no electrical or mechanical operation of the mechanism shall endanger the operator or damage the equipment. A mechanical indicating device shall be provided to indicate the state of the charge spring and shall be visible with the door of the cubicle closed. An alarm shall be provided for spring failing to be charged within a pre-set time after circuit breaker closing. The spring mechanism shall be fitted with a local manual release, preferably by a push button to avoid inadvertent operation. Means shall be provided for discharging the spring when the circuit breaker is in the open position without circuit breaker attempting to close.

Opening spring and closing spring with limit switches for automotive charging and other necessary accessories to make the mechanism a complete operating unit shall also be provided. As long as power is available to the motor, a continuous sequence of the closing and opening operations shall be possible. The motor shall have adequate thermal rating for this duty.

After failure of power supply to the motor one close open operation shall be possible with the energy contained in the operating mechanism.

Breaker operations shall be independent of the motor which shall be used solely for compressing the closing spring. Facility for manual charging of the closing spring shall also be provided. The motor rating shall be such that it requires not more than 30 seconds for full charging of the closing spring.

Closing action of the breaker shall compress the opening spring ready for tripping.

When closing spring are discharged after closing a breaker, closing spring shall automatically charged for the next operation and an indication of this shall be provided in the local and remote control cabinet.

The spring operating mechanism shall have adequate energy stored in the operating spring to close and latch the circuit breaker against the rated making current also to provide the required energy for the tripping mechanism in case the tripping energy is derived from the operating mechanism.

Provision shall be made to prevent a closing operation of the breaker when the spring is in the partial charged condition. Mechanical interlocking shall be provided in the operating mechanism to prevent discharging of closing spring when the breaker is already in the closed position.

5.18.1 OPERATED MECHANISM FOR 400 KV BREAKER.

The operating mechanism for 420 KV circuit breakers shall also be spring operated mechanism.(Closing spring and opening spring).

5.19 OPERATING MECHANISM HOUSING

The operating mechanism housing/control cabinet shall conform to the requirement specified in clause 5.29. The entire operating mechanism and control mechanism control circuitry & etc as required, shall be housed in an outdoor type, made out of **Aluminium alloy enclosure/ Galvanised M.S (minimum 3mm thickness)** enclosure. This enclosure shall conform to the

degree of protection IP-55 of IS- 2147. The enclosure shall be painted / powder coated to the Shade no 631 of IS:5(for aluminium/GI M.S enclosure)

5.20 INTERLOCKS

It is proposed to electrically interlock the circuit breaker with purchaser's associated air break isolating switches in accordance with switch yard safety interlocking scheme. The details of the scheme will be furnished to the supplier. All accessories required on breaker side for satisfactory operation of the scheme shall be deemed to be included in the scope of supply of this specification.

5.21 SUPPORT STRUCTURE

The supplier shall indicate the price of support structure along with the foundation bolts required separately in the bid proposal sheets and these shall be considered in evaluation. Purchaser reserves the right to procure these from the supplier or through separate contract. However, in case the equipment offered have integral support structure or the specialties of the breaker are such that support structures have to be provided by the supplier, the prices of these support structure shall be included in the price of the equipment and same shall be indicated clearly in the bid proposal sheet. The support structure shall meet the following requirements:

- 1) The minimum vertical clearance from any energized metal part to the bottom of the circuit breaker (structure) base, where it rests on the foundation pad, shall be minimum 8 mtrs for 400 KV, 5.5 mtrs for 245KV & 4.6 mtrs for 145 KV.
- 2) The minimum vertical distance from the bottom of the lowest porcelain part of the bushings, porcelain enclosures or supporting insulators to the bottom of the circuit breaker base, where it rests on the foundation pad shall be 2.55 mtrs. for all voltages.
- 3) The minimum clearance between the live parts and earth shall be 3.5 mtrs for 400 KV, 2.4 mtrs for 245 KV and 1.5 meters for 145 KV.

5.22 FITTINGS AND ACCESSORIES

5.22.1 Following is a partial list of some of the major fittings and accessories to be furnished by supplier in the central control cabinet. Number and exact locations of these parts shall be indicated in the bid.

- a) Central control cabinet in accordance with clause no. 5.29 complete with
 - i) Cable glands.
 - ii) Local/remote changeover switch.
 - iii) Operation counter.
 - iv) SF6 pressure gauges.
 - v) Control switches to cut off control power supply.
 - vi) Fuses as required.
 - vii) The number of terminals provided shall be adequate enough to wire out all contacts and control circuits plus 24 terminals spare for owner's use.

All the terminal blocks to be used in the operating mechanism and control cubicle should be provided with 1100V grade stud type terminal block of Polyamide material. (OAT-6 for non-disconnecting type and OAT 6T for disconnecting type of Elmex) / Connectwell (Equivalent). At least 20% spare terminals shall be provided.

- b) Anti-pumping relay.
- c) Rating and diagram plate in accordance with IEC / IS incorporating year of manufacture.

5.23 PAINING, GALVANISING AND CLIMATE PROOFING

5.23.1 All interiors and exteriors of tanks and other metal parts shall be thoroughly cleaned to remove all rust, scales, corrosion, greases or other adhering foreign matter and the surfaces treated by phosphating (e.g. seven tank phosphating sequence). All steel surfaces in contact with insulating oil, as far as accessible, shall be painted with not less than two coats of heat resistant, oil insoluble, insulating paint.

5.23.2 All metal surfaces exposed to atmosphere shall be given, in addition to the treatment described in clause 5.23 two primer coats of zinc chromate and two coats of epoxy paint with epoxy base thinner. All metal parts not accessible for painting shall be made of corrosion resisting material. All machine finished or bright surfaces shall be coated with a suitable preventive compound and suitably wrapped or otherwise protected. All paints shall be carefully selected to withstand tropical heat and extremes of weather within the limits specified. The paint shall not scale off or wrinkle or be removed by abrasion due to normal handling. All external paintings shall be as per shade no. 697 of IS:5.

5.23.3 Paint inside the metallic housing shall be of anti-condensation type and the paint on outside surfaces shall be suitable for outdoor installation.

5.23.4 All components shall be given adequate treatment of climate proofing as per IS:3202 so as to withstand corrosive and serve service conditions.

5.24 GALVANISING

All ferrous parts including all sizes of nuts, bolts, support channels, structures, etc. as also the mechanism housing shall be hot dip galvanized conforming to latest version of IS:2629. Spring washers shall be electro galvanized.

5.25 EARTHING

The operating mechanism housing, control cabinets, dead tanks, support structure etc. shall be provided with two separate earthing terminals suitable for bolted connection to 50X8 mm mild steel flat to be provided by the Purchaser for connection to station earth mat.

5.26 NAME AND RATING PLATES:

Circuit breaker and its operating device shall be provided with a rating plate or plates marked with but not limited to following data:

- a) Manufacturer's name or trade mark.
- b) Serial Number or type designation making it possible to get all the relevant information from the manufacturer.
- c) Year of manufacture.
- d) Rated voltage.

- e) Rated insulation level.
- f) Rated frequency.
- g) Rated normal current.
- h) Rated short circuit breaking current.
- i) First pole to clear factor.
- j) Rated duration of short circuit.
- k) Rated auxiliary D.C. supply voltage of closing and opening devices.
- l) Rated pressure of compressed air gas for operation and interruption.
- m) Rated out of phase breaking current.
- n) Rated supply voltage of auxiliary circuits.
- o) Rated supply frequency of auxiliary circuits.
- p) Number of closing & Tripping coils
- q) Opening time & closing time

Other informations are as per IS 12729/IEC 60694 .

The coils of operating devices shall have a reference mark permitting the data to be obtained from the manufacturer.

The rating plate shall be visible in position of normal service and installation. The rating plate shall be weather proof and corrosion proof.

5.27 LIMITS OF TEMPERATURE RISE

The temperature rise on any part of equipment shall not exceed the maximum temperature rise specified below under the conditions specified in test clauses. The permissible temperature rise indicated is for a maximum ambient temperature of 50 deg. C. If the maximum ambient temperature rises, permissible values shall be reduced accordingly.

Sl. No.	Nature of the part or of the liquid	Maximum Value of	
		Temp.	Temp. rise at a max. ambient air temp. not exceeding 50 deg. C.
1.	Contacts in air, silver-faced copper, copper alloy or aluminium alloy [see notes (i) and (ii)]	105	55
	Bare copper or tinned aluminium alloy.	75	25
2.	Contacts in oil: Silver-faced copper, copper alloy or aluminium alloy (see note ii)	90	40
	Bare copper or tinned aluminium alloy	80	30
3.	Terminals to be connected to external conductors by screws or bolts silver faced (see note iii)	105	55
4.	Metal parts acting as springs	See Note iv	See note iv
5.	Metal parts in contact with insulation of the following classes:		
	Class Y: (for non-impregnated materials)	90	40

	Class A: (for materials immersed in oil or impregnated)	100	50
	Class E: in air	120	70
	in oil	100	50
	Class B: in air	130	80
	in oil	100	50
	Class F: in air	155	105
	in oil	100	50
	Enamel: Oil base	100	50
	Synthetic, in air	120	70
	Synthetic, in oil	100	50
6.	Any part of metal or of insulating material in contact with oil, except contacts	100	50
7.	Oil	90	40

Notes: (i) When applying the temperature rise of 55 deg. C, care should be taken to ensure that no damage is caused to the surrounding insulating materials.

- (ii)** The quality of the silver facing shall be such that a layer of silver remains at the points of contact after the mechanical endurance test. Otherwise, the contacts shall be regarded as öbareö.
- (iii)** The values of temperature and temperature rise are valid whether or not the conductor connected to the terminals is silver-faced.
- (iv)** The temperature shall not reach a value whether the elasticity of the material is impaired. For pure copper, this implies a temperature limit of 80 deg. C.

5.28 TERMINAL CONNECTORS

5.28.1 The terminal connectors shall meet the following requirements:

- a) Terminal connectors shall be manufactured and tested as per IS: 5561.
- b) All castings shall be free from blow holes, surface blisters, cracks and cavities. All sharp edges and corners shall be blurred and rounded off.
- c) No part of a clamp shall be less than 10 mm thick.
- d) All ferrous parts shall be hot dip galvanized conforming to IS: 2633.
- e) For bimetallic connectors, copper alloy liner of minimum thickness of 2 mm shall be cast integral with aluminium body.
- f) Flexible connectors shall be made from tinned copper.
- g) All current carrying parts shall be designed and manufactured to have minimum contact resistance.
- h) Connectors shall be designed to be corona free in accordance with the requirements stipulated in IS: 5561.

5.29 SPECIFICATION FOR CONTROL CABINETS:

1. Control cabinets shall be of the free standing floor mounting type.

2. Control cabinet of the operating mechanism shall be made out of **Aluminium alloy enclosure/ Galvanised M.S (minimum 3mm thickness). The operating mechanism shall be strong,rigid & not subject to rebound.** Hinged door shall be provided with padlocking arrangement. Sloping rain hood shall be provided to cover all sides. 15 mm thick neoprene or better type of gaskets shall be provided to ensure degree of protection of at least IP55 as per IS: 2147. The control cabinet enclosure shall be painted / powder coated to the Shade no 631 of IS:5(for aluminium/G.I M.S enclosure).
3. Bus bars shall be of tinned copper of adequate cross-section to carry the normal current, without exceeding the permissible temperature rise over an ambient temperature of 50 deg. C outside the cubicle. The buses shall be braced to withstand forces corresponding to short circuit current of 25 KA.
4. Motors rated 1 kw and above being controlled from the control cabinet would be suitable for operation on a 415 V, 3 phase 50 Hz system. Fractional KW motors would be suitable for operation on a 240 V, 1-phase, 50 Hz supply system.
5. Isolating switches (MCBs) shall be group operated units (3 pole for use on 3-phase supply systems and 2 pole for single phase supply systems) quick make quick break type, capable of breaking safely and without deterioration, the rated current of the associated circuit. Switch handle shall have provision for locking in both fully open and fully closed positions.
6. Push buttons shall be rated for not less than 6 Amps, 415 V A.C. or 2 Amps, 220 V D.C. and shall be flush mounted on the cabinet door and provided with appropriate name plates. Red, Green and Amber indicating lamps shall be flush mounted.
7. For motors up to 5 KW, contactors shall be direct-on-line, air break, single throw type and shall be suitable for making and breaking the stalled current of the associated motor which shall be assumed equal to 6.5 times the full load current of the motor at 0.2 p.f. For motors above 5 KW, automatic star delta type starters shall be provided. 3 pole contactors shall be furnished for 3 phase motors and 2-pole contactors for single phase motors. Reversing contactors shall be provided with electrical interlocks between forward and reverse contactors. If possible, mechanical interlocks shall also be provided. Contactors shall be suitable for uninterrupted duty and shall be of duty category class AC4 as defined in IS: 2959. The main contacts of the contactors shall be silver plated and the insulation class for the coils shall be class E or better. The dropout voltage of the contactors shall not exceed 70% of the rated voltage.
8. Contactors shall be provided with a three element, positive acting, ambient temperature compensated, time lagged, hand reset type thermal overload relay with adjustable setting, hand reset button shall be flush with the front door of the cabinet and suitable for resetting with starter compartment door closed.
9. Single phasing preventer relay shall be provided for 3 phase motors to provide positive protection against single phasing.
10. Mini starters shall be provided with no volt coils whenever required.
11. Purchaser's power cables will be of 1100 volts grade stranded aluminium conductor. PVC insulated, PVC sheathed single steel wire armoured and PVC jacketed. All necessary cable terminating accessories such as glands, crimp type tinned copper lugs etc. for power as well as control cables shall be included in supplier's scope of supply. Suitable brass cable glands shall be provided for cable entry.

12. Wiring for all control circuits shall be carried out with 1100 volts grade PVC insulated tinned copper stranded conductors of sizes not smaller than 2.5 sq. mm. Atleast 10% spare terminal blocks for control wire terminations shall be provided on each panel. The terminal blocks shall be of non-disconnecting stud type. All terminals shall be provided with ferrules indelibly marked or numbered and these identifications shall correspond to the designations on the relevant wiring diagrams. The terminals shall be rated for adequate capacity which shall not be less than 10 Amps.
13. Separate terminal blocks shall be provided for terminating circuits of various voltage classes. CT loads shall be terminated on a separate block and shall have provision for short circuiting the CT secondary terminals.
14. Control cabinet shall be provided with 240 V, 1-phase 50 Hz, 20 W CFL TUBE light fixture and a suitably rated 240 V, 1-phase, 5 amps, 3 pin socket for hand lamps.
15. Strip heaters shall be provided inside each cabinet complete with thermostat (preferably differential type) to prevent moisture condensation. Heaters shall be controlled by suitably rated double pole miniature Circuit Breakers.
16. Signal lamps provided shall be of neon screw type with series resistors, enclosed in bakelite body. Each signal lamp shall be provided with a fuse integrally mounted in the lamp body.
17. Electric measuring instruments shall be of moving iron type. Ammeters for measuring current upto 30 Amps shall be directly connected while those for measuring above 30 Amps shall be connected through suitable CBs. Ammeters shall be provided with selector switches.
18. Items inside the cabinet made of material shall be coated with a fungus resistant varnish.

5.30 MOTORS :(UNIVERSAL MOTOR)

Motors shall be universal type suitable for operation in AC & DC supply, as per IS:325 of sufficient size capable of satisfactory operation for the application and duty as required for the driven equipment.

6.1.1 TESTS

Type Tests

All the equipments offered shall be fully type tested as per the relevant standards(**IEC-62271-100,IEC-60694/IS-12729** with latest amendments) & **tests as indicated below. The bids offering equipments not type tested will be rejected.** In case, the equipment of the type & design offered has already been type tested, the bidder shall furnish four sets of the type test reports along with the offer. **The test must have been conducted not latter than five years from the date of opening of the bids.** The purchaser reserves the right to demand repetition of some or all the type & additional type tests in the presence of his representative. For this purpose, the bidder may quote unit rates for carrying out such type tests. For any change in the design/type already type tested the design/type offered against this specification, the purchaser reserves the right to demand repetition of tests without any extra cost or reject the bid without any intimation.

Type Tests:--(As per IEC-62271-100 with latest amendments)

- 1) Dielectric Test(LI Voltage,PF Voltage Withstand(Dry&Wet)& etc)

- 2) RIV Test
- 3) Measurement of resistance of the main circuit
- 4) Temperature rise Test
- 5) Short Time withstand current & Peak withstand current Test
- 6) Tightness Test
- 7) Mechanical Operation Test, Mechanical endurance test
- 8) Short Circuit making & Breaking Test
- 9) Capacitive Current, Switching Test , Line charging current breaking Test
- 10) Test to verify degree of protection
- 11) EMC Test

Routine Tests:-

- 1) Dielectric Tests on the main Circuit ,auxiliary & control circuits
- 2) Measurement of resistance of the main circuit.
- 3) Tightness Test
- 4) Design & Visual Checks
- 5) Mechanical operation Test
- 6) Operating time of the device, motor Characteristics, measurement of coil current & resistance , Sf6 gas pressure monitoring , control Circuit , antipumping, dimensions,nameplate details , contact travel & timing checks .

The following additional type tests are proposed to be conducted. The type test charges for these tests shall be quoted along with other type tests(AS indicated above) as per IEC/ IS in the relevant schedule & the same shall be indicated in the total bid price.

- 1) Corona extinction voltage Test(As per Annexure-I)
- 2) Out of phase closing test as per IEC
- 3) Line charging breaking current test
- 4) Seismic Withstand test in unpressurised condition(as per Annexure-I)

6.1.2 The prices quoted by the bidder towards conductance of type tests & additional type tests shall be taken in to consideration for bid evaluation.

6.2 TYPE, ACCEPTANCE AND ROUTINE TESTS

6.2.1 All acceptance and routine tests as stipulated in IEC-62271-100,IEC-60694/IS-12729, IS 13118 with its latest amendments & routine tests as indicated above shall be carried out by the supplier in the presence of purchaser's representative. Also type test on one unit may be carried out by the supplier in the presence of purchaser's representative if purchaser decides & if such facility will be available either in the manufacturer's laboratory or in the CPRI. Rates for these tests must be indicated in the Annexure-IV, V, of Section-III of this tender specification. If the manufacturer wants to do the above tests in free of cost, then he may indicate the rates as -NIL. Purchaser reserves the right to conduct type test or may not insist for this test.

6.2.2 In addition to the mechanical and electrical tests specified by IEC, the following shall also be performed.

Speed curves for each breaker shall be obtained with the help of a suitable operation analyzer to determine the breaker contact movement during opening, closing, auto-reclosing and trip free operation under normal as well as limiting operating conditions (control voltage, pressure etc.). The tests shall show the speed of contacts directly at various stages of operation, travel of contacts, opening time,

closing time, shortest time between separation and meeting of contacts at break/make operation etc. This test shall also be performed at site for which the necessary operation analyzer along with necessary transducers, cables, console, etc. shall be furnished as mandatory maintenance equipment.

6.2.3 Immediately after finalization of the programme of type/acceptance/routine testing, the supplier shall give sufficient advance intimation (20 days) to the purchaser to enable him to depute his representative for witnessing the tests.

6.3 ADDITIONAL TESTS

The purchaser reserves the right for carrying out any other tests of a reasonable nature at the works of the supplier/laboratory or at any other recognized laboratory/research institute in addition to the above mentioned type, acceptance and routine tests at the cost of the purchaser to satisfy that the material complies with the intent of this specification.

7.0 INSPECTION

7.1 The inspection may be carried out by the purchaser at any stage of manufacture. The supplier shall grant free access to purchaser's representative at a reasonable time when the work is in progress. Inspection and acceptance of any equipment under this specification by the purchaser shall not relieve the supplier of his obligation of furnishing equipment in accordance with the specification and shall not prevent subsequent rejection if the equipment is found to be defective.

The supplier shall keep the purchaser informed in advance, about the manufacturing programme so that arrangement can be made for inspection. Before offering for inspection, the supplier shall furnish shop routine test certificates and calibration reports of the equipments/instruments to be used during testing. After acceptance of these calibration reports and shop routine test certificate, inspecting officer of the purchaser will be deputed for witnessing such inspections.

7.2 The purchaser reserves the right to insist for witnessing the acceptance/routine testing of the bought out items.

7.3 No material shall be dispatched from its point of manufacture unless the material has been satisfactorily inspected and tested or unless the same is waived by the purchaser in writing.

8.0 QUALITY ASSURANCE PLAN:

The bidder shall invariably furnish following information along with his offer, failing which his offer, shall be liable for rejection.

i) Statement giving list of important raw materials including but not limited to:

- (a) Contact Material
- (b) Insulation
- (c) Porcelain
- (d) Oil
- (e) Sealing material
- (f) Contactor, limit switches, etc. in control cabinet.

Names of sub-suppliers for the raw materials, list of standards according to which the raw materials are tested, list of test normally carried out on raw materials in presence of Bidder's representative, copies of test certificates.

ii) Information and copies of test certificates as in (i) above in respect of bought out accessories.

Iii) List of areas in manufacturing process, where stage inspections are normally carried out for quality control and details of such tests and inspections.

iv) Special features provided in the equipment to make it maintenance free.

vi) List of testing equipment available with the Bidder for final testing of breakers vis-à-vis, the type, special, acceptance and routine tests specified in the relevant standards. These limitations shall be very clearly brought out in the relevant schedule i.e. schedule of deviations from specified test requirements.

Vii) The supplier shall, within 30 days of placement of order, submit following information to the purchaser.

- 1) List of raw materials as well bought out accessories and the names of sub-suppliers selected from those furnished along with offer.
- 2) Type test certificates of the raw material and bought out accessories.
- 3) Quality assurance plan (QAP) with hold points for purchaser's inspection (if purchaser will desires).

The supplier shall submit the routine test certificates of bought out items and raw material, at the time of routine testing of the fully assembling breaker

9 .0 DOCUMENTATION

9.1 All drawings shall conform to relevant International Standards Organization (ISO) Specification/ISS. All drawings shall be in ink and suitable for micro filming. All dimensions and data shall be in S.I. Units.

9.2 List of Drawings and Documents:

The Bidder shall furnish four sets of relevant descriptive and illustrative published literature pamphlets and the following drawings/documents for preliminary study along with the offer.

- a) General outline drawings showing dimensions and shipping weights, quantity of insulating media, air receiver capacity etc.
- b) Sectional views showing the general constructional features of the circuit breaker including operating mechanism, arcing chambers, contacts with lifting dimensions for maintenance.
- c) Schematic diagrams of breaker offered for control supervision and reclosing.
- d) Structural drawing, design calculations and loading data for support structures.
- e) Foundation drilling plan and loading data for foundation design.

f) Type test reports .

9.3 The supplier shall, within 2 weeks of placement of order submit four sets of final version of all the above drawings for purchaser's approval. The purchaser shall communicate his comments/approval on the drawings to the supplier within reasonable period. The supplier shall, if necessary, modify the drawings and resubmit four copies of the modified drawings for purchaser's approval within two weeks from the date of comments. After receipt of purchaser's approval, the supplier shall, within three weeks, submit 15 prints and one good quality reproducibles of the approved drawings for purchaser's use.

9.4 The supplier shall also furnish fifteen copies of manuals covering erection, commissioning, operation and maintenance instructions and all relevant information and approved drawings pertaining to the main equipment as well as auxiliary devices. Marked erection drawings shall identify the component parts of the equipment as shipped to enable purchaser to carry out erection with his own personnel. Each manual shall also contain one set of all the approved drawings, type test reports as well as acceptance reports of the corresponding consignment dispatched.

9.5 The manufacturing of the equipment shall be strictly in accordance with the approved drawings and no deviation shall be permitted without the written approval of the purchaser. All manufacturing and fabrication work in connection with the equipment prior to the approval of the drawing shall be at the supplier risk.

9.6 TEST REPORTS

- i) Four copies of acceptance test reports and type test reports shall be furnished to the purchaser as per the inspection of testing. One copy will be returned, duly certified by the purchaser and only there after wards shall the material be dispatched.
- ii) All records of routine test reports shall be maintained by the supplier at his works for periodic inspection by the purchaser.
- iii) All test reports of tests conducted during manufacture shall be maintained by the supplier. These shall be produced for verification as and when requested for by the purchaser.

10 .0 PACKING AND FORWARDING

The equipment shall be packed in suitable crates so as to withstand handling during transit. The supplier shall be responsible for any damage to the equipment during transit, due to improper and inadequate packing and handling. The easily damageable materials shall be carefully packed and marked with the appropriate caution symbols. Wherever necessary, proper arrangement for lifting such as lifting hooks etc. shall be provided. Any material found short inside the packing cases shall be supplied by the supplier without any extra cost.

Each consignment shall be accompanied by a detailed packing list containing the following information:

- a) Name of the consignee.
- b) Details of consignment.
- c) Destination.

- d) Total weight of consignment.
- e) Sign showing upper / lower side of the crate.
- f) Handling and unpacking instructions.
- g) Bill of material indicating contents of each package and spare material.
- h) Manuals containing approved drawings & test reports

The supplier shall ensure that the packing list and bill of material are to be supplied in advance to the purchaser & to the consignees before dispatch.

11.0 SUPERVISION OF ERECTION, TESTING AND COMMISSIONING (ET&C)

The erection, testing and commissioning of the breakers shall be supervised, by trained personnel (Engineer) of the supplier who shall direct the sequence of ET&C and make the necessary adjustments to the apparatus and correct in the field any errors or omissions in order to make the equipment and material properly perform in accordance with the intent of this specification. The Engineer shall also instruct fully (up to the satisfaction) to the plant operators, in the operation and maintenance of equipment furnished. The supplier shall be responsible for any damage to the equipment, on commissioning the same, if such damage results from faulty or improper ET&C procedure. Purchaser shall provide adequate number of skilled/semi-skilled workers as well as all ordinary tools and equipment and cranes required for breaker erection, at his own expense. Apart from the above, the purchaser shall not be responsible for any other expenses incurred by the supplier and against personal injuries to the Engineer etc., shall be to supplier's account. Special tools, if required for erection and commissioning shall be arranged by the supplier at his cost and on commissioning these shall be supplied to the purchaser, free of cost, for future use.

12.0 QUANTITY AND DELIVERY REQUIREMENTS

- i) The scope of supply shall include a supply of 25% extra-quantity of bolts, nuts, washers, split pins, cotter pins and such other small loose items free of cost.

SCHEDULE A

TECHNICAL PARTICULARS AND GUARANTEES

1. Topographical and Meteorological site conditions

Location		State of Orissa
Altitude	m	1000
Air Temperatures		

Minimum	°C	0
Maximum	°C	55
maximum daily average	°C	32
Humidity variation	per cent	100
Pollution level to IEC 815		Heavy
Airborne contamination, if any		Highly polluted
Isoceraunic level	day/annum	70
Seismic withstand factor (all equipment)	g	0.3
Maximum wind pressure	kg/sq. m	80.84
Wind velocity - (Wind Zone to IS 875)	m/sec	50
Average annual rain fall	cm	150

1	SYSTEM DETAILS	kV	400	220	132
1.1	Rated system voltage	kV	420	245	145
1.2	Earthing of system neutral		solid	solid	solid
1.3	System frequency	Hz	50	50	50
2	INSULATION LEVEL (at site altitude)				
2.1	Lightning impulse voltage withstand level, positive and negative polarity	kVp	1425	1050	650
2.2	Switching impulse voltage withstand level of insulation to ground, positive and negative polarity				
	dry	kVp	1050	-	-
	wet	kVp	1050	-	-
2.3	Power frequency withstand voltage				
	dry	kV	520	460	275
	wet	kV	520	460	275
2.4	Voltage below which corona shall not be visible	kV	320	176	105
2.5•	Maximum radio interference voltage level measured at 1.1 times $U_s/\sqrt{3}$ at 1 MHz	μV	<1000	<500	<500
2.6••	Minimum creepage to earth over insulation on rated service voltage (to				

IEC 815)	mm/kV	25	25	25
----------	-------	----	----	----

- **Us is rated system voltage**
- **Creepage distance across interrupter chambers shall be at least 10 percent greater than the creepage distance to earth and shall comply with the pollution conditions of IEC 815.**

2. - SWITCHGEAR DETAILS

Item No	Description	Particulars			
		kV	420	245	145
1	TYPE OF SWITCHGEAR				
1.1	Type of switchgear GIS or Open terminal			Open terminal	
1.2	Installation Outdoor	Outdoor	Outdoor	Outdoor	
2	SHORT TIME CURRENT CAPACITY				
2.1	All equipment 3 seconds	kA	63	40	40
2.2	Maintenance earthing devices, 3 seconds	kA	63	40	40
3	CIRCUIT BREAKER				
3.1	Normal current rating	A	3150	3150	3150
3.2	Fault rating				
'3.2.1	Making current	kAp	157.5	100	100
'3.2.2	Breaking current (symmetrical)	kA	63	40	40
'3.2.3	Breaking current (asymmetrical)	% DC/kAp	IEC 56 <50%	IEC 56 <50%	IEC 56 <50%
'3.2.4	Breaking current under out of phase conditions	kA	10	10	10
'3.2.5	Rated line charging current	A	600	125 as per IEC	50 as per IEC
'3.2.6	Rated cable charging current	A	600	250 as per IEC	160 as per IEC
'3.2.7	Rated inductive current	A	1 to 10 - 50 - 100 ó 200		
'3.2.8	Maximum overvoltage factor on any switching duty	pu	<2.0	<2.0	<2.0
3.3	Operating sequence				
'3.3.1	Normal		0-0.3 s - CO-3 min ó CO		

Item No	Description	Particulars			
'3.3.2	Auto reclosing	0-0.3 s - CO-3 min ó CO			
'3.3.3	Delayed three phase auto reclose cycle adjustable dead time range	s	2-30	2-30	2-30
'3.3.4	High speed single phase auto reclose cycle adjustable dead time	kV	420	245	145
'3.3.5	Number of closing operations under out of synchronous conditions	s	0.3-20	0.3-20	-
3.4	Transient recovery voltage	(2.0 pu)	2	2	2
'3.4.1	First phase to clear factor		1.3	1.3	1.5
'3.4.2	Recovery voltage parameter for 3 phase unearthed terminal fault		IEC 56	IEC 56	IEC 56
'3.4.3	Short line fault parameter		IEC 56	IEC 56	IEC 56
'3.4.4	Surge impedance for short line fault test	ohms	450	450	450
'3.4.5	Minimum voltage to earth when switching capacitive currents, (1.4 times rated phase to earth voltage)	kV	340	198	117
'3.4.6	Voltage across circuit breaker under out of phase switching conditions	pu	2	2	2
3.5	Electro mechanical performance				
'3.5.1	Maximum total break time throughout complete rating, ie trip coil initiation to final arc extinction	ms	40	50	50
'3.5.2	Maximum time interval between closure of first and last phase of three phase circuit breakers	ms	2	1	1
'3.5.3	Maximum time interval between closure of interrupters of one phase of the circuit breaker	ms	1	-	-
'3.5.4	Maximum time interval between opening of first and last phase of three phase circuit breaker	ms	3.3	3.3	3.3
'3.5.5	Maximum time interval between opening of interrupters of one phase of the circuit breaker	ms	1	-	-
		kV	420	245	145

Item No	Description	Particulars			
4	Insulation level (IEC 694)				
41 *	Lightning impulse withstand (1.2/50 wave) - positive and negative				
	a. To earth, closed contacts				
	b. Across, open contacts	kVp	1425	1050	650
		kVp	-	1200	750
		kVp + kVACp	1425 +(240)	-	-
4.2*+	Switching impulse withstand (250/ 2500 wave) - positive and negative				
	c. To earth, closed contacts	kVp	1050	-	-
	d. Across, open contacts	kVp	1050	-	-
		kVp + kVACp	900 +(345)	-	-
4.3	Power frequency withstand	Dry/wet			
	e. To earth, closed contacts - 1 minute	kV	520	460	275
	f. Across, open contacts - 1 minute	kV	610	530	315
4.4	Ancillary equipment				
4.5	Number of trip coils required		2	2	2
4.6	Number of closing coils required		1	1	1
4.7	Degree of protection		IP 55	IP 55	IP 55

* Biased tests (Impulse + ACp), required on switchgear for 300 kV and above.

+ Wet tests are required on outdoor open-terminal switchgear.

TABLE 1. - 420KV CIRCUIT BREAKERS

(A) TERMINAL FAULT REQUIREMENTS - FOUR PARAMETER TRV

Fault duty	Current kA (rms)	First test voltage U1 (kV)	Time co-ord t1 (µs)	TRV peak value Uc (kV)	Time co-ordt2 (µs)	Time delay td (µs)	Volt co-ord u' (kV)	Time co-ord t' (µs)	Rate of rise U'/t kV (kV/µs)
10% symmetrical	5	-	-	787	88	11	262	4	8.9
30% symmetrical	15	446	89	669	668	5(22)	223	50(67)	5.0
60% symmetrical	30	446	149	669	671	2(37)	223	76(111)	3.0
100% symmetrical	50	446	223	624	669	2	223	113	2.0
100% Asym.	**	446	223	624	669	2	223	113	2.0
Asynchronous	12.5	686	446	857	1338	-	-	-	-
100% closing	125	-	-	-	-	-	-	-	-

** Dependent on circuit breaker opening time

*** 100% Sym and Assym duties shall either include ITRVs of Table III of IEC 56 or the SLF duties have been performed with $t_{dL} = 0$

(B) SHORT LINE FAULT REQUIREMENTS

Source side	50	343	171	480	513	2	171	88	2.0
				U_L	t_L	t_{dL}			U_L/t_L
Line side L90	45	-	-	54.9	6.1	0.5	-	-	9
Line side L75	37.5	-	-	137.3	18.4	0.5	-	-	7.46
Line side L 60	30	-	-	219	36.5	0.5	-	-	6

TABLE 2 - 245 kV CIRCUIT BREAKERS

(A) TERMINAL FAULT REQUIREMENTS - FOUR PARAMETER TRV

	Current	First test voltage	Time co-ord	TRV peak value	Time co-ordt2	Time delay	Volt co-ord	Time co-ord	Rate of rise U'/t kV
--	---------	-----------------------	----------------	-------------------	------------------	------------	-------------	----------------	-------------------------

Fault duty	kA (rms)	U1 (kV)	t1 (µs)	Uc (Kv)	(µs)	td (µs)	u' (kV)	t' (µs)	(kV/µs)
10% symmetrical	5	-	-	459	66	8	153	30	7.0
30% symmetrical	15	300	60	450	450	5(15)	150	35(45)	5.0
60% symmetrical	30	260	87	390	392	2(22)	130	45(65)	3.0
100% symmetrical	50	260	130	364	390	2	130	67	2.0
100% asymmetrical	**	260	130	364	390	2	130	67	2.0
Asynchronous	12.5	400	260	500	780	-	-	-	1.54
100% closing	125	-	-	-	-	-	-	-	-

** Dependent on circuit breaker opening time

*** 100% Sym and Assym duties shall either include ITRVs of Table III of IEC 56 or the SLF duties have been performed with $t_{dL} = 0$

(B) SHORT LINE FAULT REQUIREMENTS

Source side	50	200	100	280	300	2	100	52	2.0
				U_L	t_L	t_{dL}			U_L/t_L
Line side L 90	45			32	3.6	0.5	-	-	8.9
Line side L 75	37.5			80	10.6	0.5	-	-	7.55
Line side L 60	30			128	21.3	0.5	-	-	6

**TABLE 3 - 145 kV CIRCUIT BREAKERS
(A) TERMINAL FAULT REQUIREMENTS - FOUR PARAMETER TRV**

Fault duty	Current kA (rms)	First test voltage U1 (kV)	Time co-ord t1 (µs)	TRV peak value Uc (kV)	Time co-ordt2 (µs)	Time delay td (µs)	Volt co-ord u' (kV)	Time co-ord t' (µs)	Rate of rise U'/t kV (kV/µs)
10% symmetrical	4	-	-	272	45	6	91	21	6.0

30% symmetrical	12	178	36	266	270	5(9)	89	23(27)	5.0
60% symmetrical	24	178	59	266	266	2(15)	89	32(44)	3.0
100% symmetrical	40	178	89	249	267	2	89	46	2.0
100% asymmetrical	**	178	89	249	267	2	89	46	2.0
Asynchronous	10	296	178	370	534	-	-	-	1.67
100% closing	100	-	-	-	-	-	-	-	-

** Dependent on circuit breaker opening time

*** 100% Sym and Assym duties shall either include ITRVs of Table III of IEC 56 or the SLF duties have been performed with $t_{dL} = 0$

(B) SHORT LINE FAULT REQUIREMENTS

Source side	40	118	59	166	177	2	59	32	2.0
				U_L	t_L	t_{dL}			U_L/t_L
Line side L90	36	-	-	18.9	2.6	0.2	-	-	7.3
Line side L75	30	-	-	47.4	7.9	0.2	-	-	6.0
Line side L60	24	-	-	75.9	15.8	0.2	-	-	4.8
Item No	Description			Particulars					
			kV	420	245	145			

Source side	40	118	59	166	177	2	59	32	2.0
1	MINIMUM FACTORS OF SAFETY FOR SWITCHGEAR								
1.1	Complete insulators based on electro-mechanical test			2.5	2.5	2.5			
1.2	Insulator metal fittings based on elastic limit			2.5	2.5	2.5			
1.3	Steel structures based on elastic limit of tension members and on crippling loads of compression members			2.5	2.5	2.5			
1.4	Foundations for structures against overturning or uprooting under maximum simultaneous working loadings			2.5	2.5	2.5			

8. CLEARANCES*

8.1 Clearances for busbars and connections

RATED SYSTEM VOLTAGE kV					
		36	145	245	420
BIL	kVpK	170	650	1050	1425
SIL	kVpK	-	-	-	1050
Minimum Clearance between Live metal and Earth	m	0.32	1.3	2.0	3.4
Minimum Clearance between Live metal of Different Phases	m	0.43	1.5	2.4	3.9
Safety Working Clearance Horizontal	m	2.3	3.2	3.3	5.4
Safety Working Clearance Vertical	m	2.9	3.7	4.5	6.4
Minimum height to base of insulation	m	2.4	2.4	2.6	2.7

* Based on BS 7354: 1990

Clearances apply only to equipment not subject to impulse voltage type tests.

They apply to conditions of maximum conductor swing and sag.

Item	Description	Particulars
9	FINISH OF EQUIPMENT	
9.1	Outdoor equipment	Outdoor Outdoor Outdoor r
9.1.1	Porcelains	Brown Brown Brown
9.1.2	Structures	Hot dip galvanized
9.1.3	Cubicles and enclosures	As specified
10	LVAC EQUIPMENT	
10.1	Rated system voltage	V 415V-30 415V-30 415V-30 240V-10 240V-10 240V-10
10.2	Rated frequency	Hz 50 50 50
10.3	Method of earthing system neutral	Solidly earthed
10.4	Type of equipment required (switchfuses, MCCBs, air circuit breakers etc)	Air circuit breaker MCCBs
10.5	Voltage limits for correct operation of circuit breakers	% V ±10 ±10 ±10 % f ±5 ±5 ±5
11	DC AUXILIARY SUPPLIES	
11.1	Nominal voltage of system	V 220 220 220
11.2	Voltage limits for correct operation of equipment	% ±10 ±10 ±10 ±5 ±5 ±5
12	NOMINAL VOLTAGE OF AUXILIARY SUPPLIES	
12.1	Supply for electrical operation of circuit breakers	
12.1.1	Closing initiation	V dc 220 220 220
12.1.2	Tripping	V dc 220 220 220
12.2	Power supply for compressor equipment	415 415 415
12.3	Power supply for spring and hydraulic charging motors	V ac 240 240 240
12.4	Supply for indication and alarm circuits	V dc 220 220 220

CORONA, RIV AND SEISMIC TEST PROCEDURES

Corona and Radio Interference Voltage (RIV) test:

1) General:

Unless otherwise stipulated, all equipment together with its associated connectors, where applicable, shall be tested for external corona both by observing the voltage level for the extinction of visible corona under falling power frequency voltage and by measurement of radio interference voltage(RIV).

2) Test Levels:

The test voltage levels for measurement of external RIV and for corona extinction voltage are listed under the relevant clauses of the specification.

3) Test Methods for RIV

3.1 RIV tests shall be made according to measuring circuit as per International Sub-Committee on Radio Interference Publication 1- 1972 second edition. The measuring circuit shall preferably be tuned to frequency of 0.5 MHz but other frequencies in the range of 0.5 MHz to 2 MHz may be used. The measuring frequency shall be recorded. The results shall be in microvolts.

3.2 Alternatively, RIV tests shall be conducted in accordance with NEMA standard publication No. 107-1964 except as otherwise noted herein.

3.3 In measurements of RIV only standard fittings of identical type supplied with the equipment and a simulation of the connections as used in the actual installation will be permitted in the vicinity within 3.5 metres of terminals.

3.4 Ambient noise shall be measured before and after each series of tests to ensure that there is no variation in ambient noise level. If variation is present, the lowest ambient noise level will form basis for the measurement. RIV levels shall be measured at increasing and decreasing voltages of 85%, 100%, 115% and 130% of the specified RIV test voltage for all equipments unless otherwise specified.

3.5 The metering instruments shall be as per CISPR recommendation or equipment device so long as it has been used by other testing authorities.

3.6 The RIV measurement may be made with a properly tuned noise meter.

4.0 Test Methods for Visible Corona:

4.1 The purpose of this test is to determine the corona extinction voltage of apparatus and connectors, the test shall be carried out in the same manner as RIV test described above with the exception that RIV measurements are not

required during test and a search technique shall be used near the onset of extinction voltages, when the test voltage is raised and lowered to determine their precise values. The test voltage shall be raised to 130% of RIV test voltage and maintained there for five minutes. The voltage will then be decreased slowly until all visible corona disappears. The voltage will then be raised slowly again to the same maximum voltage. The procedure shall be repeated at least 4 times with corona inception and extinction voltage recorded each time. The corona extinction voltage for purposes of determining compliance with the specification shall be the lowest of the four values at which visible corona (negative or positive polarity) disappears. Photographs with laboratory in complete darkness shall be taken under test conditions, at all voltage steps i.e., 85%, 100%, 115% and 130%. Additional photographs shall be taken at corona inception and extinction voltages. At least two photographs shall be taken in each case.

- 4.2 The test to determine the visible corona extinction voltage need not be carried out simultaneously with test to determine RIV levels. However, both tests shall be carried out with the same test set up and as little time duration between tests as possible. No modifications or treatment of the sample between tests will be allowed. Simultaneous RIV and visible corona extinction voltage testing may be permitted at the discretion of owner's inspector if, the same, in his opinion, will not prejudice other tests.

B. Seismic Withstand Test:

The seismic withstand test on the complete equipment shall be carried out along with the supporting structures etc. The seismic level specified shall be applied at the base of the structure. The accelerometers shall be provided at the terminal pad of the equipment and any other point as agreed by the purchaser. The seismic test shall be carried out in all possible combinations of the equipment. The detailed seismic test procedure shall be furnished for approval to the purchaser ,before offer for inspection.

TECHNICAL SPECIFICATION

FOR

36 KV VACCUM CIRCUIT BREAKERS (OUT DOOR TYPE)

TECHNICAL SPECIFICATION FOR 36 K.V. VACCUM CIRCUIT BREAKERS (OUTDOOR TYPE)

1.1 SCOPE:

36 K.V. 1430 MVA Circuit Breakers are intended to be purchased for installation at different Sub-stations. Some of the Sub-stations for which equipment are tendered are situated in coastal areas where saline climate prevails. The base structure of the circuit breakers must be galvanized.

1.2 POWER SUPPLY TO AUXILIARIES :

A.C. supply to auxiliaries will be 3 phase, 3 wire, 430 volt or single phase 250 volts at 50 C/s. The voltage variation will be within 10% and the frequency variation $\pm 5\%$.

1.03 33 K.V. CIRCUIT BREAKERS TYPE AND RATING :

The circuit breakers shall be vacuum type suitable for outdoor operation under the climatic conditions specified without any protection from sun and rain.

The circuit breaker shall have the following ratings :

- | | | | |
|----|-------------------------------------|---|--|
| 1. | Number of poles | : | 3 (One unit with three phase making and breaking). |
| 2. | Frequency. | : | 50 C/s. |
| 3. | Nominal system voltage | : | 33 KV rms. |
| 4. | Highest system voltage | : | 36.0 KV rms. |
| 5. | Basic insulation level | : | 170 KVP |
| 6. | Power frequency test Voltage (wet). | : | 75 KV (rms.) |
| 7. | <u>Nominal Current.</u> | : | 1250 Amps rms. |

- | | | | |
|--------|---|---|------------------------------------|
| 7a. | First pole to clear factor | : | 1.5 |
| 8. | Breaking capacity. | | |
| | (a) Symmetrical. | : | 25 KA/1430 MVA. |
| | (b) Asymmetrical. | : | 33 KA Peak. |
| 9. | Making capacity. | : | 62.5 KA Peak. |
| 10. | Continuous current rating. | : | 1250 Amps (RMS) |
| 11. | Operating Duty. | : | 0-0.3 Sec-CO-3 Min-CO. |
| 12.(a) | Break time | : | 3 Cycles |
| | (b) Make time | : | 5 Cycles. |
| | (c) Minimum reclosing time | : | 15 Cycle. |
| | (d) Minimum dead time for reclosing: | : | 15 Cycle |
| 13. | Dry one minute power frequency withstand test voltage | | |
| | a) Between line terminal | : | 75 KV rms. |
| | b) Between line and body | : | 75 KV rms. |
| 14. | Impulse withstand test voltage ; | | |
| | a) Between terminal with C.B. open. | : | 170 KV (Peak) |
| | b) Between body & terminal | : | 170 KV (Peak) |
| 15. | Insulator or bushing | | |
| | a) Dry one minute power Frequency voltage, | : | 75 KV |
| | b) Wet one minute power Frequency withstand Voltage. | : | 75 KV |
| | c) Creepage distance | : | 580 mm (Minimum) |
| 16. | Short time current rating for 3 seconds. | : | Not less than 25 KA for 3 seconds. |
| 17. | Control circuit voltage | : | 220 V D.C |

1.04 **STANDARDS :**

The circuit breakers shall comply with the requirements of latest issue of IEC-62271-100, IEC-60694/IS12729:2004, IS-13118:1991, except wherein specified otherwise. Where the equipment offered confirm to any other standard the silent points of difference between the standard adopted and the IS or IEC recommendations shall be brought out in the tender. Equipment meeting any other authoritative standard which ensures an equal or better quality than the standard mentioned above is also acceptable.

CLIMATIC CONDITIONS :

The climatic conditions at site under which the equipment shall be operated satisfactorily are as follows :

- | | | |
|---|---|-------|
| Peak ambient air temperature | : | 50° C |
| Maximum temperature attainable by an object exposed to sun. | : | 60° C |
| Minimum temperature of the air in shade. | : | 0° C |
| Maximum yearly weighted average | : | 32° C |

ambient Temp.

Maximum daily average ambient temp	:	35deg C
Maximum humidity.	:	100%
Average number of thunder storm:		70 Days per annum.
Average number of rainy days per Annum.	:	120
Average annual rainfall.		1500 mm
Number of months of tropical Monsoon conditions per annum.		4
Maximum wind pressure.		260 kg/Sq.m.
Altitudes not exceeding.	:	1000 M

For the purpose of the specification, the limit of ambient temperature shall be 50° C peak and 45° C average over a 24 hours period.

Some of the breakers to be purchased against this specification are intended to be installed on the sea coast having extremely saline climate. Necessary anti corrosive provisions need be incorporated.

1.5 **GENERAL :**

1.6 The circuit breakers shall be of vacuum type. The breakers shall be furnished as a complete unit with all accessories and equipment in place and all internal wiring installed and terminated in the mechanism.

1.7 The circuit breakers shall provide rapid and smooth interruption of current under all conditions, completely suppressing all undesirable phenomena even under the most severe and persistent short circuit conditions or when interrupting small currents of leading or lagging reactive current. The details of any device incorporated to limit or control the rate of rise of restricting voltages across the circuit breaker contacts shall be stated. The over voltages caused by the circuit breaker switching on inductive or capacitive load shall not exceed, 2.5 times the normal phase to neutral voltage. The total break time for the circuit breakers throughout the range of their operating duty shall be stated in the tender and guaranteed.

1.8 **CONSTRUCTIONAL FEATURES :**

Each circuit breaker shall comprise 3 identical poles complete with a gang operated mechanism for specified duty. All these poles of the C.B. shall be linked together Electrically, Mechanically for specified duty.

The breaker shall be capable of interruptions of low reactive current (lagging/leading) without undue over voltage and restrike.

1.9 **CONTROL CUBICLE :**

A common control cubicle shall be furnished to house electrical controls, monitoring devices and all other accessories. The cubicle shall be of gasketed weather proof construction, fabricated from sheet **Aluminium alloy enclosure/ Galvanised M.S (minimum 3mm thickness). The operating mechanism shall be strong,rigid and not subject to rebound.**

1.10 The cubicle shall have front access door with lock and keys and removable gland plate at the bottom for owner's cable entry. Thermostat controlled space heater, internal illumination lamp, 5 A 3 pin socket with individual on off switches shall be provided in the cubicle.

1.11 MOUNTING :

The circuit breakers shall be suitable for mounting on steel galvanized structures. The prices of necessary frames for mounting the circuit breaker shall be included with the offer. A ladder should be provided in the structure for easy access to the operating mechanism house. The ladder shall be of M.S with hot dip galvanized.

1.12 The circuit breakers shall consist of three identical single phase units with a common operating mechanism. All joints shall be welded so as to have adequate mechanical strength. The breaker porcelain shall be capable of withstanding all pressure resulting from any specified performance of the breaker.

The circuit breaker shall be supplied complete with the necessary lifting tools, foundation bolts and other accessories.

1.13 TEMPERATURE RISE :

The maximum temperature attained by any part of the equipment when in-service at site under continuous full load conditions and exposed to direct rays of sun shall not exceed the permissible limits fixed by approved specifications. When the standards specifies the limits of temperature rise these shall not exceed when corrected for the difference between ambient temperature at site and the ambient temperature specified in the approved specification. The corrections proposed shall be stated in the tender and shall be subject to approval of the purchaser.

1.14 INSULATION OF THE CIRCUIT BREAKERS :

1.15 The insulation to ground, the insulation between open contacts, the insulation between phases of the completely assembled circuit breakers, should be capable of withstanding satisfactorily die-electric test voltages corresponding to basic insulation level specified in clause-1.03.

1.16 The clearance in open air shall be as follows, unless the apparatus is impulse tested after complete assembly.

- | | | |
|------|---|---------|
| i) | Minimum clearance between phase : | 505 mm |
| ii) | Phase to Earth. : | 305 mm |
| iii) | Minimum clearance between live :
Parts and grounded objects. | 1400 mm |
| iv) | Minimum ground clearance to live:
part. | 3700 mm |

1.17 BUSHING AND INSULATIONS :

The basic insulation level of the insulating porcelains shall be as specified and shall be suitable for installation in contaminated atmospheres. The porcelains used shall be homogenous and free from cavities and other flaws. They shall be designed to have ample insulation, mechanical strength and rigidity for satisfactory operation under conditions specified above. The puncture strength of the bushings shall be greater than the flashover value. The bushings shall be entirely free from radio disturbance when operating at a voltage 10% above rated voltage and also be free from external corona.

Adequate means shall be provided to accommodate conductor expansion and there should not be any undue stressing of any part due to temperature change.

1.12 **OPERATION MECHANISM** :

1.12.1 The operating mechanism shall be spring operated type. In case of spring operating mechanism it shall be of motor operated having provision of hand operated spring charging type of by local/remote electric control under normal operation. The mechanism shall be trip from electrically and mechanically. All working parts in the mechanisms shall be corrosion resistant material and all bearings which require greasing shall be equipped with pressure grease fittings. The mechanism shall be strong, positive, quick in action and shall be removable without disturbing the other parts of the circuit breakers. The mechanisms of breaker shall be such that the failure of any spring will not prevent tripping.

1.12.2 The operating mechanism along with its accessories shall be mounted in a weather proof cabinet with hinged doors located near the breakers. A local control switch and the breaker position indicator shall be provided in the cabinet. The circuit breakers shall also be provided with means for manual operation for maintenance purposes.

1.12.3 The control circuits shall be designed to operate on 220V. d.c. It shall be possible to adopt to work on other voltages by simply changing the operating coils. The closing and operating coils shall be designed to operate satisfactorily at any control voltage from 70% to 115% of the normal rated voltage. A heater shall be provided in the cabinet to prevent moisture condensation.

1.12.4 Necessary cable glands for the cables of the operating mechanism shall be provided.

1.12.5 The operating mechanism enclosure shall be of **Aluminium alloy enclosure/ Galvanised M.S (minimum 3mm thickness)**.

1.12.6 **All the terminal blocks to be used in the operating mechanism should be of stud type of Poly-amide/Melamine material of make like Elmex (OAT-6 for non-disconnecting type and OAT 6T for disconnecting type) / Connectwell (Equivalent).**

1.12.7 **The Motor to be used for spring charging shall be of Universal type and suitable for AC and DC supply(220 V DC).**

1.13 **TERMINAL CONNECTORS** :

Technical connectors suitable for all ACSR Moose/ACSR Zebra Conductor (as per the provision laid down) shall be provided, Suitable terminal earth connector for earthing connections shall also be supplied.

1.14 **AUXILIARY SWITCHES** :

Spare 10 Nos N/O (normally open) & 10 Nos N/C (normally closed) of auxiliary switches (contacts) shall be provided on each circuit breaker for use in the remote indication and control scheme of the circuit breaker and for providing safety interlocking etc. Special contact for use with trip coil and single short reclosing operation which permits relative adjustment with respect to the travel of the moving contact of the circuit breaker shall also be provided. There shall be provision to add more auxiliary switches at the later date if required.

1.15 **COMPLETENESS OF EQUIPMENT** :

Any fittings, accessories or apparatus which may not have been specifically mentioned in those specification but which are usual or necessary in

the equipment of similar plant shall be deemed to be included in the contract and shall be supplied by the contractor without extra charges. All plant and equipment shall be complete in all details whether such details are mentioned in the specification or not. The detail bill of materials list to be furnished along with the tender.

1.16 **AFTER SALES SERVICE :**

1.16.1 The supplier should guarantee for after sales service for a minimum period of one and half years from the date of receipt of the equipment or one year from the date of commissioning of the equipment whichever is earlier.

1.16.2 The supplier also should guarantee after sales service beyond the free service period.

1.16.3 Supplier also should provide after sales service within 15 days of receipt of intimation from the field Engineer-in-charge of the equipment or the purchaser.

1.16.4 **COMMISSIONING :**

The manufacturers shall render all help for commissioning of the breakers. Supervision of erection , testing & Commissioning charges per breaker to be quoted in the schedule of prices (Annexure-v) for evaluation of the Price bid or else it will be presumed that the charges towards Supervision of erection , testing & Commissioning per Breaker are included in the unit price offered.

1.17 **EXPERIENCE :**

The list of supplies already made by the supplier/manufacturers are to be enclosed along with the tenders.

1.18 **RECOMMENDED SPARES AND TOOLS :**

For 5 (five) years operation, price are to be enclosed along with the tenders for each item of spares and special tools.

2.0 **TEST :**

2.1 Type test : - All the equipment offered shall be fully type tested as per the relevant standards. In case the equipment of the type and design offered, has already been type tested in an Govt. Approved test Laboratory, the bidder shall furnish four sets of type test reports along with the offer. These tests **must not have been conducted earlier than five years from the date of opening of bids**. The purchaser reserves the right to demand repetition of some or all the type tests in the presence of owner's representative. For this purpose the bidder may quote unit rates for carrying out each type test. These prices shall be taken into consideration for bid evaluation. For any change in the design/type offered against this specification, if accepted by the purchaser, the purchaser reserves the right to demand repetition of tests without any extra cost. Reports of Type tests as stipulated in relevant IS along with Impulse and short circuit test documents conducted shall be supplied along with the tender. All the test reports should be submitted and shall be approved by the purchaser before dispatch of the material.

Note :- Tender not accompanying with the type test reports alongwith Impulse and short circuit tests are liable for rejection.

Type Tests:--(As per IEC-62271-100)

1) Dielectric Test(LI Voltage,PF Voltage Withstand(Dry&Wet)& etc)

- 2) RIV Test
- 3) Measurement of resistance of the main circuit
- 4) Temperature rise Test
- 5) Basic short circuit duty test ,Short Time withstand current & Peak withstand current Test
- 6) Mechanical Operation Test, Mechanical endurance test
- 7) Out of phase / Short Circuit making & Breaking Test
- 8) Capacitive Current, Switching Test ,a) cable charging current Test b) Single capacitor Bank current switching test
- 9) Test to verify degree of protection

Routine Tests:-

- 1) Dielectric Tests on the main Circuit ,auxiliary & control circuits
- 2) Measurement of resistance of the main circuit.
- 3) Design & Visual Checks(Dimensions,clearances&etc)
- 4) Mechanical operation Test
- 5) Operating time of the device, motor Characteristics, measurement of coil current & resistance , S_f6 gas pressure monitoring ,electrical scheme,control Circuit,antipumping, vacuum interrupter(type,make&etc),dimensions, name plate details , contact travel & timing checks .

Acceptance and Routine Tests.

2.1.1 All acceptance and routine tests as stipulated in the relevant standards & above shall be carried out by the supplier in presence of owner's representative.

2.1.2 Immediately after finalization of the programme of type/acceptance/routine testing, the supplier shall give twenty days advance intimation to the purchaser, along with the shop routine test certificate and valid calibration certificates of the equipments/instruments calibrated in a govt. approved test house ,to be used during testing for scrutiny,to enable him to depute his representative for witnessing the tests.

3.0 **INSPECTION** :The inspection may be carried out by the purchaser at any stage of manufacture. The successful tenderer shall grant free access to the purchaser's representative at a reasonable time when the work is in progress. Inspection and acceptance of any equipments under this specification by the purchaser, shall not relieve the supplier in his obligation of furnishing equipment in accordance with the specification and shall not prevent subsequent rejection if the equipment is found to be defective.

The supplier shall keep the purchaser informed in advance, about the manufacturing programme so that arrangement can be made for inspection.

The purchaser reserves the right to insist for witnessing the acceptance/routine testing of the bought out items.

4.0 **QUALITY ASSURANCE PLAN** :

4.1 The tenderer shall invariably furnish following information along with his offer, failing which his offer shall be liable for rejection. Information shall be separately given for individual type of equipment offered.

- (i) Statement giving list of important raw materials names of sub-suppliers for the raw materials, list of standards according to which the raw materials are tested. List of tests normally carried out on raw materials in presence of tenderer's representative, copies of test certificates.
- (ii) Information and copies of test certificates as in (i) above in respect of bought out accessories.
- (iii) List of manufacturing facilities available.
- (iv) Level of automation achieved and list of areas where manual processing exists.
- (v) List of areas in manufacturing process, where stage inspections are normally carried out for quality control and details of such tests and inspections.
- (vi) Special features provided in the equipment to make it maintenance free.
- (vii) List of testing equipments available with the tenderer for final testing of equipment specified and test plant limitation. If any, vis-avis the type, special acceptance and routine tests specified in the relevant standard. These limitations shall be very clearly brought out in schedule of deviations from specified test requirements.

4.2 The successful tendered shall within 30 days of placement of order, submit following information to the purchaser.

- (i) List of raw materials as well as bought out accessories and the names of sub suppliers selected from those furnished along with offer.
- (ii) Type test certificates of the raw material and bought out accessories.
- (iii) Quality assurance plan (QAP) with hold points for purchaser's inspection. The quality assurance plan and purchaser's hold points shall be discussed between the purchaser and supplier before the QAP is finalized.

4.3 The successful bidder shall submit the routine test certificates of bought out accessories and central excise passes for raw material viz. oil, copper, aluminum, conductors, insulating materials, core material at the time of routine testing of the fully assembled equipment.

4 .4 DOCUMENTATION :

5.1 All drawing shall conform to International Standards organization (ISO). A series of drawing sheet/Indian standards specification IS.656. All drawings shall be in ink and suitable for micro filming. All dimensions and data shall be in S.I. Units.

4.1 List of drawings and documents.

The bidder shall furnish four sets of following drawings along with his offer.

- a) General outline and assembly drawings of the equipment.
- b) Graphs showing the performance of equipments
- c) Sectional views showing :-
 - i) General Constructional features.
 - ii) The materials/gaskets/sealing used.
 - iii) method of connections.
 - iv) Porcelain used and its dimensions along with the mechanical and electrical characteristics.
- d) Arrangement of terminal's and details of connection studs provided.

- e) Name Plate.
- f) Schematic drawing :-
- g) Type test reports in case the equipment has already been type tested.
- h) Test reports, literature, pamphlets of the bought out items, and raw material.

4.2 The successful tender shall, within 2 weeks of placement of order, submit four sets of final version of all above said drawings for purchaser's approval. The purchaser shall communicate his comments/ approval on the drawings to the supplier within four weeks. The supplier shall, if necessary modify the drawings and resubmit three copies of the modified drawings for owner's approval within two weeks from the date of owner's comments. After receipt of owner's approval, the supplier shall within two weeks, submit. 15 prints and two good quality reproducible of the approved drawings for purchaser's use.

4.3 Six sets of the type test reports, duly approved by the purchaser, shall be submitted by the supplier for distribution before commencement of supply. Adequate copies of acceptance and routine test certificates, duly approved by the purchaser, shall accompany the dispatched consignment.

4.4 The manufacturing of the equipments shall be strictly in accordance with the approved drawings and no deviation shall be permitted without the the written approval of the purchaser. All manufacturing and fabrication work in connection with the equipment prior to the approval of the drawing shall be at the supplier's risk.

4.5 15 sets of nicely printed and bound volumes of operation, maintenance and erection manuals in English language for each type and rating of equipment supplied shall be submitted by the supplier for distribution, prior to the dispatch of the equipment. The manual shall contain all the drawings and information required for erection, operation and maintenance of the equipment. The manual shall also contain a set of all the approved drawings, type test reports etc.

4.6 Approval of drawings/work by purchaser shall not relieve the supplier of his responsibility and liability for ensuring correctness and correct interpretation of the drawings for meeting the requirement of the latest revision of applicable standards, rules and codes of practices. The equipment shall conform in all respects to high standards of engineering design workmanship & latest revisions of relevant standards at the time of ordering & purchaser shall have the power to reject any work or materials which in his judgement is not in full accordance therewith.

5 PACKING AND FORWARDING

5.1 The equipments shall be packed in crates suitable for vertical/horizontal transport as the case may be, and suitable to withstand handling during transport and outdoor storage during transit. The supplier shall be responsible for any damage to the equipment during transit, due to improper and inadequate packing. The easily damageable material shall be carefully packed and marked with the appropriate caution symbol. Wherever necessary, proper arrangement for lifting, such as lifting books etc. shall be provided. Any material found short inside the packing cases shall be supplied by supplier without any extra cost.

5.2 Each consignment shall be accompanied with a detailed packing list containing the following information.

- a) Name of the consignee.
- b) Details of consignment.
- c) Destination
- d) Total weight of consignment.
- e) Sign showing upper/lower side of the crate.
- f) Handling and unpacking instructions.
- g) Bill of material indicating contents of each package.

The supplier shall ensure that the packing list and bill of material are approved by the purchaser before dispatch.

TOPOGRAPHICAL AND METEOROLOGICAL SITE CONDITIONS

Location of installations	State of Orissa
Altitude	1000 m
Maximum Temperature	60°C
Minimum Temperature	0°C
Maximum daily average temperature	35°C
Maximum humidity	100%
Pollution level	Heavy
Airborne contamination, if any	Highly Polluted
Seismic withstand factor	0.3 g
Maximum wind pressure	260 kg/m ²
Wind velocity	50m/sec
Maximum rainfall per annum	2000 mm
Average rainfall per annum	1500 mm
Average no. of thunder-storm days/annum	70
Average no. of dust storm days per annum	20

ODISHA POWER TRANSMISSION CORPORATION LIMITED

**TECHNICAL SPECIFICATION
FOR
CURRENT TRANSFORMERS**

I: - 33KV CT

a) **RATIO-400-200A-100/1-1-1A**

b) **RATIO-800-400-200A/1-1-1-1 A**

II: - 132 KV CT

a) **RATIO-800-400-200A/1-1-1-1A**

b) **RATIO-600-300-150A/1-1-1-1A**

c) **RATIO-400-200A-100/1-1-1-1A**

d) **RATIO-200-100/1-1-1-1A**

III: - 220 KV CT

RATIO-1200-600-300A/1-1-1-1-1A

IV:- 400 KV CT

RATIO:2000-1000-500/1-1-1-1-1A

Remarks: Metering core of all type CT's shall be 0.2s

**TECHNICAL SPECIFICATION FOR 33KV, 132KV,
220KV & 400 KV CURRENT TRANSFORMERS WITH
METERING CORES OF ACCURACY CLASS 0.2**

1.0 SCOPE :

1.1. The specification covers the design, manufacture, assembly, inspection and testing at the manufacturer's work, packing and delivery F.O.R. (destination) of the outdoor mounted dead tank type, single phase, single unit type current Transformers and CT console(one CT console per 3 CT's) for protection and metering services in 33KV, 132KV, & 220KV and 400 KV solidly grounded system.

Current transformers shall be supplied with common marshalling box in a batch of three CT's along with terminal connectors and other fittings for forming necessary interphase and control room interconnections. The CT console shall be of Aluminum alloy sheets having 3 mm thickness.

1.2. The current transformers shall be of the outdoor type, single phase, 50 C/S, oil immersed, self cooled, hermetically sealed and suitable for operating in the tropical conditions with maximum ambient temperature upto 50⁰C. The C.TS should be suitable for use in the areas subject to heavy lightning storms and highly polluted conditions.

1.3. Followings are the list of documents constituting this specification.

[i]	Technical specification(TS)	
[ii]	Technical Requirements	Appendix I
[iii]	Quantity and Delivery Schedule (Appendix II)	Appendix II
[iv]	Guaranteed Technical Particulars	Annexure . A
[v]	Calibration Status of testing equipments and meters / Instruments	Annexure . B
[vi]	Check-List towards Type Test Reports	Annexure-C
[vii]	Check-List for Delivery Schedule	Annexure-D
Note :	Annexure- A, B, C & D are to be filled up by the Bidder	

1.4 The current transformer shall conform in all respects to high standards of engineering, design, workmanship and latest revisions of relevant standards at the time of offer and purchaser shall have the power to reject any work or material which in his judgment is not in full accordance therewith.

1.5 Bidders are required to quote for 0.2 accuracy class of metering cores with the following data / informations etc.

- [a] Guaranteed Technical particulars.
- [b] Technical literatures, brochures and drawings as per this specification.
- [c] Type Test Reports.
- [d] List of orders, executed and User's certificates, failing submission of the above particulars with the offer, the tender may not be considered for evaluation.

2.0 STANDARDS

2.1 Except to the extent modified in the specification, the C.TS shall conform to the latest editions and amendments of the standards listed hereunder.

Sl. No.	Standard Ref. No.	Title
1	IEC-44	Instrument transformer-measurement of PDS
2.	IEC-60	High Voltage Testing Technique.
3.	IEC-171	Insulation co-ordination
4.	IEC-185	Current Transformers.
5.	IEC-270	Partial Discharge Measurement
6.	IEC-8263	Method for RIV Test on High Voltage Insulators.
7.	IS-335	Insulating oil for Transformers

8.	IS:2071	Method of High Voltage Testing
9.	IS:2099	High Voltage porcelain Bushings
10.	IS:2147	Degree of Protection Provided by Enclosures for Low Voltage Switchgear and Control.
11.	IS:2165	Insulation Co-ordination for equipment of 100KV and above
12.	IS:2705 [Part-I to IV)	Current Transformers
13.	IS:3347	Dimensions of Porcelain Transformer Bushing
14.	IS:5621	Specification for Large Hollow Porcelain for use in Electrical installation.
15.	IS:4201	Application guide for CTS
16.		Indian Electricity Rules, 1956
17.	<i>IS:13072 –of1991</i>	<i>SF6 Gas (for 220kv SF6 gas filled CTs only)</i>
18.	<i>IEC:60376</i>	<i>SF6 Gas(for 220kv SF6 gas filled CTs only)</i>

2.2 Current Transformers with the requirements of other authoritative standards, which ensure equal or better quality than the standards, mentioned above, shall also be acceptable, Where the equipment, offered by the supplier conforms to other standards, salient points of difference between the standards adopted and specified standards shall be brought out in th offer. 4 (four) copies of the reference standards in English language shall be furnished along with the offer.

2.3 The supplier is to furnish the latest edition of the standards as mentioned above from SI.1 to SI.15 with their amendments, if any, at their own cost, if required by the Purchaser.

2.4 All the above alongwith amendments thereof shall be read and interpreted together. However, in case of a contradiction between the Technical Specification and any other volume, the provisions of this specification will prevail.

3.0 CLIMATIC & SERVICE CONDITIONS :

3.1 The current Transformers are required to operate satisfactorily under the following conditions.

[a]	Maximum ambient temperature	50 ⁰ C
[b]	Minimum ambient temperature	0 ⁰ C
[c]	Maximum daily average ambient air temperature	45 ⁰ C
[d]	Maximum relative humidity	100%
[e]	Average no. of rainy days in a year.	120 days
[f]	Average annual rainfall	150 cm
[g]	Maximum wind pressure	260 Kg/Sq.m

[h]	Altitude not exceeding	1000 m
-----	------------------------	--------

3.2 EARTHQUAKE INCIDENCE

The current Transformers are to be designed to withstand earthquakes of an intensity equivalent to seismic acceleration of 0.3g in the horizontal direction and 0.15g in the vertical direction, where g stands for acceleration due to gravity.

3.3 The current Transformers covered under this specification shall be suitable for outdoor installation.

4.0 PURCHASER'S AUXILIARY POWER SUPPLY :

4.1 Following power supplies shall be made available at site.

- (a) A.C. Three phase, 415V, 50HZ earthed
- (b) A.C. Single Phase, 240V, 50HZ earthed.
- (c) 220 V D.C. ungrounded.

4.2 All the equipments and devices shall be capable of continuous satisfactory operation on AC and DC supplies of normal voltage mentioned above with the variation given below.

[a]	AC voltage variation	$\pm 10\%$
[b]	Frequency variation	$\pm 5\%$
[c]	Combined voltage and frequency variation	$\pm 10\%$
[d]	DC Voltage Variation	<u>190V to 240V</u>

4.3 The supplier shall make his own arrangements for the power supplies other than those specified under clause 4.1 above.

5.0 GENERAL TECHNICAL REQUIREMENTS :

5.1 The C.T. shall be of dead tank design and shall be so constructed that it can be easily transported to site within the allowable limitation and in horizontal position if the transport limitations so demand. *The 400 KV CTs may be of live tank design.*

5.2 For compensation of variation in the oil volume due to ambient variation, nitrogen cushion / metal bellows shall be used. Rubber diaphragms shall not be permitted for this purpose.

5.3 The C.T. secondary terminals shall be brought out in a weather proof terminal box. The terminal box shall be provided with removable gland plate and gland (s) suitable for 1100 volts grade PVC insulated, PVC sheathed, multicore 4 Sq. mm stranded copper conductor cable. The terminal blocks shall be stud-type and provided with ferrules, indelibly marked or numbered. The terminals shall be rated for not less

than 10 Amps. The terminal box shall be dust and vermin proof. Suitable arrangements shall be made for drying of air inside the secondary terminal box. The dimensions of the terminal box and its openings shall be adequate to enable easy access and working space with the use of normal tools.

5.4 Polarity shall be indelibly marked on each primary and secondary terminal. Facility shall be provided for short-circuiting and grounding of the C.T. secondary terminals inside the terminal box.

5.5 The C.T. shall be provided with non-corrosive, legible name plate with the information, specified in the relevant standards, duly engraved/punched on it.

5.6 The current Transformer shall be vacuum filled with oil after processing and thereafter hermetically sealed to eliminate breathing and to prevent air and moisture from entering the tanks. Oil filling and / or sampling cocks, if provided to facilitate factory processing should be properly sealed before despatching the C.T., The method adopted for hermetic sealing shall be described in the offer

5.7 The castings of base, collar etc. shall be diecast and tested before assembly to detect cracks and voids, if any.

5.8 The instrument security factor of metering core shall be low enough and not greater than 5. This shall be demonstrated on all the ratios of the metering core in accordance with procedure, specified in IEC-185 OR IS:2705. In case the instrument security factor of 5 or less is not possible to be achieved on higher ratios, auxiliary CTS of ratio 1/1 and 0.2 accuracy class shall be deemed to be included in the supplier's scope of supply. This shall also be specifically brought out by the supplier in his offer. However, all parameters, specified shall have to be met treating auxiliary CT/ reactor as an integral part of the current Transformer. The auxiliary C.TS/reactor shall be inbuilt construction of the C.TS.

5.9 Current transformers' guaranteed burdens and accuracy class are to be intended as simultaneous for all cores.

5.10 For 245 KV, 145 and 36 KV Current Transformers, characteristics shall be such as to provide satisfactory performance for burdens ranging from 25% to 100% of rated burden over a range of 5% to 120% of rated current in case of metering CTS and upto accuracy limit factor / knee point voltage in case of relaying C.TS.

5.11 Current Transformers shall be designed so as to achieve the minimum risk of explosion in service. The Bidder shall bring out in his offer, the measures taken to achieve this.

5.12 PRIMARY WINDING

5.12.1 Primary winding may be either ring type or hair pin type or the type, which has been type tested.. For 220KV, 132KV, and 33KV class C.Ts, the rated extended primary current shall be 120% on all cores of the C.Ts, specified in tables.

5.12.2 The primary windings of current transformers shall be constructed of high purity, annealed, high conductivity electrolytic copper/Aluminium meeting to the requirements of IEC 28/IS:2705.

5.13 SECONDARY WINDINGS:

Suitably insulated copper wire of electrolytic grade shall be used for secondary windings. Type of insulation, used shall be described in the offer. The secondary taps shall be adequately reinforced to withstand handling without damage.

The rating of the Current Transformer's secondary winding shall be 1 (One) Amp. The secondary terminals shall be brought out in a compartment for easy access.

5.14 PRIMARY TERMINALS

The primary terminals shall be heavily tinned electrolytic copper or Aluminium alloy of 99.9% conductivity. The minimum thickness of tinning shall be 1.5 microns.

5.15 SECONDARY TERMINALS

5.15.1 Secondary terminal studs shall be provided with at least three nuts and adequate plain and spring washers for fixing the leads. The studs, nuts and washers shall be of brass, duly nickel plated. The minimum outside diameter of the stud shall be 6 mm. The length of at least 15 mm shall be available on the studs for inserting the leads. The horizontal spacing between the centers of the adjacent studs shall be at least 1.5 times the outside circum-dia of the nuts.

5.15.2 The current transformer shall be provided with suitable test tap for measurement of capacitance, tan delta as well as partial discharges. Provision shall be made on a screw cap for solid and secured earthing of the test tap connection, when not in use. A suitable caution plate shall be provided duly fixed on the cover of the secondary terminal box indicating the purpose of the test tap and the necessity of its solid earthing as per prescribed method before energising the Current Transformer.

5.15.3 The secondary terminals shall be provided with shorting arrangements.

5.16 CORE

Each core of the Current Transformer shall be of toroidal shape. Core laminations shall be of cold rolled grain oriented silicon steel or other equivalent alloys of low hysteresis and eddy current losses, high permeability to ensure high accuracy at both normal and over-current conditions. The cores used for protection shall produce undistorted secondary current under transient conditions at all ratios, with specified Current Transformer parameters. The core material, thickness of lamination, the

relevant graphs showing the characteristics of the core material shall be submitted alongwith the offer.

5.17 TANK

5.17.1 Both expansion chambers and the tanks of the Current Transformers shall be made up of high quality steel ,which should be able to withstand full vacuums and pressure occurring during transit and thermal and mechanical stresses resulting from maximum short circuit current during operation. The tanks alongwith all ferrous parts shall be galvanised as per relevant standard.

5.17.2 The metal tanks shall have bare minimum number of welded joints so as to minimise possible locations of oil leakage. Welding in horizontal plane is to be avoided as welding at this location may give way due to vibrations during transport resulting in oil leakage. Supplier has to obtain specific approval from purchaser for any horizontal welding used in the bottom tank.

5.18 SECONDARY TERMINAL BOX :

5.18.1 Secondary Terminal Boxes shall be weather proof with a rating not less than IP 55

5.18.2 All secondary terminals shall be brought out in a compartment on one side of each current transformer for easy access.

5.18.3 The exterior of this terminal box shall be of aluminium alloy sheet of minimum 3 mm thickness.

5.18.4 A terminal board which shall have arrangement for series / parallel connection and arrangement for shorting of secondary terminals shall be provided.. For 220KV and 132KV C.Ts, at least one of the ratios should be achieved through secondary tapping(s). i.,e

primary re-connection is allowed for two ratios where as third ratio is to be achieved by provision of secondary tapping or alternatively all the stipulated ratios may be achieved through secondary tappings. For 132KV C.T. of ratio-400-200A/1-1-1-1A, the specified ratios may be obtained by. Series parallel connection or by secondary tapping.

5.18.5 The terminal box shall be provided with a removable cable gland plate at bottom for mounting cable glands for 1.1KV PVC sheathed 4 x 4 Sq. mm stranded copper conductor cables.

5.18.6 The terminal box shall be provided with a door in front so as to have easy access of secondary terminals. The door shall have a sealing / locking arrangement and shall be suitable to prevent penetration of moisture and rain water.

5.18.7 All terminals shall be clearly marked with identification number to facilitate connection to external wiring.

5.18.8 The secondary box of the CTs also of high quality steel materials with galvanizing as per standard (IS).

5.18.9 The CT console to be provided (one per 3 CTs) is also of high quality steel with proper galvanization.

5.19 PORCELAIN HOUSING

5.19.1 The housing shall be made up of homogeneous, vitreous porcelain of high mechanical and dielectric strength, Glazing of porcelain shall be of uniform brown or dark brown colour with a smooth surface, arranged to shed away rain water or condensed water particles (fog.) The details of location and type of joint, if provided on the porcelain, shall be furnished by the Bidder along with the offer.

5.19.2 The bushings of the Current Transformers shall conform to the latest edition of IS:2099. The hollow porcelain insulator shall conform to the latest edition of IS:5621.

5.19.3 The insulators shall be cemented with Portland cement to the flanges resulting in high mechanical, tensile and breaking strength.

5.19.4 The bushings shall have ample insulation, mechanical strength and rigidity for the condition under which they shall be used and shall be designed to prevent accumulation of explosive gases and provide adequate oil circulation to remove the internal heat.

5.19.5 Cast metal end caps for the bushings shall be of high strength, hot dip galvanized malleable iron. They shall have smooth surface to prevent discharge taking place between the metal parts and porcelain as a result of ionisation.

5.19.6 The insulation of bushings shall be coordinated with that of the current transformer such that the flashover, if any, will occur only external to the Current Transformer.

5.19.7 Oil level gauge and convenient means of filling, sampling and draining of oil should be provided.

5.19.8 End shields should be provided for distribution of stresses.

5.19.9 Corona shields for bushings, if required should be provided.

5.20 INSULATING MEDIUM (OIL TYPE)

The quantity of insulating oil for the filling and the complete specification of the insulating oil shall be stated. The oil shall comply in all respects with the provisions of latest edition of IS: 335. The current Transformers shall be supplied, filled with purified oil completely.

PREVENTION OF OIL LEAKAGE AND ENTRY OF MOISTURE :

5.20.1 The supplier shall ensure that the sealing of the Current Transformer is properly achieved. In this connection, the arrangement provided by the supplier at various

locations including the following ones shall be described, supported by sectional drawings.

- (a) locations of emergence of primary and secondary terminals.
- (b) Interface between porcelain housing and metal tank/s
- (c) Cover of the secondary terminal box.

5.20.2 Nuts and bolts or screws, used for fixation of the interfacing porcelain bushings for taking out terminals shall be provided on flanges, cemented to the bushings and not on the porcelain.

5.20.3 For gasketed joints, wherever used, nitrile butyl rubber gaskets shall be used. The gasket shall be fitted in properly machined groove with adequate space for accommodating the gasket under compression.

5.21 **FITTINGS AND ACCESSORIES :**

Fittings and accessories, listed below shall be supplied with each Current

Transformer. Any fitting, required essential other than those listed below shall also be supplied alongwith each Current Transformer without any extra cost to the purchaser :

- (a) Oil level gauge.
- (b) Oil filling hole and cap.
- (c) Pressure relieving device.
- (d) Phase terminal connectors.
- (e) Lifting lugs for core and windings, bushings and complete Current Transformers.
- (f) Tank earthing pads/terminals with necessary nuts, bolts and washers for connecting to purchaser's earth strip.
- (g) Name / Rating plate.

5.21.1 **(A) OIL LEVEL GAUGE :**

An oil level gauge shall be provided to indicate the oil level in the Current Transformer. This gauge shall be mounted in such a way that the oil level can be seen from ground level. If metal bellow is used, a ground glass window shall be provided to monitor the position of the metal bellow. The metal below shall be tested in accordance with relevant standards. The details shall be to the approval of the purchaser.

5.21.2 **PRESSURE RELIEVING DEVICE :**

Each Current Transformer shall be provided with a pressure relieving device so as to protect bushing of the Current Transformer even under unfavorable conditions. In case of non provision of the PRD, the same should be brought out clearly in the offer with detailed explanation and proof.

5.21.3 (A) OIL DRAIN COCK :

An oil drain cock alongwith a stop cock shall be provided in the bottom flange so as to permit taking of oil samples for testing, if required.

5.21.4 EARTHING :

Metal tank of each Current Transformer shall be provided with two separate earthing terminals for bolted connection to 50mm X 6mm and 75X10 mm flat, to be provided by the purchaser for connection to station earth-mat.

5.21.5 LIFTING ARRANGMENT :

The Current Transformer shall be provided with suitable lifting arrangement to lift the entire unit. The lifting arrangement shall be clearly shown in the general arrangement drawing. Lifting arrangement (lifting eye) shall be positioned in such a way so as to avoid any damage to the porcelain housing or the tanks during lifting for installation / transport. Necessary string guides shall be offered which shall be of removable type.

5.21.6 NAME PLATE & MARKING :

5.21.6.1 The Current Transformer shall be provided with non-corrosive, legible name plate with the information specified in relevant standards, duly engraved/punched On it.

5.21.6.2 A schematic drawing indicating the connections shall be provided in the interior of the Terminal box.

5.21.7 TERMINAL CONNECTORS :

All the Current Transformers shall be provided with bimetallic solderless clamp type, rigid type terminal connectors, suitable for

- (i) 33KV C.T. . ACSR MOOSEqconductor.
- (ii) 132KV C.T. . ACSR MOOSEqconductor.
- (iii) 220 KV C.T. . ACSR MOOSEqconductor & also suitable for AC tube of 4 inchs.
- (iv) 400 KV CT . suitable for Al tube of 4 inch or more

Each terminal connector shall be of universal type, suitable for both horizontal and vertical connections to the transmission line conductors / station bus bars.

5.21.7.1 Terminal connectors shall be manufactured and tested as per IS:5561.

5.21.7.2 All castings shall be free from blow holes, surface blisters, cracks and cavities. All sharp edges and corners shall be blurred and rounded off.

5.21.7.3 No part of a clamp shall be less than 10mm thick.

5.21.7.4 All ferrous parts shall be hot-dip galvanised conforming to relevant standard.

5.21.7.5 For bimetallic connectors, copper alloy linear of minimum thickness of 2 mm shall be cast integral with aluminium body.

5.21.7.6 All current carrying parts shall be designed and manufactured to have minimum contact resistance.

5.21.7.7 Connectors shall be designed to be corona free in accordance with the requirements, stipulated in IS:5561.

6.0 TEST :

6.1 TYPE TESTS & SPECIAL TESTS:-

The current transformers, offered should have been subjected to the following type tests and Special Tests in Government approved test laboratory. The bidder shall furnish four sets of type test and Special Tests reports alongwith the offer for 0.2 accuracy class CTs. These tests should not have been conducted earlier than five

years from the date of opening of the bid. For any change in the design/type already type tested and the design/type offered against this specification, the purchaser reserves the right to demand repetition of some or all type & special tests without any extra cost to OPTCL in the presence of OPTCL representative(s) at the cost of the supplier.

- (a) Lightning Impulse Voltage Test.
- (b) High Voltage power frequency wet withstand voltage Test.
- (c) Short time current test.
- (d) Temperature rise test.
- (e) Determination of errors or other characteristics according to the requirements of the appropriate designation and accuracy class as per individual parts of IS:2705.
- (f) Instrument Security Factor Test.
- (g) IP-55 Test on Secondary Terminal Box.

(In addition to the above tests, following type tests/special tests should have been conducted exclusively for 220KV/400 KV C.T)

- (h) Radio Interference voltage test.
- (i) Corona Extinction test.
- (j) Thermal stability test.
- (k) Thermal Co-efficient test.
- (l) Fast transient test.
- (m) Seismic withstand test.
- (n) Mechanical terminal load on bushing.
- (o) Magnetisation and internal burden tests..

- (p) Effectiveness of sealing tests.
- (q) capacitance and dielectric loss angle test. (For 400 KV ,220KV & 132KV C.Ts.)

N.B :

- Lightning Impulse Test, switching Impulse Voltage test and High Voltage power frequency wet withstand voltage Tests should have been carried out on the same current transformer.
- After the current transformers have been subjected to lightning Impulse Test, and High Voltage power frequency wet withstand voltage tests, these must have been subjected to all the routine tests as per IS:2705 (Part-I to IV).

6.2 ROUTINE TESTS :

The following routine tests shall be conducted on each Current Transformer in the presence of OPTCL's representative(s) for which no charges will be payable by OPTCL. No sampling will be allowed.

- (i) Appearance and Dimensional Check.
- (ii) Verification of Terminal Marking and polarity.
- (iii) Verification of all individual parts / components of the Current Transformer so as to ensure to have complied the above specification.
- (iv) Measurement of Insulation Resistance.
- (v) Power Frequency Dry withstanding Test on Primary and Secondary winding including primary intersections.
- (vi) Over . Voltage Interturn test.
- (vii) Partial discharge Test for 400 KV,220 KV and 132KV C.TS
- (viii) Knee point voltage and Excitation current measurement for μ Sqclass cores.
- (ix) Secondary winding resistance measurement.
- (x) Determination of errors.
- (xi) ISF Test.
- (xii) Leakage Test.
- (xiii) Magnetization Characteristics of the Current Transformers.
- (xiv) Turn ratio error on μ Sqclass cores.
- (xv) Measurement of capacitance for 400 KV,220KV and 132KV C.TS.
- (xvi) Measurement of tan delta at 0.3, 0.7, 1.0 and 1.1U / $\sqrt{3}$ for 400 KV,220KV & 132KV C.Ts.
- (xvii) Checking of SF6 gas Pressure.(for SF6 gas filled CTs)

- The Method For Conducting Partial Discharge Test.

The test circuit for the measurement of partial discharge (PD) should have been in accordance with sub-clause 4.2 of IEC-270. The applied voltage should be raised to

the rated voltage of the Current Transformers and should have been maintained for a period greater than or equal to 10 seconds. The voltage should have been reduced to measuring voltage of

1.1 X145/245/400KV rms/phase
3½

to ground and maintained for a period greater than or equal to 1 minute. The PD should not exceed 10 picco-coulombs.

7.0 **INSPECTION :**

7.1 The purchaser shall have access at all times to the works and all other places of manufacture, where the Current Transformers are being manufactured and the supplier shall provide all facilities for unrestricted inspection of the supplier's works, raw materials, manufacture of all the accessories and for conducting the necessary tests.

7.2 The supplier shall keep the purchaser informed in advance of the time of starting and of the progress of manufacture of equipment in its various stages so that arrangement could be made for inspection.

7.3 No material shall be despatched from its point of manufacture unless the material has been satisfactorily inspected, tested and despatch clearance issued. However, the purchaser reserves the right to alter the despatch schedule, attached to this specification without any extra financial liability to OPTCL.

7.3.1 The acceptance of any quantity of equipment shall in no way relieve the supplier of his responsibility for meeting all the requirements of this specification and shall not prevent subsequent rejection, if such equipments are found to be defective.

8.0 **QUALITY ASSURANCE PLAN :**

8.1 The Bidder shall invariably furnish following information alongwith his offer.

(i) Statement giving list of important raw materials, names of sub-suppliers for the raw materials, list of standards, according to which the raw materials are tested, list of tests, normally carried out on raw material in presence of Bidders' representative, copies of test certificates.

(ii) Information and copies of test certificates as in (i) above in respect of bought out items.

(iii) List of manufacturing facilities available.

(iv) Level of automation achieved and list of areas where manual processing exists.

(v) List of areas in manufacturing process where stage inspections are normally carried out for quality control and details of such test and inspections.

(vi) Special features provided in the equipment to make it maintenance free.

(vii) List of testing equipments, meters available with the Bidder for final testing of equipment specified and test plant limitation, if any, vis-à-vis the type, acceptance and routine tests, specified in the relevant standards. These limitations shall be very clearly brought out in the offer.

(viii) All the testing equipments, meters etc, should have been calibrated in a Government approved laboratory. The Bidder must submit the list of testing equipments and meters test-wise as per Annexure . B of the Technical Specification.

8.2 The supplier shall within 30 days of placement of order submit the following information to the purchaser.

(i) List of raw materials as well as bought out accessories and the names of the materials as well as bought-out accessories and the names of sub-suppliers, selected from those, furnished alongwith the offer.

(ii) Type Test Certificates of the raw material and bought out accessories.

(iii) Quality Assurance plan (QAP) with hold points for the purchaser's inspection. The QAP and hold points shall be discussed between the purchaser and the supplier before the QAP is finalized.

8.3 The supplier shall submit the routine test certificate of bought-out items and raw materials at the time of acceptance testing of the fully assembled equipment.

9.0 **DOCUMENTATION :**

9.1 All drawings shall conform to relevant Indian Standard as per relevant IS. All drawings shall be in ink and suitable for microfilming. All dimensions and data shall be in S.I. units.

9.2 The supplier shall furnish four sets of following drawings/documents along with his offer for 0.2 accuracy class metering core CTs.

(a) General outline and assembly drawings of the Current Transformers.

(b) Sectional views showing.

(i) General constructional features.

(ii) Materials / gaskets / sealing used.

(iii) The insulation of the winding arrangement, method of connection of the primary / secondary winding to the primary / secondary terminals etc.

(c) Schematic drawing

(d) Rating and Diagram plate.

(e) Secondary Terminal Box.

(f) Assembly Sectional view of Primary Terminal

(g) Assembly drawing for secondary terminal.

- (h) The detailed dimensional drawing of Porcelain Housing such as ID, OD, thickness and Insulator details such as height, profile of petticoats, angle of inclination and gap between successive petticoats, total creepage distance etc.
- (i) Sectional view of Pressure Release device.
- (j) Drawing showing details of Oil level Indicator.
- (k) All type and special test reports relating to tests, as mentioned at Cl. No. 6.1 of this Technical Specification.
- (l) Ratio and phase angle error curves for CTS.
- (m) Magnetization characteristic curves such as B-H curves and sp.loss vs. flux density curves.
- (n) Drawings for Terminal Connector.

10.0 TEST REPORTS :

- (i) Four copies of type test and special test reports shall be furnished to the purchaser with the tender offer for 0.2 accuracy class metering core CTs.
- (ii) Copies of acceptance test reports and routine test reports shall be furnished to the purchaser. One copy will be returned, duly certified by the purchaser and only thereafter shall the materials be despatched.
- (iii) All records of routine test reports shall be maintained by the supplier at his works for periodic inspection by the purchaser.
- (iv) All test reports of tests, conducted during manufacture shall be maintained by the supplier. These shall be produced for verification as and when required for by the purchaser.

11.0 SPARE PARTS

A list of spare parts recommended for five years operations for each Current Transformer shall be furnished with the tender. The purchaser will decide the actual quantities of spare parts to be ordered on the basis of the list and the item wise price of spare parts.

12.0 The necessary galvanized flanges, bolts etc. for the base of the Current Transformers shall be supplied without any extra cost to the purchaser.

13.0 PACKING AND FORWARDING :

13.1 The equipment shall be packed in suitable crates so as to withstand handling during transport and outdoor storage during transit. The supplier shall be responsible for any damage to the equipment during transit, due to improper and inadequate packing. The easily damageable material shall be carefully packed and marked with the appropriate caution symbols. Wherever necessary, proper arrangement for lifting such

as lifting hooks etc. shall be provided. A material found short inside the packing cases shall be supplied by supplier without any extra cost.

13.2 Each consignment shall be accompanied by a detailed packing list containing the following informations :-

- (a) Name of the consignee
- (b) Details of consignment
- (c) Destination
- (d) Total weight of consignment
- (e) Sign showing upper / lower side of the crate
- (f) Handling and unpacking instructions
- (g) Bill of materials indicating contents of each package.

13.3 The supplier shall ensure that the bills of materials are approved by the purchaser before despatch.

13.4 Any tender without complete information, as asked for in the above specification, is likely to be rejected.

APPENDIX-I**TECHNICAL REQUIREMENT FOR 33 KV, 132 KV & 220 KV CURRENT TRANSFORMERS**

The Current Transformers under this specification shall conform to the parameters given below :-

Sl. No.	Item.	Specification	
		36 KV	145 KV
1	Type of CT/Installation.	Single phase, dead tank, oil filled, hermetically sealed SF6 gas filled CT's- Single phase, live tank, hermetically sealed	
2	Type of mounting.	Pedestal type	
3	Suitable for system frequency.	50 HZ \pm 5 %	
4	Rated voltage (KV rms)	33	132
5	Nominal system voltage (KV rms)	33	132
6	Highest system voltage (KV rms)	36	145
7	Current ratio (A/A)	a)400-200A/100/ 1-1-1A b)800-400-200A/1-1-1-1 A & 800-400-200A/1-1-1 A & 800-400-200A/1-1 A & 1200-600-300/1-1 A	a)800-400-200A/1-1-1-1-1-1 b)600-300-150A/1-1-1-1-1-1 c)400-200A-100/1-1-1-1-1-1 d)200-100/1-1-1-1-1-1A
8.	Method of earthing the system where the current transformer will be installed.	Solidly Effectively earthed.	
9	Rated continuous thermal current (A)	120 % of rated primary current	
10	Acceptable limit of temperature rise above 50°C ambient temperature for continuous operation at rated current.		
(a)	Winding	45°C	
(b)	Oil	40°C	
(c)	External surface of the core, metallic parts in contact with or adjacent to, insulation.	45°C	
11	Acceptable partial discharge level	Less than 10 picco coulombs	
12.	Maximum radio interference voltage at I. I times the maximum rated voltage.	Less than 500 micro volts	
13.	1.2/50 micro second lightning impulse withstand voltage (KVP) (dry)	170	650
14.	1 minute dry power frequency withstand voltage primary (KV rms)	70	275
15.	Switching Impulse with stand and voltage (KVP)	--	-
16.	1 Minute dry power frequency withstand voltage secondary (KV rms)	3	3
17.	Minimum creepage distance of porcelain Housing (mm)	900	3625
18.	Rated short time withstand current for 1 second at all ratios (KA rms)	25KA	31.5 KA
19.	Instrument security factor at all ratios for metering core.	Not more than 5.0	
20.	Minimum rated short time thermal current density of the primary winding at all ratios (A/mm ²)	As per clause No9.6.3- Note of IS: 2705 (Part-I) Enclosed in separate sheets for each rating of the transformer	

21.	Application, current ratio, output burden, accuracy class, minimum knee point voltage, secondary winding resistance,	Torroidal type 0.15g (Vertical) 0.3g (Horizontal)
22.	Type of core	0.005 or less
23.	Seismic acceleration	
24.	Dielectric dissipation factor at 245/1.732KV (for 220KV C.T) & 145/1.732KV (for 132 KV C.T.) at ambient temperature	
25.	Accuracy class of standard C.T. to be used during testing towards determination of ratio errors and phase angle errors for metering cores.	0.05 or better.

400 KV Current transformer Selection philosophy

The following shall be adopted for selecting the type of current transformers:

- Insulation : Oil impregnated paper/ porcelain.
- Type : Live /Dead Tank type
- Voltage Class : 400kV
- Application : Outdoors

IMPORTANT: ALSO REFER THE SPECIFICATION OF CT,S MENTIONED IN ABOVE SECTIONS.

General

Current transformers shall comply with IEC 60044-1/ IS 2705.

Current transformers shall be supplied with common marshalling box in a batch of three CTs along with terminal connectors and other fittings for forming necessary interphase and control room interconnections.

Current transformers shall operate satisfactorily in system with high **X / R** ratio.(Tp=100ms)

Current transformer tanks along with top metallic parts shall be hot dip galvanised.Spray galvanisation as per IS-5905 with 250 micron thickness of Zinc followed by finishing coats of a suitable primer with sealer.

The impregnation details along with tests and checks to ensure successful completion of impregnation cycle shall be furnished for Project Manager's approval.

Bellows if used for expansions of insulating oil shall be tested in accordance with relevant standards. The details shall be to the approval of the Project Manager.

The instrument transformers shall be designed for use in geographic and meteorological condition as stipulated (GTR)

Constructional features

The secondary windings of current transformers shall be as stated in the schedules and shown in the attached single line diagrams; the secondary windings shall meet the requirements stated in the tables attached under this section of this Specification.

Each current transformer secondary winding circuit shall be earthed at one point only i.e. in the control room.

Terminal boxes shall be weather proof with a rating not less than IP 55. The terminal box shall be provided with a gland plate suitable for PVC insulated PVC sheathed 10 core, 2.5 mm² stranded copper conductor cables.

Where adequate earth screens are fitted between the primary and secondary windings earthing of the secondary winding shall be via a link mounted in the related protection or instrument cubicle. Where such earth screens are not fitted a separate earth system may be necessary.

Wherever possible the connection to earth shall be on the side of the S2 terminals.

Necessary markings for connections shall be provided on each CT at load termination end points and at the associated terminal blocks. Provision shall be provided for short circuiting and grounding of the CT secondary at the terminal blocks.

Different ratios specified shall be achieved by secondary taps only and primary reconnection shall not be accepted.

Core laminations shall be of cold rolled grain oriented silicon steel or other equivalent alloys. The cores used for protection shall produce undistorted secondary current under transient conditions at all ratios, with specified CT parameters.

The expansion chamber at the top of the porcelain insulators should be suitable for expansion of oil.

Facilities shall be provided at terminal blocks in the marshalling box for star delta formation, short circuiting and grounding of CT secondary terminals.

A wiring diagram plate for the interconnections of the three single phase CTs shall be provided inside the marshalling box.

The physical disposition of the secondary cores shall preferably be in the same order as that given in the tables in this section of the specification.

Current transformers shall be suitable for mounting on lattice support structure as stipulated elsewhere in this Specification.

Technical specification of current transformers

Current transformers guaranteed burdens and accuracy class are to be intended as simultaneous for all cores.

For 400 kV class CT's the rated extended primary current of the CT's shall be 200 % of rated primary on all except 2000/1 tap ratio. On 2000/1 ratio the rated extended primary current shall be 120%. However, at 2000/1 ratio the CT shall be thermally rated for 200 % for 15 minutes and 120 % continuous.

For 420kV current transformers, characteristics shall be such as to provide satisfactory performance for burdens ranging from 25 % to 100 % of rated burden over a range of 10 % to 100 % of rated current in case of metering CTs, and up to the accuracy limit factor / knee point voltage in case of relaying CTs.

Current transformers shall be suitable for horizontal transportation. It shall be ensured that the CT is able to withstand all the stresses imposed on it while transporting and there shall be no damage in transit.

For 420 kV CTs the instrument security factor at all ratios shall be less than five (5) for metering cores. If any auxiliary CTs or reactors are used in the current transformers then all parameters specified shall have to be met treating auxiliary CTs or reactors as an integral part of the current transformer. The auxiliary CTs or reactors shall preferably be inbuilt construction of the CTs. In case these are to be mounted separately they shall be mounted in the central marshalling box suitably wired up to the terminal blocks.

Current transformers shall be designed so as to achieve the minimum risks of explosion in service. The Bidder shall bring out in his offer, the measures taken to achieve this.

420 kV and 245 kV current transformers shall be suitable for high speed auto reclosing.

Oil impregnated current transformers

Post type current transformers using oil impregnated paper as the insulant may be of the bar, single or multi-turn primary and shall be hermetically sealed and conform to the requirement of IEC 185.

In case bar primary inverted type current transformers are offered the manufacturer will meet following additional requirements :

- The secondary shall be totally encased in metallic shielding providing a uniform equipotential surface for even electric field distribution.
- The lowest part of the insulation assembly shall be properly secured to avoid any risk of damage due to transportation stresses.
- The upper part of insulation assembly resting on primary bar shall be properly secured to avoid any damage during transportation.
- Nitrogen if used for hermetic sealing should not come in direct contact with oil.

The primary windings of current transformers shall be constructed of high purity, annealed, high conductivity copper or electrolytic grade aluminium meeting to the requirements of IEC 28. secondary windings shall be constructed out of copper only.

Each current transformer shall be impregnated and filled with oil of the grade specified in IEC 296.

The following facilities shall be provided:

- Visual means of determining the level of oil within the transformers from ground level.
- Oil drain cock and sampling device where applicable.
- Earth terminal of adequate dimensions so arranged that the earth connection cannot be inadvertently removed.

The creepage and flashover distances of the support insulator shall be dimensioned to suit the outdoor service conditions specified in the schedules.

Technical parameters

In addition to meeting the system technical parameters the parameters given in the following tables shall apply.

SPECIFIED PARAMETERS FOR KPV, SEC. WDG. RESISTANCE, EXCITATION CURRENT FOR PS CLASS CORES

AND

BURDEN, ISF FOR METERING CORES

OF
ACC.CLASS 0.2s
FOR
33KV, 132KV & 220 KV C.TS

REQUIREMENT FOR 245 KV CURRENT TRANSFORMERS OF RATIO

1200-600-300/1-1-1-1A

No. of Cores	Core No.	Application	Current ratio	Output burden in VA	Accuracy class as per IS: 2705	Minimum knee point voltage (V_k) at all ratios in volts.	Maximum CT resistance RCT in ohms at 75 °C at all ratios	Maximum excitation current at V_k in mA at all ratios.	Instrument security factor
1	2	3	4	5	6	7	8	9	10
5	1	Bus different oil check	1200/1 600/1 300/1	- - -	PS PS PS	600	5.0	40	
	2	Bus differential main	1200/1 600/1 300/1	- - -	PS PS PS	600	5.0	40	
	3.	Metering	1200/1 600/1 300/1	30 30 30	0.2s 0.2s 0.2s	- - -	- - -	- - -	1200/1:-5or less 600/1:-5 or less 300/1:-5 or less
	4.	Transformer back up / line protection	1200/1 600/1 300/1	- - -	PS PS PS	1200	5.0	40	
	5.	Transformer back up/line protection	1200/1 600/1 300/1	- - -	PS PS PS	1200	5.0	40	

REQUIREMENT FOR 145 KV CURRENT TRANSFORMERS OF RATIO

a) 800-400A-200A/1-1-1-1A

No. of Cores	Core No.	Application	Current Ratio	Output burden in VA	Accuracy class as per IS: 2705	Minimum knee point voltage (V_k) at all ratios in	Maximum CT resistance RCT in ohms at 75 °C at all	Maximum excitation current at V_k in mA at all	Instrument security factor at all ratios
--------------	----------	-------------	---------------	---------------------	--------------------------------	---	---	--	--

1	2	3	4	5	6	volts.	ratios	ratios.	10
4	1.	Protection	800/1 400/1 200/1	- - -	PS PS PS	400	4	30	-
	2.	Metering	800/1 400/1 200/1	30 30 30	0.2s 0.2s 0.2s	- - -	- - -	- - -	5 or less 5 or less 5 or less
	3.	Back up	800/1 400/1 200/1	- - -	PS PS PS	400	4	30	-
	4.	For owner's future use.	800/1 400/1 200/1	- - -	PS PS PS	400	4	30	-

REQUIREMENT FOR 145 KV CURRENT TRANSFORMERS OF RATIO

b) 600-300A-150A/1-1-1-1

No. of Cores	Core No.	Application	Current Ratio	Output burden in VA	Accuracy class as per IS: 2705	Minimum knee point voltage (V _k) at all ratios in volts.	Maximum CT resistance RCT in ohms at 75 °C at all ratios	Maximum excitation current at V _k in mA at all ratios.	Instrument security factor at all ratios
1	2	3	4	5	6	7	8	9	10
4	1.	Protection	600/1 300/1 150/1	- - -	PS PS PS	500	5	60	-
	2.	Metering	600/1 300/1 150/1	30 30 30	0.2s 0.2s 0.2s	-	-	-	5 or less 5 or less 5 or less

3.	Back up	600/1 300/1 150/1	- - -	PS PS PS	500	5	60	-
4.	For owner's future use.	600/1 300/1 150/1	- - -	PS PS PS	500	5	60	-

REQUIREMENT FOR 145 KV CURRENT TRANSFORMERS OF RATIO

c) 400-200A-100/1-1-1-1A

No. of Cores	Core No.	Application	Current Ratio	Output burden in VA	Accuracy class as per IS: 2705	Minimum knee point voltage (V_k) at all ratios in volts.	Maximum CT resistance RCT in ohms at 75 °C at all ratios	Maximum excitation current at V_k in mA at all ratios.	Instrument security factor at all ratios
1	2	3	4	5	6	7	8	9	10
4	1.	Protection	400/1 200/1 100/1	- - -	PS PS PS	800	4	30	-
	2.	Metering	400/1 200/1 100/1	30 30 30	0.2s 0.2s 0.2s	-	-	-	5 or less 5 or less
	3.	Back up	400/1 200/1 100/1	- - -	PS PS PS	800	4	30	-
	4.	For owner's future use.	400/1 200/1 100/1	- - -	PS PS PS	800	4	30	-

REQUIREMENT FOR 145 KV CURRENT TRANSFORMERS OF RATIO

d) 200A-100/1-1-1-1A

No. of Cores	Core No.	Application	Current Ratio	Output burden in VA	Accuracy class as per IS: 2705	Minimum knee point voltage (V_k) at all ratios in volts.	Maximum CT resistance RCT in ohms at 75 °C at all ratios	Maximum excitation current at V_k in mA at all ratios.	Instrument security factor at all ratios
1	2	3	4	5	6	7	8	9	10
4	1.	Protection	200/1 100/1	- -	PS PS	800	4	30	-
	2.	Metering	200/1 100/1	30 30	0.2s 0.2s	-	-	-	5 or less 5 or less
	3.	Back up	200/1 100/1	- -	PS PS	800	4	30	-
	4.	For owners future use.	200/1 100/1	- -	PS PS	800	4	30	-

REQUIREMENT FOR 36KV CURRENT TRANSFORMERS OF RATIO

(a) 400-200A-100/1-1-1A

No. of Cores	Core No.	Application	Current Ratio	Output burden in VA	Accuracy class as per IS: 2705	Minimum knee point voltage (V_k) at all ratios in volts.	Maximum CT resistance RCT in ohms at 75 °C at all ratios	Maximum excitation current at V_k in mA at all ratios.	Instrument security factor
1	2	3	4	5	6	7	8	9	10
3.	1	Protection	400/1 200/1 100/1	- - -	PS PS PS	400	5.0	25	
	2.	Metering	400/1 200/1 100/1	30 30 30	0.2s 0.2s 0.2s	-	-	-	5 or less 5 or less 5 or less
	3.	Protection	400/1 200/1 100/1	- - -	PS PS PS	400	5.0	25	-

REQUIREMENT FOR 36KV CURRENT TRANSFORMERS OF RATIO

(b) 800-400-200A/1-1-1A

No. of Cores	Core No.	Application	Current Ratio	Output burden in VA	Accuracy class as per IS: 2705	Minimum knee point voltage (V_k) at all ratios in volts.	Maximum CT resistance RCT in ohms at 75 °C at all ratios	Maximum excitation current at V_k in mA at all ratios.	Instrument security factor
--------------	----------	-------------	---------------	---------------------	--------------------------------	--	--	--	----------------------------

1	2	3	4	5	6	7	ratios	9	10
3	1	Protection	800/ 1 400/1 200/1	- - -	PS PS PS	450	10	40	
	2.	Metering	800/1 400/1 200/1	30 30 30	0.2s 0.2s 0.2s	-	-	-	5 or less 5 or less 5 or less
	3.	Protection	800/1 400/1 200/1	- - -	PS PS PS	450	10	40	-

**REQUIREMENT FOR 36KV CURRENT TRANSFORMERS OF RATIO
(b) 800-400-200A/1-1-1-1A**

No. of Cores	Core No.	Application	Current Ratio	Output burden in VA	Accuracy class as per IS: 2705	Minimum knee point voltage (V _k) at all ratios in volts.	Maximum CT resistance RCT in ohms at 75 °C at all ratios	Maximum excitation current at V _k in mA at all ratios.	Instrument security factor
1	2	3	4	5	6	7	8	9	10
4	1	Protection	800/ 1 400/1 200/1	- - -	PS PS PS	450	10	40	
	2.	Metering	800/1 400/1	30 30	0.2s 0.2s	-	-	-	5 or less 5 or less

			200/1	30	0.2s				5 or less
	3.	Protection	800/1 400/1 200/1	- - -	PS PS PS	450	10	40	-
	4	Protection	800/1 400/1 200/1	- - -	PS PS PS	450	10	40	-

**REQUIREMENT FOR 36KV CURRENT TRANSFORMERS OF RATIO
(b) 800-400-200A/1-1A (NCT)**

No. of Cores	Core No.	Application	Current Ratio	Output burden in VA	Accuracy class as per IS: 2705	Minimum knee point voltage (V _k) at all ratios in volts.	Maximum CT resistance RCT in ohms at 75 °C at all ratios	Maximum excitation current at V _k in mA at all ratios.	Instrument security factor
1	2	3	4	5	6	7	8	9	10
2	1	Protection	800/ 1 400/1 200/1	- - -	PS PS PS	450	10	40	
	2	Protection	800/1 400/1 200/1	- - -	PS PS PS	450	10	40	-

**REQUIREMENT FOR 36KV CURRENT TRANSFORMERS OF RATIO
(b) 1200-600-300A/1-1A (NCT)**

No. of Cores	Core No.	Application	Current Ratio	Output burden in VA	Accuracy class as per IS: 2705	Minimum knee point voltage (V_k) at all ratios in volts.	Maximum CT resistance RCT in ohms at 75 °C at all ratios	Maximum excitation current at V_k in mA at all ratios.	Instrument security factor
1	2	3	4	5	6	7	8	9	10
2	1	Protection	1200/1 600/1 300/1	- - -	PS PS PS	1200	5.0	40	
	2	Protection	1200/1 600/1 300/1	- - -	PS PS PS	1200	5.0	40	

ANNEXTURE – B.

CALLIBRATION STATUS OF TESTING EQUIPMENTS AND INSTRUMENTS / METERS

Name of the	Meters & Equipm	Date of Calibr	Due Date of Calibrati	Name of the Calibrat	Whether Calibrati-ng Agency is	Whether documen-ts relating to Govt.	Whether the meters / equipmen-ts	Whether the calibrating agency has put	Whether green sticker or Blue Sticker or	Inspite of imposed limitations, whether the particular meter / equipment can still be used ?	Re-marks
-------------	-----------------	----------------	-----------------------	----------------------	--------------------------------	--------------------------------------	----------------------------------	--	--	--	----------

Test	ents required for the corresponding test with range accuracy, make & Sl.No.	ation	on	i- ng Agency	Govt. approved	approval of the calibrating Agency furnished	fulfill the accuracy class as per calibration report	any limitation towards the use of the particular meter / equipment. If yes state the limitations.	Yellow Sticker has been affixed on the body of the particular equipment / meter. State the colour of the affixed sticker	Justify its use for corresponding test (s)	
1	2	3	4	5	6	7	8	9	10	11	12

Signature of the tenderer with seal & date

ANNEXURE 6 C
CHECK-LIST TOWARDS TYPE TEST & SPECIAL TEST REPORTS

Name of the Type Test & special test	Date of Test.	Name of the Laboratory where the Test has been conducted	Whether the Laboratory is Government approved	Whether the Test report is valid as per Cl.No. 6.1 of TS	Whether the copy of test report in complete shape alongwith drawings etc. furnished or not ?	Whether the tested Current Transformers fulfill the technical requirements as per TS	If the tested Current Transformer does not fulfill the technical requirements as per this specification, whether the bidder agrees to conduct the particular type test again at their own cost	Remarks

							without any financial liability to OPTCL in the presence of OPTCL representative(s) within the specified delivery period.	
1	2	3	4	5	6	7	8	9

Signature of the Tenderer with seal and date
ANNEXURE 6D

Requirements for 420 kV current transformers

No. of cores	Core No.	Application	Current ratio	Output burden in VA	Accuracy class as per IEC 185	Minimum knee point voltage V_k corresponding to tap position in Volts	Maximum CT resistance R_{CT} in Ω corresponding to tap position	Maximum excitation Current at V_k in mA corresponding to tap position	Remarks
5	1	Bus differential Check	2000/1 1000/1	PS PS	2000 1000	10 5	30 on 2000/1 tap 60 on 1000/1 tap	
	2	Bus differential Main	2000/1 1000/1	PS PS	2000 1000	10 5	30 on 2000/1 tap 60 on 1000/1 tap	
	3	Metering	2000/1 1000/1 500/1	60 60 60	0.2s 0.2s 0.2s	10 5 2.5	
	4	Transformer / line Protection	2000/1 1000/1 500/1	PS PS PS	4000 2000 1000	10 5 2.5	30 on 2000/1 tap 60 on 1000/1 tap 120 on 500/1 tap	
	5	Transformer back up /	2000/1 1000/1	PS PS	4000 2000	10 5	30 on 2000/1 tap 60 on 1000/1 tap	

	line Protection	500/1	...	PS	1000	2.5	120 on 500/1 tap	
--	--------------------	-------	-----	----	------	-----	------------------	--

REMARKS: THE BIDDERS ARE ALSO TO FILL-UP THE GTP FOR 400 KV CT'S AS PER THE STANDARD FORMAT OF OPTCL MENTIONED ABOVE FOR OTHER CLASS CT,S. SAME GTP TO BE FILLED-UP.

ODISHA POWER TRANSMISSION CORPORATION LIMITED

OFFICE OF THE SR. GENERAL MANAGER,
CENTRAL PROCUREMENT CELL,
JANAPATH, BHUBANESWAR – 751022.

TECHNICAL SPECIFICATION FOR ISOLATORS

400KV SINGLE ISOLATOR WITH 1 EARTH SWITCH

400KV SINGLE ISOLATOR WITH 2 EARTH SWITCH

220KV SINGLE ISOLATOR WITHOUT EARTH SWITCH

220KV SINGLE ISOLATOR WITH EARTH SWITCH

220 KV TANDEM ISOLATOR

132 KV DOUBLE ISOLATOR WITH EARTH SWITCH

132 KV SINGLE ISOLATOR WITH EARTH SWITCH

132 KV SINGLE ISOLATOR WITHOUT EARTH SWITCH

132 KV TANDEM ISOLATOR

33 KV DOUBLE ISOLATOR WITH EARTH SWITCH

33 KV SINGLE ISOLATOR WITHOUT EARTH SWITCH

1. TECHNICAL PARTICULARS OF 400 kV,220 kV,132 kV & 33 KV ISOLATOR

	Type:	400 kV	220 kV	132 kV	33 kV
1	Main switch	Double end break centre post rotating, gang operated			
2	Service	Outdoor			
3	Applicable standard	IS : 9921 / IEC-62271-102			
4	No. of Phases	3 phase			

5	Design Ambient temperature	50°C			
6	Type of operation	Electrically Ganged	Mechanically Ganged		
7	Rated voltage (kV)	In KV	In KV	In KV	In KV
	a) Nominal	400	220	132	33
	b) Maximum	420	245	145	36
8	Rated current (Amps)	3150	2000	1250	1250
9	Short time current for 3 sec. (kA)	63	40	31.5	25
10	Rated requency	50 HZ \pm 5%			
11	System earthing	Effectively earthed			
12	Temperature rise	As per relevant IS/IEC standards			
13	Lightening Impulse withstand voltage (kVp)				
	(a) Across Isolating distance	1425(+240)	1200	750	195
	(b) To earth	1425	1050	650	170
14	1 minute power frequency withstand voltage				
	a) Across Isolating distance	610	530	315	80
	b) To earth	520	460	275	70
15	Switching Impulse withstand voltage (kVp)				
	a) Across Isolating distance	900(+345)	-	-	-
	b) To earth	1050	-	-	-
16	Max. RIV for frequency between 0.5 MHz and 2 MHz (micro-volt)	1000 at 267kV	1000 at 156kV	500 at 92kV	-
17	Corona Extinction Voltage (kV)	320	-	-	-

	Type	400 kV	220 kV	132 kV	33 kV
18	Operating mechanism				
	a) Isolator	Motor	Motor	Motor	Motor
	b) Earth switch	Motor	Motor	Motor	Manual
19	Auxiliary voltage				
	a) Control & Inter lock	220V DC 80% to 110%			
	b) Motor voltage	3 Phase 415V AC 50Hz			
	c) Heater, lamp & socket	Single phase 240 V 50HZ			

20	Safe duration of overload				
	150% of rated current	5 minute			
	120% of rated current	30 minute			
21	Minimum creepage distance of insulator (mm)				
22	Mounting structure	Tubular	Tubular / Lattice	Lattice	Lattice
23	Operating time	Less than 12 secs			
24	Insulator Data				
	a) Bending Strength (kgf)	800	800	800	600
	b) Height (mm)	3650	2300	1500	508
	c) Bottom PCD (mm)	300	254	184	76
	d) No. of holes & hole dia	8x18	8x18	4x18	4xM12
	e) Top PCD	127	127	127	76
	f) No. of holes & hole dia	4xM16	4xM16	4xM16	4xM12
	g) Minimum creepage distance (mm) 25mm/kV	10500	6125	3625	900
25	Bus Bar height from Plinth level (mm)	8000	5900	4600	3700
26	Phase Spacing (mm)	7000	4500	3000	1500
27	Minimum clearances (mm)				
	a) Phase to Phase	4000	2100	1300	320
	b) Phase to earth	3500	2100	1300	320
	c) Sectional clearance	6500	5000	4000	3000

2. SCOPE

This specification provides for design, manufacturer, testing at manufacturer's Works and delivery, supervision of erection, commissioning (if required) of outdoor station type 400 kV/220kV /132kV /33kV, 3 phase triple pole double break electrically / mechanically gang operated center rotating type (Single / Double) Isolator with / without earth switches, with electrical interlock, insulators and complete in all respect with connectors, arcing horns, operating mechanism, auxiliary switches, indicating devices etc. as described hereinafter.

3. STANDARDS

Isolators covered by this specification shall conform to latest edition of IEC 62271-102 and IS: 9921 and unless specifically stated otherwise in this specification.

4. TYPE

- The Isolators shall be outdoor type with three phase suitable for electrical as well as manual operation and local/remote operation. They shall have crank and reduction gear mechanism.
- All Isolators offered shall be suitable for horizontal upright mounting on steel structures. Each pole unit of the Isolators and earth switches shall be of identical construction and mechanically linked for gang operation for Isolators upto 220kV. 400kV Isolators shall be individual pole electrical gang operated
- Each pole of the Isolator shall be provided with two sets of contacts to be operated in series and the moving contact blades shall rotate in horizontal plane.
- It should be suitable for continuous service at the system voltages specified herein. The Isolators shall be suitable to carry the rated current continuously and full short circuit current at site condition without any appreciable rise in temperature. These shall also be suitable for operation at 110% rated (normal) voltage.
- The Isolators shall be suitable for Isolating low capacitive / inductive currents of 0.7amp at 0.15 power factor. The isolators shall be so constructed that they don't open under the influence of short circuit conditions.
- The Isolators and earth switches are required to be used on electrically exposed installation and this should be taken into account while fixing the clearance between phases and between phase and earth.

5. MAIN CONTACTS

Isolator shall have heavy duty, self-aligning and high pressure line type contacts made of high conductivity, corrosion resistant, hard-drawn electrolytic copper. All copper contact points shall be silver plated to 25 micron thickness or more. Fixed contact should be of reverse loop type with adequate number of copper strips which shall be backed by powerful phosphor bronze/stainless steel springs.

The Isolator moving arm/blade shall be made out of high conductivity, corrosion resistant, hard-drawn electrolytic copper of proper length, thickness and contact/surface area for Isolators upto 220kV.

For 400kV Isolator, the moving arm shall be made out of High conductivity *aluminium* tube of outer diameter not less than 120 mm.

The dimensions of the contacts should conform to the drawing approved during type test. However the current density of the current carrying parts shall not be more than the values specified below.

Current Density in Amps/sq. mm

	<u>Tubes</u>	<u>Flats</u>
Copper	2.5	2.0
Aluminium	1.25	1.0

These fixed and moving contacts shall be able to carry the rated current continuously and the maximum fault current without any appreciable rise in temperature. The Isolator blades shall retain their form and straightness under all conditions of operation including all mechanical stress arising out of operation as well as under rated short circuit condition.

The Isolator shall be self-cleaning type so that when Isolator remains closed for long periods in a heavily polluted atmosphere, binding does not occur. No undue wear or scuffing shall be evident during the mechanical endurance tests.

Contacts and springs shall be designed so that adjustment of contact pressure shall not be necessary throughout the life of the isolator. Contact springs shall not carry any current and shall not lose their characteristics due to heating effects. Each contact or part of contacts shall be independently sprung so that full pressure is maintained on all contact at all times.

The live parts shall be designed to eliminate sharp joints, edges and other corona producing surfaces, where this is impracticable adequate corona rings made out of aluminium tubes shall be provided. Corona shields are not acceptable.

6. Base :

Each single pole of the isolator shall be provided with a complete galvanized steel base provided with holes and designed for mounting on a supporting structure. The base for 400/220/132 kV shall be made out of two channels of size 200x100 / 150x75 / 150x75 or more having thickness not less than 5mm. Base channel shall be rigid in construction and capable of taking all the loads like short circuit force, terminal load, wind load and vibration caused due to seismic / operation of Isolator. Leveling screws of adequate size shall be provided on either side of the base channel under the Insulator for the alignment of Isolator. For 33kV Isolator single base channel of size 100x50 can be provided.

The rotating insulator shall be mounted on a rotating post which shall have two ball bearings of suitable size and housed inside a bearing housing made out of aluminium alloy and greased for life. The distance between the bearings shall not be less than 200/150/125/70 mm for 400/220/132/33 kV respectively.

7. ARCING HORN AND GRADING HORN

Suitable arcing horn made of GI shall be provided on the fixed and moving contacts of Isolators if required. The contacts shall be of 'make before and break after' type.

8. ELECTRICAL INTERLOCK / MECHANICAL INTERLOCK

The Isolators shall be equipped with electrical interlock for interlocking with the associated circuit breakers and earth switch. The interlocking scheme shall be approved by OPTCL.

Suitable mechanical / constructional interlock shall be provided between Isolator and earth switch which should be rigid in construction and properly mounted to ensure reliable operation.

9. AUXILIARY SWITCHES

All isolators and earth switches shall be provided with 220V DC auxiliary switches for remote position indication on the control panel and for electrical interlocking with other equipment.

The auxiliary switch shall be provided with a minimum of auxiliary contacts-12 normally open and 12 normally closed and 10 normally open and 10 normally closed for earth switch.

The auxiliary switches and auxiliary circuits shall have a continuous current carrying capacity of at least 10 Amps. Auxiliary switches shall not be used as limit switches.

Details of make, rating and type of auxiliary switch along with the type test report shall be furnished in the offer.

10. EARTH SWITCH

a) Where earth switches are specified these shall include the complete operating mechanism and auxiliary contacts. The earth switch shall be operated by a separate mechanism.

b) The earth switches shall form an integral part of the isolator and shall be mounted on the base frame of the isolator.

c) Earth switches shall be only locally operated.

d) The earth switches shall be constructionally interlocked with the isolator so that the earth switches can be operated only when the isolator is open and vice versa. The constructional interlocks shall be built in construction of isolator and shall be in addition to the electrical interlocks. Suitable mechanical arrangement shall be provided for delinking electrical drive for manual operation.

e) Each earth switch shall be provided with flexible copper braids or any other improved design for connection to earth terminal. These braids shall have the same short time current carrying capacity as the earth blade.

f) The plane of movement and final position of the earth blades shall be such that adequate electrical clearances are obtained from adjacent live parts in the course of its movement between ON and OFF position.

g) Isolator design shall be such as to permit addition of earth switches at a future date. It should be possible to interchange position of earth switch to either side.

h) The earth switch should be able to carry the same fault current as the main blades of the Isolators and shall withstand dynamic stresses.

i) 400 kV earth switches shall be of double movement type (telescopic) i.e. it has to rotate 90 degree in first movement and then lift upwards to make a contact which ensures a reliable and jerk free operation of the earth switch. Proper locking arrangement shall be provided such that the earth switch shall be locked after lifting upwards to avoid opening during short circuit.

11. OPERATING MACHANISM

- a) The bidder shall offer motor operated Isolators and earth switches except for the earth switches of 33 kV Isolator which shall be manual operated with crank and reduction gear mechanism.
- b) *Control cabinet/operating mechanism box shall be made of cast aluminium / aluminum sheet of adequate thickness (minimum 3 mm) for 33 KV,132KV and stainless steel (grade-316) of minimum thickness 1.6 mm for 400 KV and 220 KV.*
- c) The enclosure shall be painted / powder coated to the Shade no 631 of IS:5(for aluminium enclosure)
- d) The enclosures of the operating mechanism Box shall conform to the degree of protection IP- 55
- e) A "Local/Remote" selector switch and a set of open/ close push buttons shall be provided on the control cabinet of the isolator to permit its operation through local or remote push buttons.
- f) For 400kV Isolators, Gang / Individual switch shall be provided.
- g) Provision shall be made in the control cabinet to disconnect power supply through suitable MCBs to prevent local/remote power operation.
- h) All control switches shall be of MCB/rotary switch type and Toggle/piano switches shall not be accepted.
- i) Motor shall be an AC motor as per IS:325. Motors rated 373 watt and above shall be used. The motor shall withstand without damage stalled torque for atleast 3 times the time lag of tripping device.
- j) Suitable reduction gearing shall be provided between the motor and the drive shaft of the isolator. The mechanism shall stop immediately when motor supply is switched off.
- k) Manual operation facility (with handle) should be provided with necessary interlock to disconnect motor.
- l) Gear should be of forged material suitably chosen to avoid bending/jamming on operation after a prolonged period of non operation. Also all gear and connected material should be so chosen/surface treated to avoid rusting. The Gears shall be lubricated for life with graphite or better quality non-drawing and non-hardening type grease.
- m)The test report for blocked rotor test of motor shall be submitted
- n) Only stranded copper conductor shall be used for wiring. Minimum size of the conductor for control circuit wiring shall be 2.5 sq.mm Copper.
- o) The operating mechanism shall be located such that it can be directly mounted on the support structure.
- p) Suitable anti condensation heaters with the provision of thermostat shall be provided.
- q) Each operating mechanism shall be provided with 1100V grade stud type terminal block of Polyamide material. (OAT-6 for non-disconnecting type and OAT 6T for disconnecting type of Elmex) / Connectwell (Equivalent). At least 20% spare terminals shall be provided.

- r) A light fixture suitable for a 240 V CFL tube light shall be provided in each of the motor operated mechanism & shall be door operated type.
- s) A 240V, single phase, 50 Hz, 15 amp AC plug and socket shall be provided in the cabinet with ON-OFF switch for connection of hand lamps.
- t) A position indicator to show the isolator is in ON or OFF position to be provided at a suitable location.

12. OPERATION

The main Isolator and earth switches shall be individual pole electrically ganged motor operated for 400 kV and mechanically gang operated in case of 220/132/33 kV. The operating mechanism of the three poles shall be well synchronized and interlocked.

The Isolator blades shall be in positive continuous control throughout the entire cycles of operation. The operating rods and pipes shall be rigid enough to maintain positive control under most adverse conditions and to withstand all torsional and bending stresses arising from operation. Operation of the switches at any speed should not result in improper functioning, in displacement of parts / machines after final adjustment has been made. All holes in cranks, linkages etc. having moving pins shall be drilled and fitted accurately so as to prevent slackness and lost motion.

The isolator and earth switches shall be provided with "dead center mechanism" to prevent accidental opening by wind, vibration, short circuit forces or movement of the support structures.

13. DESIGN, MATERIALS AND WORKMANSHIP

- The live parts shall be designed to eliminate sharp points, edges and similar corona producing surfaces, where this is impracticable, adequate rings made out of aluminium tubes shall be provided. Corona shields are not acceptable.
- All ferrous metal parts shall be hot dip galvanized, as per IS 2629. All metal parts shall be of such materials or treated in such a way so as to avoid rust, corrosion and deterioration due to continued exposure to atmosphere and rain.
- Bolts, screws and pins shall be provided with standard locking device viz. Locknuts, spring washers, keys etc. and when used with current carrying parts, they shall be made of copper silicon or other high conductivity and wear resistant alloys.
- The switches should not need lubrication of any parts except at very long interval of five year minimum.

14. PROTECTIVE COATINGS

All ferrous parts including bolts, nuts and washers of the switches assembly shall be galvanised to withstand at least six one minute dips in copper sulphate solution of requisite strength (Preece dip tests) except the threaded portions which should withstand four dips.

15. INSULATORS

- Support insulators for all type of isolators shall be of solid core type.

- The insulator shall be made of homogeneous and vitreous porcelain of high mechanical and dielectric strength. It shall have sufficient mechanical strength to sustain electrical and mechanical loading on account of wind load, short circuit forces etc. Glazing of the porcelains shall be of uniform dark brown colour with a smooth surface arranged to shed away rain water.
- The porcelain shall be free from laminations and other flaws or imperfections that might affect the mechanical or dielectric quality. It shall be thoroughly vitrified, tough and impervious to moisture.
- The porcelain and metal parts shall be assembled in such a manner and with such material that any thermal differential expansion between the metal and porcelain parts throughout the range of temperature specified in this specification shall not loosen the parts or create under internal stresses which may affect the mechanical or electrical strength or rigidity. The assembly shall not have excessive concentration of electrical stresses in any section or across leakage surfaces. The cement used shall not give rise to chemical reaction with metal fittings.
- The insulator shall be suitable for water washing by rain or artificial means in service condition.
- Profile of the insulator shall also conform to IEC-815.
- Caps to be provided on top of the insulator shall be of high grade cast iron or malleable steel casting. It shall be machine faced and hot dip galvanized. The holes shall be suitable for bolts with threads having anti corrosive protection. The effective depth of threads shall not be less than the nominal diameter of the bolt. The cap shall be so designed that it shall be free from visible corona and shall have radio interference level within 500 micro volts.
- Casting shall be free from blow holes cracks and such other defects.

16. Name plate :

Isolator, earth switches and their operating devices shall be provided with name plate. The name plate shall be weather proof and corrosion proof. It shall be mounted in such a position that it shall be visible in the position of normal service and installation. It shall carry the following information's duly engraved or punched on it. Name plate shall be bilingual i.e. in English & Oriya

A. Isolator Base

Name : OPTCL
 Name of manufacturer –
 Type Designation –
 Manufacturers serial No. –
 Rated voltage –
 Rated normal current –
 Rated short time current (rms) and duration –
 Rated short time peak current (KAP)
 Weight

B. Earthing Switch

Name : OPTCL
 Name of manufacturer –
 Type Designation –
 Manufacturers serial No. –
 Rated voltage –

Rated normal current –
Rated short time current (rms) and duration
Rated short time peak current (KAP)
Weight

C. Operating Device

Name – OPTCL
Name of manufacturer –
Type Designation –
Reduction gear ratio –
AC motor

- i) Rated auxiliary voltage
 - ii) Starting current
 - iii) Designation of AC motor as per I.S 4722/325
 - iv) Starting torque at 80% of supply voltage
 - v) Over travel in degrees after cutting off supply
Total operating time in seconds
- i) Close operation – Electrical
 - ii) Open operation – electrical
Open operation – manual

All components shall be given adequate treatment of climate proofing as per IS:3202 so as to withstand corrosive and severe service conditions.

All metal parts not suitable for painting such as structural steel, pipes, rods ,levers, linkages, nuts and bolts used in other than current path etc. shall be hot dip galvanized as per IS -2629

Complete details of painting, galvanizing and climate proofing of the equipment shall be furnished in the offer.

17. TESTS

Type Tests

Isolators offered, shall be fully type tested as per the relevant standards. The Bidder shall furnish one set of the following valid type test reports for their different type of offered Isolators along with the offer. The Purchaser reserves the right to demand repetition of some or all the type tests in the presence of purchaser's representative. For this purpose the Bidder may quote unit rates for carrying out each type test and this will be taken during bid price evaluation, if required.

The following type test reports shall be submitted for evaluation purpose. In the absence of any one of the following, the bid is liable to reject.

- a) Short time withstand & peak withstand current test for Isolator & Earth Switch.
- b) Power frequency (Dry & Wet), Lightning Impulse dry withstand Test
- c) Radio interference voltage (RIV) test
- d) Mechanical endurance Test & Terminal load test
- e) Degree of Protection test (IP-55)
- f) Corona Test (For 400kV Only)
- g) Temperature rise test
- h) Blocked rotor test

During type tests the isolator shall be mounted on its own support structure or equivalent support structure and installed with its own operating mechanism to make the type tests representative. Drawing of equivalent support structure and mounting

arrangements shall be furnished for Purchaser's approval before conducting the type tests.

The type tests shall be conducted on the isolator along with approved insulators and terminal connectors.

Mechanical endurance test shall be conducted on the main switch as well as earth switch of one isolator of each voltage class for M0 class (1000 operations) for Isolators upto 220kV. 400kV Isolators shall be tested for extended mechanical endurance test, M2 class (10000 operations) as per IEC 62271-102 which shall be tested at any NABL accredited independent laboratory like CPRI/ERDA.

Acceptance and Routine Test :

All acceptance and routine test as stipulated in the relevant standards shall be carried out by the supplier in presence of Purchaser's representative.

Mechanical operation test (routine test) shall be conducted on isolator (main switch and earth switch) at the supplier's works as well as purchaser's substation site.

Immediately after completion of the routine test, the supplier shall give 20 days' advance intimation along with routine test certificates, valid calibration reports from Govt. approved test laboratories for the equipments, instruments to be used during testing for scrutiny by the purchaser to enable him to depute his representative for witnessing the tests.

If there will be any discrepancies in the routine test certificates and calibration reports furnished by the manufacturer, then after settlement of the discrepancies only, purchaser's representative will be deputed for witnessing the tests.

Special tests proposed to be conducted (if decided to conduct) as type test on isolators, are given at Annexure. These special type test charges shall be quoted along with all other type tests as per relevant IEC standard and these charges shall be included in the total bid price.

Test certificates of various raw materials and bought out items including but not limited to the following shall be furnished at the time of routine tests.

- a) Chemical analysis of copper alongwith a copy of excise certificate indicating genuine source of procurement of electrolytic grade copper.
- b) Aluminium extrusions
- c) Aluminium ingots & castings
- d) Fasteners
- e) Insulators
- f) Motor
- g) Gears
- h) Auxiliary switch
- i) Limit switch
- j) Overload / single phase preventer
- k) Interlocking devices
- l) Terminal block

18. INSPECTION

- i) The Purchaser shall have access at all times to the works and all other places of manufacture, where the Isolators, earth switches and associated equipment are being manufactured and the supplier shall provide all facilities for unrestricted inspection of the

works of raw materials manufacture of all the accessories and for conducting necessary tests as detailed herein.

ii) The supplier shall keep the purchaser informed in advance of the time of starting of the progress of manufacture of equipment in its various stages so that arrangements could be made for inspection.

iii) No material shall be dispatched from its point of manufacture unless the material has been satisfactorily inspected and tested.

iv) The acceptance of any quantity of the equipment shall in no way relieve the supplier of his responsibility for meeting all the requirements of this specification and shall not prevent subsequent rejection if such equipment are later found to be defective.

63

19. QUALITY ASSURANCE PLAN

The Bidder shall invariably furnish following information along with his offer, failing which his offer shall be liable for rejection.

(i) Names of sub suppliers for raw materials, list of standards according to which the raw materials are tested, list of tests normally carried out on raw materials in presence of Supplier's representative, copies of test certificate

(ii) Information and copies of test certificates as in (I) and (ii) above in respect of bought out accessories.

(iii) List of manufacturing facilities available

(iv) Level of automation achieved and list of areas where manual processing still exists.

(v) List of areas in manufacturing process, where stage inspections are normally carried out for quality control and details of such tests and inspections.

(vi) List of testing equipments with calibration certificates from Govt. approved test house available with supplier for final testing equipment and test plant limitation if any, vis-à-vis the type, special acceptance and routine test specified in the relevant standards. These limitations shall be very clearly brought out in the specified test requirements.

The supplier shall within 30 days of placement of order, submit following information to the purchaser.

i) List of raw material as well as bought out accessories and the names of sub-suppliers selected from the lists furnished along with offer.

ii) Type test certificates of the raw material and both bought out accessories.

iii) Quality Assurance Plan (QAP) with hold points for purchaser's inspection.

20. DOCUMENTATION

All drawings shall conform to relevant international standards organisation (ISO). All drawings shall be in ink and suitable for micro filming. All dimensions and data shall be in S.I. Units.

List of Drawings and Documents

The Bidder shall furnish four sets of following drawings / documents along with his offer.

a) General outline and assembly drawings of the dis-connector operating mechanism, structure, insulator and terminal connector.

b) Sectional views and descriptive details of items such as moving blades, contacts, arms contact pressure, contact support bearing housing of bearings, balancing of heights, phase coupling pipes, base plate, operating shaft, guides, swivel joint operating mechanism and its components etc.

c) Loading diagram

d) Drawings with structure for the purpose of type tests.

- e) Name plate.
- f) Schematic drawing.
- g) Type test reports.
- h) Test reports, literature, pamphlets of the bought out items and raw material.

The supplier shall within 2 weeks of placement of order submit four sets of final versions of all the above said drawings for Purchaser's approval. The purchaser shall communicate his comments / approval on the drawings to the supplier. The supplier shall, if necessary, modify the drawings and resubmit four copies of the modified drawings for Purchaser's approval within two weeks from the date of comments. After receipt of approval the supplier shall within three weeks submit 5 prints and soft copies in two CD of the approved drawings for purchaser's use.

Six sets of the type test reports, duly approved by the Purchaser shall be submitted by the supplier for distribution, before commencement of supply Adequate copies of acceptance and routine test certificates, duly approved by the Purchaser shall accompany the despatched consignment.

The manufacturing of the equipment shall be strictly in accordance with the approved drawings and no deviation shall be permitted without the written approval of the purchaser. All manufacturing and fabrication work in connection with the equipment prior to the approval of the drawing shall be at the supplier risk.

21. INSTRUCTION MANUALS :

Five copies of the erection, operation and maintenance manuals in English be supplied for each type of Isolator one month prior to despatch of the equipment. The manual shall be bound volumes and shall contain all drawings and information required for erection, operation and maintenance of the Isolator including but not limited to the following particulars.

- (a) Marked erection prints identifying the component parts of the Isolator as shipped with assembly drawings.
- (b) Detailed dimensions and description of all auxiliaries.
- (c) Detailed views of the insulator stacks, metallics, operating mechanism, structure, interlocks, spare parts etc.

22. PACKING AND FORWARDING.

The equipment shall be packed in crates suitable for vertical / horizontal transport, as the case may be and suitable to withstand handling during transport and outdoor storage during transit. The supplier shall be responsible for any damage to the equipment during transit, due to improper and inadequate packing. The easily damageable material shall be carefully packed and marked with the appropriate caution symbols. Wherever necessary, proper arrangement for lifting, such as lifting hooks etc. shall be provided. Any material found short inside the packing cases shall be supplied by supplier without any extra cost.

Each consignment shall be accompanied by a detailed packing list containing the following information:

- (a) Name of the consignee.
- (b) Details of consignment.
- (c) Destination.
- (d) Total weight of consignment.
- (e) Handling and unpacking instructions.
- (f) Bill of material indicating contents of each package.

The supplier shall ensure that the bill of material is approved by the purchaser before dispatch.

23. SUPERVISION OF ERECTION TESTING & COMMISSIONING (ET&C)

Purchaser proposes to utilize the services of the supplier for supervision of testing and commissioning of the equipment being supplied by him, if it is required. For this purpose, the supplier should make available the services of trained personnel (Engineers) who shall correct in the field, any errors or omissions in order to make the equipment and material properly perform in accordance with the intent of this specification.

The Engineer shall also instruct the plant operators in the operation and maintenance of the commissioned equipment. The supplier shall be responsible for any damage to the equipment on commissioning the same, if such damage results for the faulty or improper ET&C.

Purchaser shall provide adequate number of skilled / semi skilled workers as well as general tools and equipment and cranes required for equipment erection, at his own expenses. Apart from the above, the Purchaser shall not be responsible for providing any other facilities to the supplier. Special tools if required for erection and commissioning shall be arranged by the supplier at his cost and on commissioning these shall be supplied to the purchaser free of cost for future use.

24. QUATITITY AND DELIVERY REQUIREMENTS :

The scope of supply shall include a supply of 2.5% extra quantity of galvanised bolts, nuts, washers, split pins, cotter pins and such other small loose items free of cost.

ANNEXURE
(Isolators)

LIST OF SPECIAL TESTS TO BE CARRIED OUT
(IF DECIDED BY THE PURCHASER)

Sl. No.	Name of the Test	Standard to which it conforms.
1.	Test for visible Corona and Radio interference voltage (RIV) on Isolators and terminal connector	NEMA Pub No. 107-1964 ISRI Pub No. 1-1972
2.	Tests on insulators	IS-2544 IEC. 168
3.	Tests on terminal connectors	IS:5561
4.	Tests on galvanised components	IS:2633
5.	Stalled torque test on motor operating mechanism	At 110% of supply voltage

LIST OF MANDATORY SPARES

Sl. No	Item	Quantity
1.	Copper contact fingers for male and female contact per Isolator	2sets each for each Type of Isolators (400/220/132/33KV)
2.	Relay, power contactors, MCBs, Rotary switches for electrical control circuit per Isolator (Indicate the nos of relay, power contactors, MCBs, Rotary switches used in the electrical circuit of each type of isolators)	2sets for each Type of Isolators
3.	Support insulator stack for one pole of the isolator	2 stacks for each type of Isolators
4.	Terminal pad	2 Nos. for each type of isolators
5.	Limit switch and Auxiliary switch per Isolator (Indicate the nos of each switch used in each type of isolators)	2sets for each type of Isolators
6.	Terminal connectors per Isolator	2 sets for each type of isolators.

