

ଓଡ଼ିଶା ବିଦ୍ୟୁତ ଶକ୍ତି ସଂଚାରଣ ନିଗମ ଲିଃ.

ODISHA POWER TRANSMISSION CORPORATION LIMITED OFFICE OF THE GENERAL MANAGER (ELECTRICAL) E.H.T. (O&M) CIRCLE, BURLA

e-mail: ehtm.cle.brl@optcl.co.in CIN: U401020R2004SGC007553

E-TENDER CALL NOTICE NO. BRL- 06/2023-24

For and on behalf of ODISHA POWER TRANSMISSION CORPORATION LTD General Manager, EHT (O&M) Circle, OPTCL, Burla, invites E-Tenders having EHT/ HT license holder having valid IT, PAN, GST Registration certificate in single part bidding system for "Construction of PCC & Metal spreading works of 132KV switchyard at 132/33KV Grid Sub-Station, Rourkela under EHT (O&M) Division, Rourkela". The interested bidders would be required to enroll themselves on the tender portal www.tenderwizard.com/OPTCL. Complete set of bidding documents are available at www.tenderwizard.com/OPTCL from 10.06.2023 (10:00 Hrs) up to 03.07.2023 Interested Bidder may visit OPTCL's official (17:00 Hrs). http://www.optcl.co.in and www.tenderwizard.com/OPTCL for detail specification.

N.B:- All subsequent addendums/corrigendum to the tender shall be hosted in the OPTCL's official website http://www.optcl.co.in and www.tenderwizard.com/OPTCL only.

GENERAL MANAGER (Elect.) EHT (O&M) CIRCLE, BURLA



NOTICE INVITING TENDER ଓଡ଼ିଶା ବିଦ୍ୟୁତ ଶକ୍ତି ସଂଚାରଣ ନିଗମ ଲିଃ.

ODISHA POWER TRANSMISSION CORPORATION LTD., OFFICE OF THE GENERAL MANAGER (ELECTRICAL) E.H.T. (0&M) CIRCLE, BURLA

E-TENDER NOTICE NO- BRL-06/2023-24.

For and on behalf of the ODISHA POWER TRANSMISSION CORPORATION LTD., the undersigned invites bids under Single part bidding system in e- tendering mode only as per the following details.

Date of online submission of e-

tender paper

Last date & Time of Receipt of

documents

Date of opening

From 10.06.2023 to 03.07.2023 upto 17:00hrs. at

EHT (O&M) Circle, Burla

On or before 04.07.2023 up to 13:00hrs. at EHT

(O&M) Circle, Burla

- On 04.07.2023 at 15:30 hrs.

Sl. No	Tender Specificati on No.	Location Details.	INDIAN RUPEES			Last date of
			Earnest Money Deposit.	Cost of Tender Spec. Document (Including GST)	Tender Processi ng Fee.	submission & Date of opening of Tender.
1	E - Tender No. 06/2023- 24	132/33KV Grid Sub- Station, Rourkela under EHT (O&M) Division, Rourkela	1 % of quoted value	Rs.7080/- [Only in the shape of DD]	Rs. 2922/-	up to dt- 04.07.2023 (13:00 Hrs) and (04.07.2023 at 15:30 hrs.)

The bidders can view the tender documents from website free of cost.

The bidders who want to submit bid shall have to pay Rs 7080/- (Rupees Seven thousand eighty only non-refundable including GST @ 18%) towards the tender cost, in the form of Demand draft/Cash only, drawn in favour of M/s General Manager, EHT (0&M) Circle, OPTCL, Burla at the office of the undersigned on or before the last date & time of submission of tender.

The bidders shall have to submit non refundable amount of Rs. 4397/- (Rupees

four thousand three hundred ninety seven only) towards the tender processing fee through **e-payment** mode. Tender processing fee acknowledgement is to be submitted & tender cost at the office of the undersigned on or before the last date & time of submission of tender.

The bidders shall scan the Demand Draft/Pay order/ Bank guarantee towards Tender Cost and tender processing fee acknowledgement and upload the same in the prescribed form in .gif or .jpg format in addition to sending the original as stated above.

The prospective bidders are advised to register their user ID, Password, company ID from website www.tenderwizard.com/OPTCL by clicking on hyper link "Register Me".

Any clarifications regarding the scope of work and technical features of the tender can be had from the undersigned during office hours.

Minimum qualification criteria of bidders: AS STIPULATED IN SECTION-II, (G.T.C.C) OF THE TENDER SPECIFICATION.

The Quantum of Work as in Table below

"Construction of PCC & Metal spreading works of 132KV switchyard at 132/33KV Grid Sub-Station, Rourkela under EHT (O&M) Division, Rourkela."

GENERAL MANAGER (ELECT.) E.H.T. (O&M) CIRCLE, BURLA

TECHNICAL SPECIFICATION FOR CONSTRUCTION OF PCC & METAL SPREADING WORKS OF 132KV SWITCHYARD AT 132/33KV GRID SUB-STATION, ROURKELA UNDER EHT (O&M) DIVISION, ROURKELA.

Description		Qty.
Picking of 20/40mm hard granite metals from switchyard area &	Sqm	4400
stacking of the same as per instruction of Engineer-in-Charge.		
Earthwork excavation in ordinary soil within initial lead of 50m	Cum	880
& initial lead of 1.5m including rough dressing & breaking clods		
to maximum 5cm to 7cm and leveling the bed & depositing the		
excavated soil away from working area outside switchyard up to		
100m as directed by the Engineer-in-charge.		
Filling of foundation & plinth with sand well watered & rammed	Cum	330
with stacking for measurement including all cost, carriage,		
royalty and all other taxes etc. and supply of labour & T&P as		
per direction of Engineer-in-charge.		
Providing and laying of Plain Cement Concrete (1:4:8) with	Cum	330
40mm size Hard Granite metal including cost, conveyance,		
Engineer-in-charge.		
Supply and stacking of new 20mm size black hard granite	Cum	308
machine broken chips.		
Spreading of old 40mm and new 20mm size black hard granite	Cum	440
machine broken chips on the PCC for metalling of switchyard as		
	Picking of 20/40mm hard granite metals from switchyard area & stacking of the same as per instruction of Engineer-in-Charge. Earthwork excavation in ordinary soil within initial lead of 50m & initial lead of 1.5m including rough dressing & breaking clods to maximum 5cm to 7cm and leveling the bed & depositing the excavated soil away from working area outside switchyard up to 100m as directed by the Engineer-in-charge. Filling of foundation & plinth with sand well watered & rammed with stacking for measurement including all cost, carriage, royalty and all other taxes etc. and supply of labour & T&P as per direction of Engineer-in-charge. Providing and laying of Plain Cement Concrete (1:4:8) with 40mm size Hard Granite metal including cost, conveyance, royalty etc and supply of labour & T&P as per direction of Engineer-in-charge. Supply and stacking of new 20mm size black hard granite machine broken chips.	Picking of 20/40mm hard granite metals from switchyard area & stacking of the same as per instruction of Engineer-in-Charge. Earthwork excavation in ordinary soil within initial lead of 50m & initial lead of 1.5m including rough dressing & breaking clods to maximum 5cm to 7cm and leveling the bed & depositing the excavated soil away from working area outside switchyard up to 100m as directed by the Engineer-in-charge. Filling of foundation & plinth with sand well watered & rammed with stacking for measurement including all cost, carriage, royalty and all other taxes etc. and supply of labour & T&P as per direction of Engineer-in-charge. Providing and laying of Plain Cement Concrete (1:4:8) with 40mm size Hard Granite metal including cost, conveyance, royalty etc and supply of labour & T&P as per direction of Engineer-in-charge. Supply and stacking of new 20mm size black hard granite machine broken chips. Spreading of old 40mm and new 20mm size black hard granite Cum machine broken chips on the PCC for metalling of switchyard as

10000 20 VZ **GENERAL MANAGER (ELECT.)**

E.H.T. (O&M) CIRCLE, BURLA