




Sl. No.	Particulars	Details
1	NIT No.	OTCN-04/2026-27
2	Type of Tender Limited/Open/E-Tender	Open
3	Scope of Work (Pl. furnish the detail/ broad scope of work)	furnished in Annexure-1
4	Location of Work: Sub-Station/ EHT Line (Particular Location)	132/33KV Grid Sub-Station Shamuka and 132/33KV Grid Sub-Station Nimapara
5	Scope of supply of materials: OPTCL/ Executing Agency (Detail to be furnished)	Executing agency to supply all the required materials like UPVC pipe,UPVC Elbow,UPVC TEE,UPVC Valve ,Cement ,Chips etc for masonry work etc.
6	Bid Validity Period (Days)	120 days from the date of opening of the tender
7	Submission of work order towards execution of similar works in Power Utilities for preceeding three years (as applicable)	Yes
8	Requirement of EHT/HT/Civil License/(Class/Type) for executing the work(Specify)	IT PAN, GSTIN Registration Certificate , Civil License,EHT/HT License
9	Brief Summary of Eligibility Criteria (Technical & Financial)	Civil License,EHT/HT License
10	Estimated Cost (Amount in Rs.)	Rs.2,12,778.00/-
11	Work Completion Period (Months/Days)	45 days
12	Basis of Estimate: Rate Contract/Schedule of Rate (Optional)	Market price
13	Tender Cost(Amount in Rs.)	Tender Cos-Rs.2,12,778.00/-Tender Paper Cost = Rs. 2,360.00 only(Incl. of GST) through DDs only in favour of EHT (O&M) Circle, OPTCL, Bhubaneswar payable at Bhubaneswar
14	Mode of Payment of Tender Cost(Demand Draft/NEFT)	Demand Draft
15	Tender Processing Fees (Incl. of GST) Amount in Rs.	Tender Paper Cost = Rs. 2,360.00 only(Incl. of GST) through DDs only in favour of EHT (O&M) Circle, OPTCL, Bhubaneswar payable at Bhubaneswar
16	Tender (Opening & Closing) Period (from DD/MM/YYYY to DD/MM/YYYY)	08.10.2026 to 21.10.2026(up to 12:00PM)
17	Date of Pre-Bid meeting (at the request of Bidders) --- Days before closing date	3
18	Issue of Offline/Online Tender documents (Bid Sheet/Tender documents) in complete shape (from DD/MM/YYYY to DD/MM/YYYY)	Issue of Only Offline Tender Documents From 08.10.2026 to 21.10.2026(upto 12:00PM Only) (During office hours from 10:00AM to 05:30PM)
19	Last date of submission of bid (Upto DD/MM/YYYY.... Hrs.)	up to 21.10.2026 and 02:00 PM


General Manager (Elect.)
EHT (O&M) Division
OPTCL, Puri

20	Date & time of opening of Techno-Commercial Bid of Tender(DD/MM/YYYY,Hrs.)	21.10.2026 at 03:00 PM
21	Date of opening of price bid of Tender(DD/MM/YYYY,Hrs.)	21.10.2026 at 03:15 PM
22	Bid Security or EMD Details/ Exemption Clause (if any)	Rs. 2,128.00 (Rupees Two Thousand One Hundred Twenty Eight)only through DDs only in favour of EHT (O&M) Circle, OPTCL, Bhubaneswar payable at Bhubaneswar
23	Performance Security requirement(...% & period of validity), if applicable	10% of Contract Value & validity for a period of 12 months from the date of completion of the work
24	Payment Terms : After completion / RA Bill based on JMC	After Completion
25	Guarantee Period (in months)	12 (twelve months) from the date of Completion
26	Liquidated damages /Penalty:	In case the contractor fails to execute by the stipulated completion date, penalty is chargeable @ a sum of half percent (i.e. 0.5 percent) of the contract price for each calendar week or part thereof of limited to maximum of 5% of cost (exclusive of GST) of contract value.
27	MSME related exemptions/ relaxations (if any):	As per OPTCL Norms
28	Contact Person details: Email id and Mobile No.)	ehm.div.puri@optcl.co.in


 General Manager (Elect.)
 EHT (O&M) Division
 OPTCL, Puri

ANNEXURE-1					
SCOPE OF WORK					
NIT NO.OTCN-04/2026-27					
Sl. No.	Description of Item	Unit	Qty of GSS Shamuka	Qty of GSS Nimapara	Total Qty
1	1 1/2" inch UPVC pipe(SCH-80) make- Ashirbad	Mtr	127	239	366
2	3/4" inch UPVC pipe(SCH-80) make- Ashirbad	Mtr	80	79	159
3	1 1/2"*3/4" TEE UPVC(SCH-80) make- Ashirbad	Pcs	60	22	82
4	1 1/2"*3/4" Elbow UPVC(SCH-80) make- Ashirbad	Pcs	7	6	13
5	1 1/2" Ball Valve UPVC(SCH-80) make- Ashirbad	Pcs	6	4	10
6	3/4" TEE UPVC(SCH-80) make- Ashirbad	Pcs	10	15	25
7	1 1/2" Elbow UPVC(SCH-80) make- Ashirbad	Pcs	5	20	25
8	3/4" Elbow UPVC(SCH-80) make- Ashirbad	Pcs	10	10	20
9	3/4" * 1/2" Brass Elbow (SCH-80) make- Ashirbad	Pcs	8	8	16
10	3/4"Ball Valve UPVC(SCH-80) make- Ashirbad	Pcs.	10	0	10
11	3/4" Offset Bend UPVC(SCH-80) make- Ashirbad	Pcs.	5	0	5
12	PVC Tap	Pcs	8	10	18
13	Solvent	Ltr	1	1	2
14	1 1/2" GI Clamp	Pcs	20	40	60
15	3/4" GI Clamp	Pcs	11	10	21
16	Concrete Nail	Pkt	1	1	2
17	Masonry work for excavated area & dismantled masonry work area as and where required as per instruction of Engineer in charge of the substation with supply of all materials of good quality of 20mm machine broken granite chips , good quality river sand,Cement , T&P to form M15 Grade concrete in ratio 1:2:4 for covering excavated area both inside and outside fence after laying UPVC water pipe line & for provision of PVC Tap with supply of good quality river sand, cement, 1st Class KB Bricks , T&P for renovation of retaining/earth pit chamber after dismantling the same & instalation of UPVC water pipe line therein.	Lot	1	1	2
18	Supply of labour for excavation of existing concrete/earth, picking of 20/40 mm HG metal in the switch yard, fitting and laying of UPVC water pipe line with accessories within existing concrete area outside Switchyard & metal spread area of S/Y, covering the pipe with PCC/metals after installation in complete shape as per specification & instruction of EIC				
19	Unskilled	Man day	15	15	30
20	High skilled	Man day	15	10	25
21	Supervision charges	Lot	1	1	2


General Manager (Elect.)
 EHT (O&M) Division
 OPTCL, Puri