



ଓଡ଼ିଶା ବିଦ୍ୟୁତ ଶକ୍ତି ସଂଚାରଣ ନିଗମ ଲିଡ.
ODISHA POWER TRANSMISSION CORPORATION LIMITED
(A GOVERNMENT OF ODISHA UNDERTAKING)

CIN - U40102OR2004SGC007553

Office of the General Manager (Elect.), E.H.T. (O&M) Division, Balangir
At-Laltikra, P.O.-Rajendra College, Dist.- Balangir - 767002
E-mail ID:- ehtm.div.bln@optcl.co.in

Letter No. 937

Dated 17/12/2024

TENDER CALL NOTICE NO.- 06/2024-25

Sealed Tenders in duplicate are invited from the undersigned from Electrical HT/Civil Contractor(Class-D & above) with work experience in any HV/EHV S/S (33KV & Above) having Valid PAN card, G.S.T certificate for "Construction of Cable trench/Earth pit Slab, 33KV SI structure foundation, BMK foundation and Grating of Transformer oil sump pit at 132/33KV Grid S/S Balangir Old".

Sl	Description of works	UNIT	QUANTITY
A. Grating of Transformer oil Sump pit			
1	Cutting, bending, binding, fitting, fixing & placing in position of steel rods including cost of binding wire with supply of all size rod(TATA, RINL/SAIL)	KG	658.80
2	Supplying , fitting, fabrication, cutting ,drilling and placing MS bar and MS angle complete as per drawing and technical specification, including cost of all materials, labours, T&P required etc. complete.	KG	148.95
3	Painting two coats of enamel Paints over one coat of primer to the iron surfaces, including cost of all materials, labours, T&P required etc. complete.	sqmtr	75.00
B. 33KV SI Structure Foundation at Dunguripali Bay			
1	Breaking of PCC (1.7*1.1*0.75)	CUM	0.14
2	Excavation of Earth (1.7*1.1*1.25)	CUM	2.3375
3	Sand Spreading (1.7*1.1*0.1)	CUM	0.187
4	PCC of 1:3:6 (1.7*1.1*0.1)	CUM	0.187
5	RCC of 1:1.5:3 (1.7*1.1*1.25)	CUM	2.3375
6(a)	32Nos of 12mm rod of length 1.1mtr & 20Nos of 12mm rod of length 1.7mm		
(b)	Supplying ,fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification, including cost of all materials, labours, T&P required etc. complete.	Kg	61.588
7	fitting and placing GI nut and bolt complete of structure as per drawing and technical specification, including cost of all materials, labours, T&P required etc. complete. (supplying cost is excluded so 33 % cost is considered)	Kg	500
C. S/Y BMK base foundation work			
1	Breaking of Existing Foundation ((1.25*1.25*0.48)*5)	CUM	3.75
2	Excavation of Earth ((1.25*1.25*0.24)*5)	CUM	1.875
3	Sand spreading ((1.25*1.25*0.1)*5)	CUM	0.78

4	PCC of 1:3:6 ((1.25*1.25*0.1)*5)	CUM	0.78
5	RCC of 1:1.5:3 ((1.25*1.25*0.5)*5)	CUM	3.9
6(a)	120Nos of 12mm rod of length 1.25mtr	KG	133.5
(b)	Supplying ,fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification, including cost of all materials, labours, T&P required etc. complete.		
D. RCC Cable trench slabs & Earth pit Slabs at 132/33KV Grid S/S, Bolangir			
1	Foundation and reinforcement: Supply of all materials, goods quality planks, ballas, shuttering plates for centering, shuttering, supply of good quality 20 mm amd 10 mm machine broken granite chips, good quality river sand and concreting, curing for foundation of columns, equipment structures, transformer and cable trench slabs etc as per IS:4156 including cost of taxes, royalties, lead lift, Labour and T&P.		
	As per above specification with ratio of concrete (1:1.5:3) with the cost of cement and without steel	CUM	14.7275
2	Supplying ,fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification, including cost of all materials, labours, T&P required etc. complete.	Kg	1275.27
3	Replacement of old damaged slabs with the new slabs:- Lifting and bringing the old damaged slabs from the cable trenches to the desired site as per the instruction of Engineer in charge and bringing the new slabs, putting in proper position over the cable trenches (within 100m) (Total cum in Sl. no.1 x 2)	CUM	29.455

The tender document can be made available in the office of the undersigned on payment of requisite amount of **Rs. 4,720/-** (Rupees four thousand seven hundred twenty) only non-refundable (including GST @18%) towards cost of tender document by Bank draft drawn in favour of G.M, E.H.T. (O&M) Circle, OPTCL, Bolangir, payable at Bolangir. **No other mode of payment is acceptable.**

The bidder has to deposit an amount of **Rs. 5272/-** (Rupees Five thousand two hundred seventy two) only as EMD in shape of Demand draft in favour of G.M. (EL), E.H.T. (O&M) Circle, OPTCL, Balangir, payable at Balangir.


The bid will be opened in presence of Tenderers or their authorised representatives possessing original authorisation letter. Incomplete tender shall be rejected.

Period & Time of Sale of Tender paper : **From Dt.- 19.12.2024 to Dt. 07.01.2025**
(During Office Hours 10:00 AM to 05:30 PM)

Last date & time of receipt of tender paper : **Dt.- 08.01.2025 up to 01.30 PM.**

Date & Time of Opening : **Dt:- 08.01.2025 at 04.00 PM.**

If the last date of receipt/opening of Tender falls on a Holiday, then the tender paper will be received/ opened in the next working days. The undersigned reserves the right to accept or reject any or all tenders without assigning any reason thereof.


General Manager (EL.)
EHT (O&M) Division, Balangir