



**ଓଡ଼ିଶା ଶକ୍ତି ସଂଚାରଣ ନିଗମ ଲିଡ.**

**ODISHA POWER TRANSMISSION CORPORATION LIMITED**

**(A Government of Odisha Undertaking)**

**EHT (O&M) DIVISION, BERHAMPUR**

**DUDUMA COLONY, DIGAPAHANDI ROAD, BERHAMPUR-760006**

Tel No.: 0680-2271587/ 9438907572

Mail Id: [ehm.div.bam@optcl.co.in](mailto:ehm.div.bam@optcl.co.in)

TENDER SPECIFICATION

ON

**N.I.T No : 09/2018-19**

For

**Internal Electrification of departmental I.B, OPTCL, Berhampur  
with supply of all fixtures & fittings.**

**Cost of tender paper Rs. 600/- + GST@12 % =Rs.672/-  
(Rupees Six hundred & Seventy-two only)**

**ISSUED TO:-**

.....  
.....  
.....  
.....  
.....  
.....

**Estimated Cost: Rs 1,28,950/-**



**ଓଡ଼ିଶା ବିଦ୍ୟୁତ୍ ଶକ୍ତି ସଂଚାରଣ ନିଗମ ଲି.ଃ.**  
**ODISHA POWER TRANSMISSION CORPORATION LIMITED**  
(A Government of Odisha Undertaking)  
E.H.T (O&M) DIVISION, BERHAMPUR  
AT- Duduma Colony, Digapahandi Road, Berhampur- 760 006  
Telephone: (0680)2271587/ 9438907572, E-mail:ehm.div.bam@optcl.co.in

---

**Notice Inviting Tender Advt. No: N.I.T No. 09/2018-19**

For and on behalf of OPTCL sealed tenders invited by the undersigned from interested Contractors having valid M.V Contract License along with PAN, GST certificate for “**Internal Electrification of departmental I.B, OPTCL, Berhampur with supply of all fixtures & fittings**”.

The tender document can be made available in the office of the undersigned on written request and payment of requisite amount towards cost of tender document by cash/Bank draft drawn in favour of Dy. General Manager, EHT (O & M) Division, Berhampur payable at Berhampur, Odisha. Those who wants to receive tender paper over post are required to deposit additional amount of Rs 100/- (Rupees one hundred). The undersigned will not be held responsible for any postal delay.

The bid must be accompanied with an amount Rs **1,290/-** as EMD in shape of DD/Cash drawn in favour of Dy. General Manager, EHT(O & M) Division, Berhampur payable at Berhampur, Odisha. The tender documents will be opened in the office of the undersigned in the presence of the Bidders (or) their Authorized Representatives present if any on 03.01.2019. If the last date of receipt opening of Tender falls in holiday, then the Tender paper will be Received /opened in the next working days.

**Date of Sale of Tender Paper:** From 20.12.2018 to 02.01.2019 (Office Hours)  
**Last Date of receipt of Tender Paper:** 03.01.2019 up to 01.00 PM.  
**Date of Opening of Tender Paper:** 03.01.2019 at 03.00 PM.  
Tender should be dropped in **Tender BOX-1.**

The authority reserves all rights to reject any, all or part of the Tender, alter/modify the requirement/ delete any part of the tender without assigning any reason thereof. For details please visit our web site: [www.optcl.co.in](http://www.optcl.co.in). Corrigendum if any will be published in the web site only.

**Dy. General Manager**  
**EHT (O & M) Division**  
**Berhampur**

**TENDER SPECIFICATION FOR N.I.T No: 09/2018-19**

**INDEX**

1.	SECTION – I	Instruction to Bidders
2.	SECTION – II	General terms & condition.
3.	SECTION – III	Technical Specification
4.	ANNEXURE – I	Schedule of Price
5.	ANNEXURE – II	Detail data sheet to be furnished by the tenderer.
6.	ANNEXURE – III	No Relationship Certificate
7.	COST OF TENDER PAPER (Non-refundable)	Rs. 600/- + GST @12% = Rs.672/- (Rupees Six hundred & Seventy-two only) by Cash/ Bank Draft drawn in favour of Dy. General Manager, EHT(O & M) Division, Berhampur payable at Berhampur, Odisha.
8.	E.M.D	Rs <b>1,290/-</b> only by cash / bank draft drawn in favour of Dy. General Manager, EHT (O & M) Division, Berhampur payable at Berhampur, Odisha.
9.	SALE OF TENDER PAPER	From <b>20.12.2018</b> to <b>Dt. 02.01.2019</b> . (During office hours) available in the office of the Dy. General Manager (Ele.), EHT(O&M) Division, OPTCL, Berhampur.
10	LAST DATE OF RECEIPT OF TENDER PAPER	<b>Dt. 03.01.2019 up to 1.00 PM.</b>
11	DATE & TIME OF OPENING OF TENDER	<b>Dt. 03.01.2019 at 3.00 P.M &amp; &amp; should be dropped in Tender Box –1.</b>
12	Tender posted by the registered post to should be reached at:	<b>Odisha Power Transmission Corporation Ltd., Office of the Dy. General Manager, EHT (O &amp; M) Division, Duduma Colony, Digaphandi Road, Berhampur-700 006, Odisha</b>

INSTRUCTION TO BIDDERS

The Bidders must read in detail the “Instruction to Bidders” and “General terms and conditions” before filling the tender documents.

**1. TENDERS:**

- A) Only those who have purchased the Tender specification from this office can submit their Tender. Tenders submitted by other mean will be rejected. Bidders must submit their bids with original signature.
- B) Tender must be submitted in sealed cover subscribed as “**N.I.T No:09/2018-19: Internal Electrification of departmental I.B, OPTCL, Berhampur with supply of all fixtures & fittings** and addressed to the Dy. General Manager, EHT (O & M) Division, Berhampur.
- C) Tender shall be submitted either in person or by registered post. The authority is not responsible for receipt of tender after due date due to postal delay or any other reasons and tenders received after due date due to postal delay or any other reason will not be considered. The tenderer who wants to receive the tender paper by post have to deposit additional Rs 100.00 (Rupees One hundred) along with the tender paper cost. Detailed postal address with PIN No., Phone / Fax/Email of bidder must be mentioned in the application requesting for tender document.
- D) The bidder is to deposit EMD @ **Rs 1,290** /- in shape of cash / bank draft drawn in favour of Dy. General Manager, EHT (O & M) Division, Berhampur. The tender without EMD will be liable for rejection. The D.D / original money receipt for the EMD should be enclosed along with original tender paper. The EMD of successful tenderers will be refunded only after deposit of security-cum-performance deposit. The EMD of all unsuccessful tenderers shall be refunded on written request after finalization of tender. No interest shall be paid on EMD. No adjustment towards EMD shall be permitted against outstanding amount, if any, remained with the OPTCL.

**2. Experience:**

The bidders are required to submit the list of his past experience if any regarding similar work done along with the supporting documents.

**3. FORFEITURE OF EMD:**

- A) In the event the successful tenderer fails to carry out the works / partly carry out the works as per the technical specification the EMD so deposited shall be forfeited.
- B) Any deviation from the terms and conditions of the contract the EMD so deposited shall be forfeited without any notice.
- C) The EMD not claimed within a period of **one year** from the date of issue of this order & the Security deposit not claimed for refund within **three years** after completion of contract, will be forfeited. Hence you are requested to claim the EMD & the Security deposit within the scheduled period.

**4. INFORMATION ON COMPETITORS:**

Bidders have right to know information on competitors only at the time of opening of the bids. No further information on competitors shall be provided at any other point / stage of the tender without prejudice to Right to Information Act – 2005.

**5. OPENING OF TENDERS:**

A) Copy of M.V Contract License, PAN card, GST certificate should be enclosed with the tender bids.

B) Bidders themselves or their authorized representatives limited to one person only (possessing authorization letter in original) will be allowed to attend opening event of the tenders.

6. Orders may also be split up among more than one tenderer, if necessary. The undersigned reserves the right to reject the lowest or any other Tender or all tenders without assigning any reason what so ever.

7. The bidders are advised to inspect the site before assessing their rate to be quoted in tender. The evaluation will be made as per statutory applicable taxes, if not specified by the bidders. Tender should be prepared clearly and without any overwriting and corrections. Erasures and other changes shall bear the dated initial of the person signing the Tender.

8. In the event of discrepancy or arithmetical error in the schedule of price, the decision of the purchaser shall be final and binding on the tenderer. For evaluation, the price mentioned in words shall be taken if there is any difference in figure and word in the price bid.

**Dy. General Manager**

**GENERAL TERMS AND CONDITIONS**

1. **a. Scope of Works** : The detailed scope of work is appended at Section-III.  
**b. Validity**: Tenderers are requested to keep the validity of their offer for a period of 03months from the date of opening of tender.
2. **Price**: The bidders are advised to quote their rate as per the price schedule at Annexure – I. The unit rate and the total amount should be entered in figures and words. In case of any difference between figure and words in the price schedule, the price mentioned in words should be taken into consideration for evaluation.
3. **Completion of Work**: The work should be completed in full shape within **30**days from the date of award of the contract. If the work could not be completed within scheduled date due to any valid reason, then completion period may be extended on written request by the Bidder. If the work is not commenced & completed within the stipulated period, then the penalty should be imposed as per clause No.04 of SECTION-II.
4. **Penalty**: Penalty @ ½% (half per cent) per week up to a maximum of 5% of the total value of the work order will be imposed and recovered from dues admissible if the work is not completed within the scheduled period.
5. **Security Deposit**: The tenderers whose offer qualifies for acceptance will be awarded Work Order and the contractor shall have to be deposit Security-cum-performance guarantee equal to 10% (Ten percent) of contract value in shape of Cash / Bank Draft in favour of **Dy. General Manager, EHT (O&M) Division, Berhampur**. The Security deposit will be released along with due bill payment on completion of work. No interest shall be paid to the contractor towards the security deposit so deposited by the contractor.
6. **Additional Performance security**: Additional performance security shall be obtained from the bidder when the bid amount is less than the estimate cost put to tender. In such event the only the successful bidder who has quoted less bid price/rates than the estimate cost put to tender shall have to furnish the exact amount of differential cost i.e. estimate cost put to tender minus the quoted amount as Additional Performance Security in Shape of Cash/Demand Draft/Term Deposit Receipt pledge in favour of **Dy. General Manager, EHT(O&M) Division, Berhampur within seven days**, otherwise the bid will be cancelled & security deposit shall be forfeited.
7. **Terms of Payment**: 100% payment will be paid by the paying officer after completion of work and due verification reports (JMC) thereof by the consignee and approval of the competent authority. The bills in triplicate should be submitted to the paying through concerned Consignee.

8. **Verifying Officer:** - SDO, TLS, Berhampur is the verifying officer for the contract.
9. **Paying Officer:** The **DGM, EHT (O&M) Division, Berhampur** is the paying officer for this contract.
10. **Agreement:** The successful contractor shall have to enter into an agreement (F-2) with the concerned Engineer-in-charge in the approved contract agreement form within 10 days of receipt of work order.
11. **Force Majure:** The Contractor shall not be liable for any penalty for delay or for failure to perform the Contract for reasons of FORCE MAJURE, such as acts of God; acts of public enemy, acts of Govt, fires, floods, epidemics, quarantine restrictions, strike, freight, embargoes provided that the contractor shall within 10 days from the beginning of such delay notify to OPTCL in writing of the cause of delay. The OPTCL shall verify the facts and grant such extensions as facts justified.
12. **Safety Measures:** Only trained & experienced person should engage to carry out the work under direct supervision of engineer-in-charge, OPTCL & firm's supervisor. The work should be carried out on full risk & cost of contractor & OPTCL will not be responsible for any kind of risk coverage arising during execution of work.
13. **WORKMEN'S COMPENSATION:** The contractor shall be fully responsible for paying compensation if any, under the Workmen Compensation Act on account of workmen deployed by him.
14. **Rejection of works:** In the event of any of the materials supplied / work done by the contractor is found defective in materials or workmanship or otherwise not in conformity with the requirement of this contract, specifications, the OPTCL shall either reject the materials or work and request the Contractor to rectify the same. The Contractor on receipt of such notice, rectify or replace the defective materials and rectify the work free of cost. If the Contractor fails to do so the OPTCL may -
1. At its option rectify such work and recover the extra cost so involve from the Contractor.
  2. Terminate the contract for balance work / supplies with enforcement of penalty as per contract.
  3. All costs and damages for which the Contractor is liable to the authority will be deducted from him, under the contract.
15. **Jurisdiction of Court:** Suits if any, arising against the work order to be issued to the contractor shall be filed by either party in any court of law to which the jurisdiction of Court of Berhampur extends.

The Authority reserves the right to reject the notice/ award the contract among any responsive bidders against this tender or without assigning any reason thereof. All other terms and conditions will be governed by OPTCL as per Rules.

**Dy. General Manager**

**SECTION-III****SCOPE OF THE WORK:**

Sl. No.	Description of Items	Unit	Qty
1	Recessed wiring to Light point/Fan point/Exhaust fan point/Call bell point with 1.5 Sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked with 20 mm dia non-metallic PVC flexible conduit with 6Amp, 250V Modular switch ISI marked and ceiling rose ISI marked mounted on metal Box having front modular cover of suitable size , metal box with 1.5sq.mm FR PVC insulated single core multi-strand copper conductor as earth wire including all accessories and connection (Make of wire -Finolex/ L&T/ Anchor/ Havells/ V-Guard/ Great White)		
(a)	-do- Group A	Point	12
(b)	-do- Group B	Point	10
(c)	-do- Group C	Point	14
2	Recessed wiring to Fan Point in		
(a)	-do- Group B	Point	3
3	Recessed wiring to Exhaust Fan Point in		
(c)	-do- Group C	Point	2
4	Recessed wiring to 5 Amp/6 Amp Socket Outlet with 2 X 1.5 Sq mm FR PVC Insulated single core multi stranded copper conductor of ISI marked in recessed 20 mm dia in non-metallic PVC box and the earthing point with 1 X 1.5 Sq.mm FR PVC Insulated single core multi stranded copper conductor for loop earthing etc. As required (make of wire-Finolex/ L&T/Anchor/Havells/V-Guard/Great White)	Each	12
5	Supply and fixing of Modular metal box on surface or in recess with suitable size of Modular cover in front including providing and fixing of 6pin 16Amp socket outlet and 16Amp Modular switches connection (make-Finolex/ L&T/ Anchor/ Havells/ V-Guard/ Great white).	Each	5
6	Recessed sub main wiring along with earth wire with the following size of PVC insulated single core multi strand copper conductor ISI marked confirming to IS-694/1990 in 20 mm dia non-metallic heavy duty flexible conduit 1.6 mm in surface by recessed PVC conduit as required.(Make of wire-Finolex/ L&T/ Anchor/ Havells/ V-Guard/ Great White)	Per mtr	
a	2x1.5sqmm + 1x1.0sqmm (1.8.2)	Per mtr	40
b	2x2.5sqmm + 1x1.5sqmm (1.8.2)	Per mtr	70
c	2x4sqmm + 1x1.5sqmm (1.8.3)	Per mtr	90
d	2x6sqmm + 1x2.5sqmm (1.8.4)	Per mtr	25
e	2x10sqmm + 1x4sqmm (1.8.5)	Per mtr	5
7	Supply and fixing Earthing with G.I earth pipe 3 mtr. long 40mm dia ISI marked including accessories and providing masonry enclosures with cover plate having locking arrangement and watering pipe etc. with charcoal and salt as required	Each	
	a) Standard earthing as per Govt. specification	Nos.	1



	b) Extra GI Flat (25 X 5mm)	Mtr.	16
8	Supply, installation , testing and commissioning of main switches(IS 13940 part-3/1993) following capacity on existing surface/wall mounting and completer with HRC fuse links, interconnections, earthing (Make-Siemens/Anchor/L&T/Havel/C&S/ RK)		
	a) 63Amp ICTPN main switches on MS angle frame	Each	1
9	Supply and fixing of bus bar with suitable sheet metal enclosure on MS angle frame with proper grouting on wall including all connections		
	a)100Amp TPN bus bar -300 X 32 X 3mm size	Each	1
10	Supply and fixing of 5Amp to 32Amp rating 240V “B” series MCB suitable for lighting and other loads of the following poles in the exiting MCB DB ISI marked complete with connections testing and commissioning etc.	Each	
	a) Single pole(SP) (Make-Siemens/Legrand/L&T/Havel/C&S)	Nos.	4
	b) 40Amp DP MCB (Make-Siemens/Legrand/L&T/Havel/C&S)	Nos.	2
11	Supply and fixing of following way single pole and neutral sheet steel MCB distribution board 250V on surface/recess complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, detachable gland plate, interconnections, phosptized and powder painted including earthing etc. as required (But without MCB/ RCCB/ Isolator)	Each	
	a) 4Way double door	Each	2
	b) 2Way Single door	Each	1
12	Supply and fixing of Exhaust fan 300mm size	Each	2
13	Supply and fixing of Modular metal box of following size (nominal size) on surface/Recess with suitable size of Modular cover in front including cutting the wall and making good the same in case of recessed conduit as required(Modular box + cover + fixing + Labour ccess)	Each	
	a) 2 Module	Nos.	6
	b) 3 Module	Nos.	5
14	S/F of 16/18 SWG metal box of following sizes (Nominal size) in recess with suitable size of phenolic laminated sheet cover in front including cutting the wall and making good the same in case of recessed conduit as required. 100mmx100mmx60mm deep	Each	6
15	S/F of 16/18 SWG metal box of following sizes (Nominal size) in recess with suitable size of phenolic laminated sheet cover in front including cutting the wall and making good the same in case of recessed conduit as required. 150mmx100mmx60mm deep	Each	5
16	Supply and fixing of modular fan regulator (Cona/ C&S/ Legrand)	Nos.	3
17	S/F of 1200mm High speed Ceiling fan, Heavy Duty, durable, copper winding, Aluminium blade(ISI mark) Crompton Grave/ Khaitan/ Orient/ Polycab/ Bajaj	Each	3
18	Supply and fixing of Ceiling rose	Nos.	30
19	S/F Angle Holder/Batten Holder	Nos.	10

20	S/F of Electronic 9 watt LED Bulb	Each	10
21	Supply and fixing of 32Amp FT/DP switch (Make-Cona/Anchor)	Each	4
22	S/F of Bed Light	Each	2
23	Supply of PVC Aluminium armoured cables ISI marked. (Make- Glowstar/ Polycab/ Nicco/ KEI/ Havelles)	Mtrs.	
	(a)25sq.mm 3-1/2 core	Mtrs.	17
24	Cable laying on wall surface with steel saddled	Mtrs.	17
27	S/F of 5KVA voltage stabiliser (CG/Shakti/V-guard/Autotac) (I/p-130V to 270V, O/P-220V to 240V)	Each	1

**Dy. General Manager**

**Schedule of Price**

Sl. No.	Description of Items	Unit	Qty	Unit Rate	Unit Rate in word
1	Recessed wiring to Light point/Fan point/Exhaust fan point/Call bell point with 1.5 Sq.mm FR PVC insulated single core multi strand copper conductor of ISI marked with 20 mm dia non-metallic PVC flexible conduit with 6Amp, 250V Modular switch ISI marked and ceiling rose ISI marked mounted on metal Box having front modular cover of suitable size , metal box with 1.5sq.mm FR PVC insulated single core multi-strand copper conductor as earth wire including all accessories and connection (Make of wire -Finolex/L&T/Anchor/Havells/V-Guard/Great White)				
(a)	-do- Group A	Point	12		
(b)	-do- Group B	Point	10		
(c)	-do- Group C	Point	14		
2	Recessed wiring to Fan Point in				
(a)	-do- Group B	Point	3		
3	Recessed wiring to Exhaust Fan Point in				
(c)	-do- Group C	Point	2		
4	Recessed wiring to 5 Amp/6 Amp Socket Outlet with 2 X 1.5 Sqmm FR PVC Insulated single core multi stranded copper conductor of ISI marked in recessed 20 mm dia in non-metallic PVC box and the earthing point with 1 X 1.5 Sq.mm FR PVC Insulated single core multi stranded copper conductor for loop earthing etc. As required (make of wire- Finolex/L&T/Anchor/Havells/V-Guard/Great White)	Each	12		
5	Supply and fixing of Modular metal box on surface or in recess with suitable size of Modular cover in front including providing and fixing of 6pin 16Amp socket outlet and 16Amp Modular switches connection (make- Finolex/L&T/Anchor/Havells/V-Guard/ Great white).	Each	5		

6	Recessed sub main wiring along with earth wire with the following size of PVC insulated single core multi strand copper conductor ISI marked confirming to IS-694/1990 in 20 mm dia non-metallic heavy duty flexible conduit 1.6 mm in surface by recessed PVC conduit as required.(Make of wire-Finolex/L&T/Anchor/Havells/V-Guard/Great White)	Per mtr			
a	2x1.5sqmm + 1x1.0sqmm (1.8.2)	Per mtr	40		
b	2x2.5sqmm + 1x1.5sqmm (1.8.2)	Per mtr	70		
c	2x4sqmm + 1x1.5sqmm (1.8.3)	Per mtr	90		
d	2x6sqmm + 1x2.5sqmm (1.8.4)	Per mtr	25		
e	2x10sqmm + 1x4sqmm (1.8.5)	Per mtr	5		
7	Supply and fixing Earthing with G.I earth pipe 3 mtr. long 40mm dia ISI marked including accessories and providing masonry enclosures with cover plate having locking arrangement and watering pipe etc. with charcoal and salt as required	Each			
	a) Standard earthing as per Govt. specification	Nos.	1		
	b) Extra GI Flat (25 X 5mm)	Mtr.	16		
8	Supply, installation , testing and commissioning of main switches(IS 13940 part-3/1993) following capacity on existing surface/wall mounting and completer with HRC fuse links, interconnections, earthing(Make-Siemens/Anchor/L&T/Havel/C&S/ RK)	Each			
	a) 63Amp ICTPN main switches on MS angle frame	Each	1		
9	Supply and fixing of bus bar with suitable sheet metal enclosure on MS angle frame with proper grouting on wall including all connections				
	a)100Amp TPN bus bar -300 X 32 X 3mm size	Each	1		

10	Supply and fixing of 5Amp to 32Amp rating 240V “B” series MCB suitable for lighting and other loads of the following poles in the exiting MCB DB ISI marked complete with connections testing and commissioning etc.	Each			
	a) Single pole(SP)	Nos.	4		
	b) 40Amp DP MCB	Nos.	2		
11	Supply and fixing of following way single pole and neutral sheet steel MCB distribution board 250V on surface/recess complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, detachable gland plate, interconnections, phosphitized and powder painted including earthing etc. as required (But without MCB/RCCB/Isolator)	Each			
	a) 4Way double door	Each	2		
	b) 2Way Single door	Each	1		
12	Supply and fixing of Exhaust fan 300mm size	Each	2		
13	Supply and fixing of Modular metal box of following size (nominal size) on surface/Recess with suitable size of Modular cover in front including cutting the wall and making good the same in case of recessed conduit as required(Modular box + cover + fixing + Labour cess)	Each			
	a) 2 Module	Nos.	6		
	b) 3 Module	Nos.	5		
14	S/F of 16/18 SWG metal box of following sizes (Nominal size) in recess with suitable size of phenolic laminated sheet cover in front including cutting the wall and making good the same in case of recessed conduit as required. 100mmx100mmx60mm deep	Each	6		
15	S/F of 16/18 SWG metal box of following sizes (Nominal size) in recess with suitable size of phenolic laminated sheet cover in front including cutting the wall and making good the same in case of recessed conduit as required. 150mmx100mmx60mm deep	Each	5		
16	Supply and fixing of modular fan regulator (Cona/ C&S/ Legrand/ Anchor	Nos.	3		
17	S/F of 1200mm High speed Ceiling fan, Heavy Duty, durable, copper winding, Aluminium blade(ISI mark) Crompton Grave/ Khaitan/ Orient/ Polycab/ Bajaj	Each	3		

18	Supply and fixing of Ceiling rose	Nos.	30		
19	S/F Angle Holder/Batten Holder	Nos.	10		
20	S/F of Electronic 9 watt LED Bulb	Each	10		
21	Supply and fixing of 32Amp FT/DP switch (Make-Cona/Anchor/ Havelles)	Each	4		
22	S/F of Bed Light	Each	2		
23	Supply of PVC Aluminium armoured cables ISI marked. (Make- Glowstar/ Polycab/ Nicco/ KEI )	Mtrs.			
	(a)25sq.mm 3-1/2 core	Mtrs.	17		
24	Cable laying on wall surface with steel shaddle	Mtrs.	17		
27	S/F of 5KVA voltage stabiliser (CG/Shakti/V-guard/Autotac) (I/p-130V to 270V, O/P-220V to 240V)	Each	1		
28	<b><i>GST on above item @ _____ extra</i></b>				

**Date:**  
**Place:**

Signature of tenderer  
with seal

**Dy. General Manager**

**Annexure –II**

**DETAILED DATA SHEET TO BE FURNISHED BY THE TENDERERS**

1	Name of the Agency/Contractor with detailed postal address.	
2	Earnest money deposited vide <b>Bank Draft No./ money receipt No</b> _____ date _____ amount in Rs. _____ (Rupees _____ )only	
3	Attested copy of Valid MV Contract License	Furnished / Not furnished
4	Attested copy of valid GST certificate	Furnished / Not furnished
5	Attested copy of PAN card	Furnished / Not furnished
6	Submitted No relationship Certificate	Furnished / Not furnished
7	Agreed to furnish Contract security deposit	Yes / No
8	Agreed to accept payment terms as per the tender specification	Yes / No
9	Agreed to adhere to completion of work as per the tender specification	Yes / No
10	Agreed to accept penalty clause as per the tender	Yes / No
11	Attach past experience certificate for similar job in OSEB/ GRIDCO/ OPTCL or any other agencies	Yes / No
12	Agreed to keep validity of the offer 3month from the date of tender opening without any variation in tender clause.	Yes / No

**Date**

**Signature of the Tenderer  
with seal**

N.B: Please tick mark the furnished one & strikeout the other.

**NO RELATION CERTIFICATE**

This is to Certify that, I/ We \_\_\_\_\_  
have no relationship with any of the employee in the rank of Asst. Manager and above  
serving under EHT(O&M), Division, OPTCL, Berhampur. In case the above  
statement is found to be false, I/We may be debarred from any payment due on  
account of this contract.

**Signature of the Tenderer  
with seal.**