



ଓଡ଼ିଶା ବିଦ୍ୟୁତ ଶକ୍ତି ସଂଚାରଣ ନିଗମ ଲିଃ.

ODISHA POWER TRANSMISSION CORPORATION LTD.

(A Government of ODISHA Under Taking)

OFFICE OF THE DY. GENERAL MANAGER (ELECT.)

EHT (O&M) DIVISION, Lapanga, AT/PO: Lapanga,

DIST: SAMBALPUR (ODISHA), PIN-768212, Email-ehm.div.lpnga@optcl.co.in

CIN:U40102OR2004SGC007553

TENDER CALL NOTICE NO. LPNGA/07/2026-27


The Dy. General Manager (Elect.), E.H.T. (O&M) Division, Lapanga invites sealed Tenders from Contractors having valid Electrical license (MV/HT) along with PAN, GST Registration certificate for providing **Servicing, testing, preventive maintenance, and repair/replacement of Air Circuit Breakers (ACBs), Moulded Case Circuit Breakers (MCCBs), and associated LT switchgear installed at 400/220/132/33 kV Grid Sub-Station, Lapanga.**

The tender specification can be obtained from the office of The D.G.M., E.H.T. (O&M) Division, Lapanga on payment of Rs. **600/- (Six Hundred only) + GST @ 18% (Non-Refundable)** in shape of Cash/Bank Draft in favor of EHT (O&M) Circle, OPTCL, BURLA payable at Union Bank of India, MAIN ROAD BURLA Branch, Sambalpur on any working day from 10:30 AM to 04:00PM (during office hours) from **Dt. 20.08.2026 to Dt. 02.09.2026**. In case the Bank Draft made in any other nationalized bank payable at any clearing branch at BURLA/Sambalpur will be allowed, but the bidders have to deposit the collection fee (Bank transaction fee) along with the paper cost. The collection fee & Paper cost is non refundable. Additional amount of Rs.100/- (One Hundred only) may be paid extra for postal delivery of the tender specification. The undersigned shall not be held responsible for any postal delay.

The Tender shall be received Up to 01.00 PM of dated 03.09.2026 & will be opened at 03.30 PM of same day in the office of the undersigned in the presence of the Bidders (or) their Authorized Representatives present if any. If any of the above date happens to be a holiday, the next working day will be the corresponding effective date. One Tender paper shall be issued to one Bidder. E.M.D @ 1% of the estimated value should be deposited in shape of Demand Draft / Cash in favour of EHT (O&M) CIRCLE, OPTCL, BURLA payable at Union Bank of India, MAIN ROAD BURLA Branch, Sambalpur Odisha, India along with Self Attested Copy of PAN, HT/MV License and GST Registration Certificate failing which the tender will be liable for rejection.

- Date of Sale of Tender Paper: Dt. **20/08/2026** to Dt.**02/09/2026** up to 5.00 PM (During Office Hours)
- Last Date of Receipt of Tender Paper: Dt. 03/09/2026 up to 05:00 PM
- Date of Opening of Price Bids: Dt.03/09/2026 at 03:30PM
- Cost of Tender Paper: Rs.600/-+ GST@18% = **Rs. 708** /- (Non-Refundable)
- E.M.D @ 1% of the estimated value = **Rs. 1428** /- (Rounded)
- The bidder should write the **“Tender Call Notice No., Name of the work & Date of Opening of the tender on the body of the Sealed Envelope”**.
- The undersigned reserves the right to accept or reject all tenders without assigning any reason thereof. For details please visit our web site: www.optcl.co.in. Corrigendum if any will be published in the web site only.

N.B:- Tender Paper must be purchased from this office only within stipulated period. No other mode like downloaded paper from website will be accepted.


Deputy General Manager (Elect.)
EHT (O&M) Division, Lapanga

SECTION-IV

SCOPE OF WORK & PRICE SCHEDULE

Name of Work


Servicing, testing, preventive maintenance, and repair/replacement of Air Circuit Breakers (ACBs), Moulded Case Circuit Breakers (MCCBs), and associated LT switchgear installed at 400/220/132/33 kV Grid Sub-Station, Lapanga under EHT (O&M) Division, Lapanga under E.H.T. (O&M) Division, Lapanga.

SCOPE OF WORK

The scope of work comprises the following:

SI No	Description	Qty (in Nos)
1	Opening front covers and back covers of LT Power Control Panels, cleaning dust from switches, MCCBs and associated components inside the panel using compressed air, checking all electrical contacts, terminals, cable terminations and busbar joints, applying CRC contact cleaner, tightening all terminals/connections as required, refixing doors and covers after testing the proper functioning of switches, ACBs and MCCBs, complete in all respects.	3
2	Drawing out, dismantling, servicing, overhauling and testing of Air Circuit Breakers (ACBs), including opening of covers, cleaning with compressed air, checking spring charging assembly, operating mechanism, locking section, auxiliary contacts and current-carrying contacts, cleaning electrical contacts with CRC, greasing moving mechanical parts, carrying out necessary repair/replacement of minor defective components, reassembly and commissioning for proper operation of the Circuit Breakers complete as required. (630A ACB – 02 Nos., 800A ACB – 03 Nos., 1600A ACB – 03 Nos.; Total – 08 Nos.)	8
3	Supply and fixing of 250A, 36kA, 3-Pole MCCB (Model No. DU250) complete as required.	1
4	Supply and fixing of Under Voltage Release (UVR) Coil for DU Series MCCB complete as required.	1

The contractor shall arrange all required skilled and unskilled manpower, supervision, tools & plants, testing instruments, compressed air equipment, consumables, safety equipment and other incidental materials necessary for successful execution of the work. The work shall be carried out under approved Permit to Work (PTW)/Line Clearance (LC) and in accordance with OPTCL safety regulations and the instructions of the Engineer-in-Charge.


Dy. General Manager (Elect.)
EHT (O&M) Division, Lapanga