



ଓଡ଼ିଶା ବିଦ୍ୟୁତ ଶକ୍ତି ସଂଚାରଣ ନିଗମ ଲିଡ.

ODISHA POWER TRANSMISSION CORPORATION LTD.

(A Government of ODISHA Under Taking)

OFFICE OF THE DY. GENERAL MANAGER (ELECT.)

EHT (O&M) DIVISION, Lapanga, AT/PO: Lapanga,

DIST: SAMBALPUR (ODISHA), PIN-768212, Email-ehm.div.lpnga@optcl.co.in

CIN:U40102OR2004SGC007553

TENDER CALL NOTICE NO. LPNGA/05/2026-27

The Dy. General Manager (Elect.), E.H.T. (O&M) Division, Lapanga invites sealed Tenders from Contractors having valid Electrical license (HT/EHT) along with PAN, GST Registration certificate for providing **Replacement of Existing 9 Nos. 220 kV and 3 Nos. 400 kV Porcelain Surge Arresters with Polymer Surge Arresters for ICT-1 and Auto Transformers-I & II at 400/220/132/33 kV Grid Sub-Station, Lapanga under E.H.T. (O&M) Division, Lapanga.**

The tender specification can be obtained from the office of The D.G.M., E.H.T. (O&M) Division, Lapanga on payment of Rs. **600/- (Six Hundred only) + GST @ 18% (Non-Refundable)** in shape of Cash/Bank Draft in favor of EHT (O&M) Circle, OPTCL, BURLA payable at Union Bank of India, MAIN ROAD BURLA Branch, Sambalpur on any working day from 10:30 AM to 04:00PM (during office hours) from **Dt. 31.07.2026 to Dt. 09.08.2026**. In case the Bank Draft made in any other nationalized bank payable at any clearing branch at BURLA/Sambalpur will be allowed, but the bidders have to deposit the collection fee (Bank transaction fee) along with the paper cost. The collection fee & Paper cost is non refundable. Additional amount of Rs.100/- (One Hundred only) may be paid extra for postal delivery of the tender specification. The undersigned shall not be held responsible for any postal delay.

The Tender shall be received Up to 01.00 PM of dated 10.08.2026 & will be opened at 03.30 PM of same day in the office of the undersigned in the presence of the Bidders (or) their Authorized Representatives present if any. If any of the above date happens to be a holiday, the next working day will be the corresponding effective date. One Tender paper shall be issued to one Bidder. E.M.D @ 1% of the estimated value should be deposited in shape of Demand Draft / Cash in favour of EHT (O&M) Circle, OPTCL, BURLA payable at Union Bank of India, MAIN ROAD BURLA Branch, Sambalpur Odisha, India along with Self Attested Copy of PAN, HT/EHT License and GST Registration Certificate failing which the tender will be liable for rejection.

- Date of Sale of Tender Paper: Dt. **31/07/2026** to Dt. **09/08/2026** up to 5.00 PM (During Office Hours)
- Last Date of Receipt of Tender Paper: Dt. 09/08/2026 up to 05:00 PM
- Date of Opening of Price Bids: Dt. 10/08/2026 at 03:30PM
- Cost of Tender Paper: Rs.600/- + GST@18% = **Rs. 708 /-** (Non-Refundable)
- E.M.D @ 1% of the estimated value = **Rs. 1585/-** (Rounded)
- The bidder should write the **"Tender Call Notice No., Name of the work & Date of Opening of the tender on the body of the Sealed Envelope"**.
- The undersigned reserves the right to accept or reject all tenders without assigning any reason thereof. For details please visit our web site: www.optcl.co.in. Corrigendum if any will be published in the web site only.

N.B:- Tender Paper must be purchased from this office only within stipulated period. No other mode like downloaded paper from website will be accepted.

J. R. G. Majhi
21/07/2026
Deputy General Manager (Elect.)
EHT (O&M) Division, Lapanga

SECTION-IV

SCOPE OF WORK & PRICE SCHEDULE

Name of Work

Replacement of Existing 9 Nos. 220 kV and 3 Nos. 400 kV Porcelain Surge Arresters with Polymer Surge Arresters for ICT-1 and Auto Transformers-I & II at 400/220/132/33 kV Grid Sub-Station, Lapanga under E.H.T. (O&M) Division, Lapanga.

SCOPE OF WORK

The scope of work comprises dismantling of the existing 03 Nos. 400 kV porcelain surge arresters installed at ICT-1 and 09 Nos. 220 kV porcelain surge arresters installed at Auto Transformers-I & II, transportation of the dismantled materials to the designated Site Store, erection of 03 Nos. 400 kV and 09 Nos. 220 kV polymer-housed surge arresters supplied by OPTCL at their respective locations, and carrying out 33 metres of Twin Moose AAAC/ACSR jumpering using conductors, clamps and connectors supplied by OPTCL.

The contractor shall provide all required skilled and unskilled labour, supervision, tools & plants, lifting tackles, cranes (if required), consumables and safety equipment for proper execution of the work. The work shall include handling, transportation within the switchyard, alignment, tightening of all mechanical and electrical connections, restoration of all jumper connections, and completion of the work in all respects as per the instructions of the Engineer-in-Charge.

All dismantled materials shall be transported to the designated Site Store and stacked properly. The work shall be executed under approved shutdowns/Line Clearances (LC) while ensuring compliance with OPTCL safety regulations and maintaining the required electrical clearances.

Sl. No.	Description of Work	Unit	Qty
1	400 kV Surge Arresters		
a	Dismantling of existing 400 kV porcelain Surge Arresters including transportation to Site Store.	Nos	3
	Transportation from Site Store, erection of 400 kV polymer-housed Surge Arresters including all electrical and mechanical connections.	Nos	3
2	220 kV Surge Arresters		
a	Dismantling of existing 220 kV porcelain Surge Arresters including transportation to Site Store.	Nos	9
b	Transportation from Site Store, erection of 220 kV polymer-housed Surge Arresters including all electrical and mechanical connections.	Nos	9
3	Twin Moose Jumpering		
a	Twin Moose AAAC/ACSR jumpering to Surge Arresters using OPTCL-supplied conductor, clamps and connectors.	Mtr	33